



**US Army Corps
of Engineers**

Alaska District

Final Interim Feasibility Report
Environmental Assessment and
Finding of No Significant Impact

Navigation Improvements Diomedede, Alaska



June 2014
EA Revised September 2014



**DEPARTMENT OF THE ARMY
U.S. ARMY ENGINEER DISTRICT, ALASKA
P.O. BOX 6898
JBER, ALASKA 99506-0898**

**NAVIGATION IMPROVEMENTS
DIOMEDE, ALASKA**

Final Interim Feasibility Report

June 2014

EXECUTIVE SUMMARY

Little Diomed Island is at the center of the Bering Strait, an extremely remote community of 115 people that rely almost entirely upon a subsistence way of life. The community is perhaps the least accessible in the United States, based on its location, the time, cost, and difficulty/uncertainty associated with travel to and from the island, and the island's severe physical attributes. The problem of concern at Diomed is restricted navigation related to harsh physical and environmental conditions, which result in a reduced quality of life, life/safety issues, and lack of access to subsistence activities.

This report documents a detailed study of these problems and alternative solutions utilizing criteria of Remote and Subsistence Harbors as defined in the Water Resources Development Act of 2007, Section 2006. This report recommends construction of breakwaters that would provide protection from predominantly northerly waves to make launching and retrieval of subsistence vessels safer and help improve the overall quality of life. The recommended plan would require 78,400 cubic yards of associated rock with a small near-shore area dredged to -10 feet, requiring removal of 3,000 cubic yards of material at a project first cost of \$28,960,000. The constructed project would support safe subsistence opportunities and provide much needed protection for navigation access.

The recommended project does not have net positive National Economic Development benefits; however, the remote and subsistence intent and specialness of the study authority is being fully relied on for justification. Although the range of total benefits is between \$6.2 million and \$7.4 million, equating a benefit to cost ratio range of 0.18 to 0.26, a cost effectiveness and incremental cost analysis was performed that substantiates the best investment in accordance with Section 2006 criteria.

Non-Federal Sponsor support for implementation of the project includes the City of Diomed and the Native Village of Diomed, with financial assistance from Kawerak, Inc. the current cost sharing Sponsor for the study effort.

CONTENTS

1.0 INTRODUCTION	1
1.1 Study Authority	1
1.2 Scope of Study	2
1.3 Study Location/Congressional District	2
1.4 Related Reports and Studies	3
1.5 Non-Federal Sponsor	4
2.0 DESCRIPTION OF STUDY AREA	5
2.1 Project Area	5
2.2 Access	5
2.2.1 Navigation	6
2.2.2 Aviation	7
2.3 Economics	8
2.4 Physical Environment	11
2.4.1 Climate	11
2.4.2 Winds	11
2.4.3 Ice Conditions	11
2.4.4 Tides and Storm Surge	11
2.4.5 Wave Climate	11
2.4.6 Currents	12
2.4.7 Bathymetry	12
2.4.8 Rivers and Creeks	12
2.4.9 Geology	12
2.4.10 Biological Resources	12
2.4.11 Archaeological and Historical Resources	14
3.0 PLANNING CRITERIA	15
3.1 Problem Statement	15
3.1.1 National Objectives	15
3.1.2 Study Objectives	15
3.1.3 Study Constraints	15
3.2 National Evaluation Criteria	16
3.3 Study Specific Evaluation Criteria	16
3.3.1 Base Year and Period of Analysis	16
3.3.2 Engineering Criteria	16
3.3.3 Economic Criteria	17
3.3.4 Environmental Criteria	18
4.0 WITHOUT-PROJECT CONDITIONS	19
4.1 Potential Future Scenarios	19
4.1.1 Future Demand for Moorage	19
4.1.2 Future of Commercial Fleet	19
4.1.3 Summary of Without-Project Condition	20
5.0 ALTERNATIVE FORMULATION	21
5.1 Project Site Selection	21
5.2 Initial Measures Screening	21
5.3 Description of Alternatives	22
5.3.1 No Action Alternative	22
5.3.2 Alternative N1 – North of Helipad	22
5.3.3 Alternative S1 – South of Helipad	25
5.3.4 Alternative S2 – South of Helipad with Hooked Breakwater	27
5.3.5 Alternative S3 – South of Helipad with Boat Storage Area	29
5.3.6 Environmental Considerations of Alternatives	31
5.3.7 Dredge Material Disposal Alternatives	32

6.0 EVALUATION OF ALTERNATIVES	33
6.1 Cost of Alternatives.....	33
6.2 Benefits of Alternatives.....	34
7.0 COMPARISON AND SELECTION OF PLANS	39
7.1 Comparison of Plans.....	39
7.1.1 Comparison of Costs	39
7.1.2 Comparison of Benefits	39
7.2 Selection of Plan	39
7.2.1 Identification of Recommended Plan	40
7.2.2 Four Accounts Evaluation	46
8.0 RECOMMENDED PLAN	48
8.1 Plan Components.....	48
8.1.1 Basin	48
8.1.2 Breakwaters	48
8.1.3 Dredged Material Disposal and Dredged Material Maintenance Plan	49
8.1.4 Local Service Facilities	49
8.2 Plan Benefits and Accomplishment.....	49
8.3 Plan Costs	51
9.0 PUBLIC AND AGENCY INVOLVEMENT	54
9.1 Public Involvement	54
9.2 Agency Coordination.....	54
9.3 Status of Environmental Compliance.....	55
9.4 Views of the Sponsor.....	56
10.0 CONCLUSIONS AND RECOMMENDATIONS	57
10.1 Conclusions	57
10.2 Consistency with the Environmental Operating Principles	57
10.3 Corps of Engineers Campaign Plan.....	58
10.4 Recommendations	59

FIGURES

<i>Figure 1. Location and vicinity map</i>	2
<i>Figure 2. Number of activities in which one or more of a subsistence resource species were targeted by Diomedes hunters by month.</i>	8
<i>Figure 3. Alternative N1</i>	24
<i>Figure 4. Alternative S1</i>	26
<i>Figure 5. Alternative S2</i>	28
<i>Figure 6. Alternative S3</i>	30
<i>Figure 7. Incremental Analysis Cost Graphic</i>	46
<i>Figure 8. Alternative S3</i>	48
<i>Figure 9 Typical Cross-section of Southern Breakwater LSF</i>	52

TABLES

<i>Table 1. Walrus harvests at Diomedes: 1989 to 2011</i>	10
<i>Table 2. Tidal Parameters – Tin City</i>	11
<i>Table 3. Sea Level Rise Prediction for a 50-Year Project Life.</i>	19
<i>Table 4. Without Project Conditions, Key Factors</i>	20
<i>Table 5. Fleet Characteristics</i>	22
<i>Table 6. Project First Costs</i>	33
<i>Table 7. Periodic Maintenance and Repair Costs</i>	33

<i>Table 8. Total Cost of Alternatives</i>	34
<i>Table 9. Wave Heights by Month and Direction at Diomedes, AK</i>	36
<i>Table 10. Wave Heights by Month and Direction at Diomedes, Alaska</i>	37
<i>Table 11. Benefit/Cost Evaluation by Alternative</i>	38
<i>Table 12. Additional Launch Days Available (waves less than 3.3 feet)</i>	42
<i>Table 13. Criteria for Little Diomedes CE/ICA</i>	44
<i>Table 14. Output and Cost of Alternatives</i>	45
<i>Table 15. Alternative Plans with Incremental Cost per SVD</i>	45
<i>Table 16. Four Accounts Evaluation for Little Diomedes Navigation Improvement</i>	47
<i>Table 17. Cost Apportionment (1 Oct 2014 price level)</i>	53
<i>Table 18. Status of Environmental Compliance.</i>	55

APPENDICES

- Appendix A: Summary of Without Project Conditions and Impacts to Diomedes
- Appendix B: Economic Value of Subsistence Activity, Little Diomedes, Alaska
- Appendix C: Engineering Appendix
- Appendix D: Value Engineering Final Report
- Appendix E: Cost Engineering Appendix
- Appendix F: Real Estate Plan & Assessment of Non-federal Sponsor’s Real Estate Acquisition Capability

This Page Has Been Left Blank Intentionally

1.0 INTRODUCTION

1.1 Study Authority

The authority for this General Investigation study is provided by the “Rivers and Harbors in Alaska” study resolution adopted by the U.S. House of Representatives Committee on Public Works on December 2, 1970, which reads in part:

“Resolved by the committee on public works of the House of Representatives, United States, that the Board of Engineers for Rivers and Harbors is hereby requested to review the reports of the Chief of Engineers on rivers and harbors in Alaska, published as House document numbered 414, 83rd Congress, 2nd session... and other pertinent reports, with a view to determine whether any modifications of the recommendations contained therein are advisable at the present time.”

and the Water Resources Development Act (WRDA) of 2007, Section 2006. Remote and Subsistence Harbors

(a) In General- In conducting a study of harbor and navigation improvements, the Secretary may recommend a project without the need to demonstrate that the project is justified solely by national economic development benefits if the Secretary determines that—

(1)(A) the community to be served by the project is at least 70 miles from the nearest surface accessible commercial port and has no direct rail or highway link to another community served by a surface accessible port or harbor; or

(B) the project would be located in the State of Hawaii, the Commonwealth of Puerto Rico, Guam, the Commonwealth of the Northern Mariana Islands, the United States Virgin Islands, or American Samoa;

(2) the harbor is economically critical such that over 80 percent of the goods transported through the harbor would be consumed within the community served by the harbor and navigation improvement; and

(3) the long-term viability of the community would be threatened without the harbor and navigation improvement.

(b) Justification- In considering whether to recommend a project under subsection (a), the Secretary shall consider the benefits of the project to—

(1) public health and safety of the local community, including access to facilities designed to protect public health and safety;

(2) access to natural resources for subsistence purposes;

(3) local and regional economic opportunities;

(4) welfare of the local population; and

(5) social and cultural value to the community.

1.2 Scope of Study

This report documents the study to investigate the feasibility of navigation improvements at Little Diomedede, Alaska. The study was conducted and the report prepared in accordance with goals and procedures for water resources planning as contained in Engineer Regulation (ER) 1105-2-100 and the project authorization. Alternatives were examined for their feasibility, considering engineering, economic, environmental, and other criteria. A determination of Federal interest, in accordance with present laws and policies, is also included. An environmental assessment was prepared for this project as an attached document.

1.3 Study Location/Congressional District

Little Diomedede Island is at the center of the Bering Strait that separates the Bering Sea from the Chukchi Sea (Figure 1). The island is about 685 miles northwest of Anchorage, 135 miles northwest of Nome, and only 2.5 miles east of Big Diomedede Island in Russia. The International Date Line passes between Big and Little Diomedede Islands.

The study area is in the Alaska Congressional District. The Congressional delegation is composed of:

Senator Lisa Murkowski (R)

Senator Mark Begich (D)

Representative Don Young (R)




Figure 1. Location and vicinity map

1.4 Related Reports and Studies

There have been several studies and reports as follows:

Diomedes Day School Protection. The Alaska District, U.S. Army Corps of Engineers prepared this report in December 1978 at the request of the Bureau of Indian Affairs (BIA). The request was for a study of wave conditions at the BIA Day School and provision of a design and specifications for a structure to protect the school from storm waves.

Navigational Improvements Reconnaissance Report. The Alaska District, U.S. Army Corps of Engineers prepared this report in May 1982 at the request of the City of Diomedes. The report concluded that navigation improvements could be economically justified and recommended feasibility level studies.

Navigational Improvements Reconnaissance Report. The Alaska District, U.S. Army Corps of Engineers prepared this report in June 1990 at the request of the Alaska Department of Transportation and Public Facilities. The report concluded that a solution to the navigation needs of Little Diomedes was possible and that the Federal government had an interest in working toward that solution.

Seabird Use at Proposed Quarry Sites Little Diomedes Island, Alaska. The U.S. Fish and Wildlife Service Migratory Bird Management Project completed this report in 1991. Three potential quarry sites (talus, beach boulder, and cliff) were investigated. It was determined that if rock were to be removed from any of the potential quarries, that doing so from the cliff quarry would pose the smallest threat to birds.

Little Diomedes Navigation Improvement Project Final Coordination Act Report. The U.S. Fish and Wildlife Service prepared this report in 1992. The report contains recommendations for further study and mitigation options for construction.

Navigational Improvement Technical Report. The Alaska District, U.S. Army Corps of Engineers prepared this report in February 1994 at the request of the Alaska Department of Transportation and Public Facilities. The report concluded that navigation improvements could not be economically justified at that time. This finding was based in part on a change in the operations and equipment of the barge company servicing the island, reducing the cost of annual freight delivery to the island and thereby reducing the benefits that could be claimed for harbor construction. (Subsequently, the annual barge delivery was suspended and currently no commercial company will provide this service except as a special charter. The cost of the special charter is very expensive and is undertaken infrequently.)

Little Diomedes Inland Seawater Intake Feasibility Report. Peratrovich, Nottingham & Drage, Inc. prepared this report for VECO Polar Resources in September 2002. The report investigated the feasibility of installing a seawater intake structure in Diomedes. Of particular interest to this navigation improvements study, a total of seven geotechnical test holes were drilled in the area to the north of the local helipad.

Section 905(b) (WRDA 86) Analysis Navigation Improvements, Little Diomed, Alaska. The Alaska District, U.S. Army Corps of Engineers prepared this report in April 2003 in response to Congressional direction included in Conference Report 106-988 for Fiscal Year 2001 Appropriations, Public Law 106-377. This report concluded that navigation improvements could be economically justified and recommended feasibility level studies.

1.5 Non-Federal Sponsor

The non-Federal Sponsor for the Feasibility Phase is Kawerak, Inc. The non-Federal Sponsors for implementation of the project are expected to be the City of Diomed and the Native Village of Diomed/Kawerak, Inc, the Norton Sound Economic Development Corporation, and the State of Alaska. The City of Diomed is a municipal entity whereas the Native Village of Diomed is a tribal entity. Both have agreed to be co-sponsors for implementation of the project. The City of Diomed has the legal capability to take real estate adversely, and presently manages the existing infrastructure within the community, so the City of Diomed will obtain the real estate for the constructed project and manage it for the life of the improvement. The Native Village of Diomed is a federally recognized tribe with access to funds provided for the benefit of tribes for transportation functions (including marine infrastructure.) The Native Village of Diomed has formed a compact with Kawerak, Inc. (a not-for-profit service corporation providing services to federally-recognized tribes in the Nome census area) to manage the transportation program for Diomed. This compact is a legally binding agency agreement that is common for Alaska Native Tribes in the Bering Strait Region. Through this compact, Kawerak acts as the agent for the Native Village of Diomed for their transportation program. Kawerak, as the agent for the Native Village of Diomed, has provided a letter of sponsorship and financial capability on behalf of the Native Village of Diomed. The City of Diomed has provided a signed certificate of real estate capability as the land owner for the project.

Other potential sources of funding include the Norton Sound Economic Development Corporation, which provides funds for community development, especially the coastal communities in this area. The State of Alaska also provides funding and oversight for design and construction of marine infrastructure projects throughout the State, and primarily works through city governments.

The minimum make-up of the joint non-Federal Sponsor will be the City of Diomed (lands and operation) and the Native Village of Diomed and Kawerak, Inc. (funding and accounting).

2.0 DESCRIPTION OF STUDY AREA

2.1 Project Area

The community of Inalik, commonly known as Diomedes or Little Diomedes, is a traditional Eskimo village of approximately 120 people located on the western shore of Little Diomedes (locally known as Ignaluk) Island, Alaska. Residents of Little Diomedes rely almost entirely upon a subsistence way of life, harvesting fish and crab, hunting whales, walrus, seals, and polar bears. Little Diomedes and its companion island, Big Diomedes, lie at the center of the Bering Strait, separating the Bering Sea from the Chukchi Sea and Russia from the United States (Figure 1). The community is 2.5 miles from Big Diomedes, which belongs to Russia; 0.6 mile from Russian waters and airspace; 27 miles from the Alaskan mainland; and about 685 air miles northwest of Anchorage.

Diomedes is an extremely remote community, perhaps the least accessible in the United States, based on its location, the time, cost, and difficulty/uncertainty associated with travel to and from the island, and the severe physical attributes of Little Diomedes Island.

Little Diomedes Island rises abruptly from the sea at a 40-degree angle to a height of nearly 1,300 feet and is characterized by steep slopes littered with substantial amounts of rock and boulders. The community's location is the only area that does not have near-vertical cliffs to the water. The island is 2-1/8 miles long and 1-7/8 miles wide, encompassing only 2.8 square miles. Little or no soil covers the side slopes of the island, and many areas are barren of vegetation. The vegetation that does exist is alpine tundra composed of salmonberry, moss, greens, and some roots. The shoreline consists of large rock and boulders with no semblance of a beach.

2.2 Access

The small size and steep topography of Little Diomedes Island makes constructing a year-round runway prohibitive. Diomedes currently has limited accessibility. Conditions permitting, a temporary airstrip is established annually on a stable section of sea ice between the two islands. Hence, year-round access to Diomedes is currently limited to helicopter. Diomedes possesses a helipad and, conditions permitting, receives mail once a week via helicopter when not accessible by plane. Seasonal conditions permitting access to Diomedes by boat during open water and plane during periods of stable sea ice are also possible.

Emergency medical service can be provided by the Alaska National Guard stationed in Nome, or other commercial sources, weather permitting. However, delays or failures to respond to medical emergencies occur every year and, in some cases, have resulted in fatalities. Travel to and from Diomedes for business and/or pleasure is restricted by the concern over irregular transportation availability. Visitors to Diomedes have been stranded in the community for long periods of time, sometimes 2 or more weeks. Likewise, Diomedes residents have been unable to return home and are forced to reside with relatives or friends since bush communities typically do not have commercial lodging or dining facilities.

2.2.1 Navigation

Few navigation improvements have been built at Diomed. There are no improved landing ramps, areas of protected moorage, or protected storage areas along the beach. Boats must be launched and retrieved directly from the shoreline, which consists of large rocks and boulders with little to no suitable landing areas. Some boulders have been placed in the near shore to the south of the helipad to form two small jetty-like structures extending a short distance perpendicular from the beach (Photo 1). The area between these two can serve as a crude launching area but only safely under the calmest of conditions due to the confined space between them and presence of boulders. Winds are typically 20 to 30 mph, with sustained winds of 60 to 80 mph common. In addition to wind generated waves, Diomed is also susceptible to long period swells. Because of the rocky beach and wave climate, landing any sort of vessel at Diomed is a risky venture. Barges delivering fuel and goods must either lighter goods to shore using small skiffs or construct a rudimentary landing from material available locally. The size of the vessels utilized by Diomed residents is limited to those sizes that can be manually hauled out of the water and stored high enough above the beach to avoid damage from waves. A crude ramp was constructed of material available from the beach and near shore in the summer of 2011 to support a school reconstruction project. This ramp required constant upkeep during the duration of the construction project to remain operational.

Located in the middle of the Bering Strait (see Figure 1), the island is nearly a full day's travel by boat to Wales, the nearest community with regular air transportation service. The Bering Strait is frequently rough and windy, making travel to and from the island in 18- to 20-foot open aluminum skiffs a hazardous undertaking, and several lives have been lost in these crossings. Because of the hazardous landing conditions at Diomed, local shipping companies have discontinued regular freight delivery service. Small freight shipments are received through the weekly helicopter service or, for a limited time during the freeze-up, by plane; however, larger items must wait for a sufficiently large accumulation to justify the expense of barge delivery. Typically this delivery interval is 2 or more years. Fuel oil is delivered once a year.



Photo 1. Aerial photo of Diomedede showing helipad and crude launch area

2.2.2 Aviation

A state-owned heliport (Photo 1) allows for weekly mail delivery. The mail helicopter carries four passengers or 1,300 pounds of small freight; however, mail has priority because the U.S. Postal Service (USPS) subsidizes this service. Bad weather and/or mechanical problems frequently disrupt service and several weeks often can pass between flights.

Conditions permitting, most commonly and recently occurring from February through April, a runway is constructed on the frozen ocean, and fixed wing aircraft are capable of transporting residents and visitors, mail, and small dry goods and supplies during this time. A shallow reef between Little and Big Diomedede Islands has historically facilitated the formation of solid ice between the two islands. More recently, though, the formation of solid ice has not been as reliable. Historically, the Bering Strait was frozen from mid-December to mid-June, but more recently, freeze-up has occurred as late as February and March. The 1982 reconnaissance report stated that fixed wing aircraft could land on the ice runway during the 5 months in which the ice between Little and Big Diomedede was frozen. Today, this runway is typically available for only 3 to 4 weeks. During the winter months of 2008 and 2009, the ice


was too thin to allow construction of the ice runway. Continuing climate change may result in this form of access being lost altogether.

2.3 Economics

Residents of Diomedede estimate that access to the ocean, given the current conditions, can only occur when waves are no greater than 2 feet. When waves are 2 feet or greater, the rocks, surges, and currents at the beach make conditions too dangerous to launch.

Because of its remote location and difficult conditions, Diomedede has had no scheduled freight deliveries for more than a decade. Occasional chartered freight deliveries come into the community for special situations, such as delivering materials for the community boardwalk. Diomedede residents acquire through subsistence a very large proportion of their food, both by necessity as well as cultural preference (Figure 2). Diomedede residents’ high level of dependence on subsistence foods for their very survival makes the community unique, even compared with other villages in the region.

Residents of the community have suggested that subsistence acquisition of foods could be increased by as much as 50 percent over current harvest levels if a project was completed that would allow the local boat fleet better access during periods of higher wave conditions¹.



Source: data from Tetra Tech, Inc. et. al. *Economic Value of Subsistence Activity, Little Diomedede, Alaska, December 2011.*

Figure 2. Number of activities in which one or more of a subsistence resource species were targeted by Diomedede hunters by month.

¹ Francis Ozenna, Diomedede IRA Council, personal communication, December 2011.

The U.S. Army Corps of Engineers completed an official survey of Diomedede residents in 2007 to gather information on the needs of the community. The following quotes are from the responses of Diomedede residents to a question asking about the impact “a protected harbor” in Diomedede would have on extending their subsistence harvests or extending the family’s subsistence activities². The phrase “protected harbor” is slightly different from the current proposed alternatives (which provide wave protection). However, we believe the effect is the same since the skiff fleet would not have remained on the water in either situation. The comments received included the following:

“Subsistence harder by year due to warming. Walrus moving in March. Used to be May.”
“20 percent more subsistence overall. Helpful in October and November when surf is harsh.”
“Yes, a protected small harbor facility would increase our subsistence harvest by lots.”
“Would extend the range of hunting.”
“Yes, a protected small harbor facility would increase our subsistence harvest by 50 percent.”
“Would make 5 more trips (per year).”
“Yes, would be able to purchase skiff – 10 to 12 trips per year.”
“Yes, a few more times a year. Protection from large swells when launching.”
“The harbor would help – boats wouldn’t have to be stored on land, larger boats.”
“Yes, 24 more hunting trips, currently 8 trips. 25 to 50 percent improvement”

The following points taken from the technical report prepared by Jim Richardson of ResourceEcon titled “Summary of Without Project Conditions and Impacts to Diomedede” provide some perspectives on greater marine access resulting in increased food production and resolving the shortage of food for the residents of Diomedede. The report is included in Appendix A.

- Diomedede residents prefer to harvest walrus that migrate past Diomedede. In the spring (May and June), females and sub-adults migrate northward through the Bering Strait. Depending on the weather and ice conditions, the period of successful hunting may be relatively short. In the fall (October and November), the reverse population migration occurs as the walrus head south to join up with the males working their way north from Bristol Bay. Again, the weather conditions dictate the potential for launching boats and safely returning in difficult wave environment at the Diomedede beach. Restricted ability for the Diomedede hunters to launch and return mean either lost opportunities and/or longer hunting trips that increase costs and risks. Table 1 shows the walrus harvests by Diomedede hunters for the period from 1989 to 2011. There is a very clear decline in the numbers harvested, particularly in recent years. We do not know the reasons for this sharp decline, but since walrus is a preferred species for food production, this trend represents restricted food opportunities for residents of Diomedede. It is likely that changing weather patterns have resulted in changed ice conditions during the periods that the walrus migrate past Diomedede Island. If that is the case, then expanding the ‘operating window’ for hunters to be able to get out, could mean a substantial increased opportunity for walrus harvests, particularly in the

² U.S. Corps of Engineers, Alaska Region. Household Interviews: Diomedede, conducted during the week of March 19 through March 23, 2007.

early spring and late fall – the time periods when migrating walrus are likely to be travelling through the area.

It is suggested that the known decline in harvests of walrus by Diomedes residents is symptomatic of the ocean access problems that could be partially addressed by one of the wave protection alternatives. Data for harvests of seals and other important subsistence species have not been collected in recent years, so trends in harvests of other species are not available.

Table 1. Walrus harvests at Diomedes: 1989 to 2011

Year	Total walrus reported as harvested
1989	1
1990	236
1991	532
1992	99
1993	91
1994	378
1995	197
1996	90
1997	152
1998	163
1999	131
2000	159
2001	57
2002	99
2003	64
2004	60
2005	15
2006	21
2007	51
2008	30
2009	46
2010	31
2011	8
Data source: U.S. Fish and Wildlife, Marine Mammals Management, Marking, Tagging, and Reporting, Program at http://alaska.fws.gov/fisheries/mmm/mtrp/mtrpmain.htm	

- We know that long-term food storage is difficult on Diomedes. Households use “ice pits” dug under their homes to preserve foods for long-term use since freezer use is not practical. The freshness and quality of subsistence foods consumed would be increased if addressing the ocean access for Diomedes hunters were enhanced throughout the season, but particularly during the early spring and late fall when walrus are migrating through the area.

- Aside from subsistence foods harvested directly for consumption by Diomedes residents, it is likely that increased ocean access would enable acquisition of food that could be traded to residents of nearby communities for food or other items not available at Diomedes.

2.4 Physical Environment

2.4.1 Climate

The climate at Little Diomedes is subarctic and dominated by the movements of weather systems and sea ice through the Bering Strait. The island receives about 10 inches of precipitation a year, with 30 inches of snow; fog is common. Temperatures average from -10 to 6 degrees F in the winter to 40 to 50 degrees F in summer.

2.4.2 Winds

Situated in the middle of the Bering Strait, Little Diomedes is subject to frequent wind, consistently blowing from the north. Winds are typically 20 to 30 mph, with sustained winds of 60 to 80 mph common.

2.4.3 Ice Conditions

The Bering Strait is generally frozen between mid-December and mid-June. Typically, the Bering Strait will freeze over entirely between Big and Little Diomedes Islands, while the waters elsewhere around the islands become covered with floe ice.

2.4.4 Tides and Storm Surge

Little Diomedes is in an area of semi-diurnal tides, with two high waters and two low waters each lunar day. Tidal parameters at Little Diomedes are similar to those at Tin City, which is 31 miles to the southeast on the Alaska mainland. The tidal parameters in Table 2 were determined using National Oceanic and Atmospheric Administration published data for Tin City. The Tin City tide data is based on observations made during September 2007. There was no reported highest observed water level and no lowest observed water level.

Little Diomedes is susceptible to low pressure events that could contribute to storm surge, but the water is too deep to allow the water to stack up and cause a significant surge. A rise in the water elevation due to surge has not been a problem reported at Little Diomedes.

Table 2. Tidal Parameters – Tin City

Parameter	Elevation (ft)
Mean Higher High Water (MHHW)	1.02
Mean Sea Level (MSL)	0.47
Mean Lower Low Water (MLLW)	0.00

2.4.5 Wave Climate

Because of its location, the rocky beach in Diomedes is unprotected from wind and waves and is vulnerable to waves from the north, south, and west. During open water months, waves

less than 2 feet in height occur only 2 to 3 days per month, the maximum wave height that allows residents to launch vessels.

The Coastal and Hydraulics Laboratory (CHL) of the Engineer Research and Development Center (ERDC) developed an Alaskan deep-water wave hindcast for the years 1985-2009 using hindcast generated wind data. This data was supplemented with selected storms from the early 1950's through 1984 for evaluation of the extreme wave condition to determine the 50-year return interval deep-water wave height of 27.5 feet. Waves from hindcast in the deep water off the coast of Little Diomedede were then transformed into the area of interest on Little Diomedede using the wave transformation model STWAVE, resulting in a design wave of 16.4 feet.

2.4.6 Currents

The dominant flow through the Bering Strait is to the north. The current velocity has been reported to vary between 1 and 3 knots. Flow at the surface is greatly influenced by winds. Flow to the north increases strongly with southerly winds and diminishes or completely reverses under the influence of northerly winds.

2.4.7 Bathymetry

Water depths have been determined within the project area, and surveys are included in the Engineering Appendix.

2.4.8 Rivers and Creeks

There are no notable surface water sources on Little Diomedede Island. Water for residents' personal use is drawn from a mountain spring and stored in a 434,000 steel tank, and families haul water from this source. The tank is filled for winter use, but the water supply typically runs out around March.

2.4.9 Geology

Little Diomedede Island is believed to be a Tuya type mountain (distinctive, flat-topped, steep-sided volcano formed when lava erupts through a thick glacier or ice sheet) and remains from the Bering land bridge. The slopes around the island of Little Diomedede are composed of loose boulders. These boulders can be unstable and result in slides. The boulders are also home to many species of birds.

2.4.10 Biological Resources

Terrestrial Habitat. The terrestrial habitat on Little Diomedede Island consists largely of boulder fields, cliffs, and rocky spires. Vegetation is limited to a very low mat of mosses, grasses, and forbs growing amongst the exposed boulders and rock outcroppings. Most boulders are heavily encrusted with lichens.

Birds. Nesting seabirds are the dominant animal life using the Little Diomedede terrestrial habitat. A total of 31 species of birds have been observed on or in the vicinity of Little Diomedede Island. The steep boulder-studded slopes, rocky cliffs, rich surrounding waters, and relatively low predator pressure at Little Diomedede Island create important breeding habitat for millions of seabirds, including auklets, kittiwakes, puffins, murre, and

cormorants. A number of additional species, such as the black guillemot, sandhill crane, and snowy owl may nest or be present on the island during various times of the year.

Mammals. Arctic fox is the only mammal known to regularly use the island's interior, and they are presumably present mostly in spring and summer, drawn by the abundance of eggs and ground-nesting birds.

Marine Habitat. Large boulders and cobbles characterize the shoreline, intertidal, and near-shore habitat. The formation and movement of sea-ice strongly affects this habitat and limits the colonization of rock faces as deep as 10 feet below the surface. Shoreline boulders and cobbles are subjected to ice-scouring and severe temperatures much of the year, which discourages multi-year growth. The intertidal zone at Little Diomede Island is very narrow and sparsely inhabited. Offshore, marine algae are able to grow amongst the boulders where they are sheltered against the worst of the local currents. At depths where the boulders are not subject to ice-scouring, they support dense growths of anemones and other epilithic organisms. As the distance from the shoreline increases, flat patches of sand or pulverized shell appear amongst the boulders, and broad areas of sand are present several hundred feet offshore. The concentration of nutrients and shallow depths within the Bering Strait provide unusually abundant, diverse, and accessible populations of marine invertebrates and fish for marine mammals to feed upon.

Marine Mammals. The Bering Strait provides the only passage for several marine mammal species that migrate between the Bering Sea and the Chukchi and Beaufort Seas. Some of these species are considered endangered or threatened, and are discussed further in the attached environmental assessment. Marine mammals occurring in the vicinity of Little Diomede include minke and beluga whales, Pacific walrus, and several seals, including the ringed, spotted, and bearded. Gray whales commonly occur in the vicinity throughout the spring, summer, and fall months. Little Diomede Island is a known haul-out area for concentrations of Pacific walrus.

Fish. Approximately 300 species of fish are found in the Bering Sea and may be expected around the Diomede Islands. These species include Pacific herring; Pacific, Arctic and saffron cod; and Pacific sand lance.

Threatened and Endangered Species and Critical Habitat. The polar bear was listed as threatened under the Endangered Species Act (ESA) on May 14, 2008. Polar bears occur in the vicinity of and have denned on Little Diomede Island. Critical habitat was designated for polar bears on November 24, 2010. At Diomede, critical habitat includes the island itself, a 1-mile "no disturbance zone" surrounding the island, as well as all sea ice, regardless of seasonal presence, out to the international border.

Several endangered species of whales under the jurisdiction of the National Marine Fisheries Service (NMFS) may occur in the waters around the island during certain seasons of the year. These include the bowhead, humpback, fin, and blue whales.

Bearded seals and ringed seals in the Arctic Ocean and adjacent Pacific Ocean waters (i.e., the Bering Sea) were listed by the NMFS as threatened under the ESA in December 2012.

These “ice seal” species are regarded to be at heightened risk from climate change and changes in sea ice formation and distribution patterns. Critical habitat designations by the NMFS for these species are pending (NMFS 2013b).

The endangered Steller sea lion might occasionally be found in the area, but haul-outs and rookeries are not documented on Little Diomedes Island, and no critical habitat areas are designated north of St. Lawrence Island, more than 100 miles to the south.

The USFWS listed the Pacific walrus as a candidate species under the ESA in February 2011. The status of candidate species under the ESA are reviewed annually, and the USFWS has until October 2017 to propose the Pacific walrus as either threatened or endangered, or to remove it from candidate status.

2.4.11 Archaeological and Historical Resources

Human use of Little Diomedes Island goes back several thousand years, and its location in the center of the Beringia region between Asia and North America suggests that it may have been occupied continuously by several successive cultures as a hunting and trading center. Cultural deposits, including middens, caches, and former dwelling sites, have been excavated within the village and are believed to be scattered through the general village area, reflecting its many centuries of occupation.

3.0 PLANNING CRITERIA

This section lays the foundation of what the study is investigating and what objectives are being used to measure study outcomes. Section 3.1 provides the problems and opportunities that exist for a project at Little Diomed. A summary of issues and concerns raised during the feasibility and NEPA scoping process are shown in Section 3.2. The planning objectives and constraints for this study are defined in Section 3.3.

3.1 Problem Statement

The problem of concern at Diomed is restricted navigation related to harsh physical and environmental conditions, which result in a reduced quality of life, life/safety issues, and lack of access to subsistence activities. Compounding this problem is the lack of aviation access.

3.1.1 National Objectives

The objectives of Federal water and land resources planning are to contribute to National Economic Development (NED) in a way that protects the nation's environment and increases the net value of goods and services provided to the economy of the United States as a whole, to contribute to National Ecosystem Restoration (NER) in a way that increases the net quantity and/or quality of ecosystem resources, and balance the net beneficial effects after considering all plan effects, beneficial and adverse, in the four Principle and Guidelines evaluation accounts: National Economic Development, Environmental Quality, Regional Economic Development, and Other Social Effects.

Navigation improvements at Diomed would have a combination of commercial and subsistence NED benefits. Diomed also meets the criteria of Section 2006 of the Water Resources Development Act (WRDA) of 2007 as detailed in Section 1.1 and may be approved without justification solely based upon NED benefits. Planning for the Little Diomed project is consistent with the NED objective and considers economic, social, environmental, and engineering factors.

3.1.2 Study Objectives

The desired alternative for Diomed would be one that meets the objective of providing reliable and safe marine access to the community to promote increased subsistence activities. It is anticipated that the project could be constructed in 2017 and this analysis considers a 50-year period of analysis.

3.1.3 Study Constraints

Constraints are statements about things you want to avoid doing, or things you cannot change, while meeting your objectives. Due the remoteness and physical characteristics of Little Diomed Island, physical construction of any project will pose challenges. Study constraints primarily involve the engineering, economic, and environmental criteria items that are discussed in the report sections that follow.

3.2 National Evaluation Criteria

Alternative plans should be formulated to address study objectives and adhere to study criteria. Each alternative plan shall be formulated in consideration of four criteria: completeness, efficiency, effectiveness, and acceptability.

- Completeness is the extent to which alternative plans provide and account for all necessary investments or other actions to ensure the realization of the planning objectives, including actions by other Federal and non-Federal entities.
- Effectiveness is the extent to which alternative plans contribute to achieve the planning objectives.
- Efficiency is the extent to which an alternative plan is the most cost-effective means of achieving the objectives.
- Acceptability is the extent to which alternative plans are acceptable in terms of applicable laws, regulations, and public policies. Mitigation of adverse effects shall be an integral component of each alternative plan.

3.3 Study Specific Evaluation Criteria

3.3.1 Base Year and Period of Analysis

The base year for this evaluation is 2017. This will allow sufficient time for more detailed engineering, obtaining financing, and finalizing any cooperative agreements necessary to implement this project. The project period of analysis is 50 years, so it runs through 2067. When constructed, the project could remain functional for longer than the 50-years, but the costs and benefits for this evaluation are limited to the 50-year timeframe.

3.3.2 Engineering Criteria

Alternative plans should be adequately sized to accommodate user needs and protection against wind-generated waves. Adequate depths and entry should provide for safe navigation. The plans must also be feasible from an engineering standpoint and capable of being economically constructed. Specific considerations for this study include:

- The Diomedes helipad has clearance requirements that alternatives will need to comply with. Proposing navigation improvements within the constraints will require coordination with the State of Alaska Department of Transportation & Public Facilities and the Federal Aviation Administration
- Any alternatives must be designed to withstand forces from the seasonal sea ice that forms in the project area
- A shallow shoal that causes turbulent water extends out perpendicular from the helipad. Approaches to any structures should not require transit in the vicinity of this shoal.
- Any proposed breakwaters must not extend too far from shore since the local bathymetry drops off quickly to deep water. Breakwater features that extend very far out from shore would do so into deep water and would be more expensive and difficult to construct.

- Potential locations for navigation improvements are limited to the current village location. There is no access to transport goods and supplies from any other portion of the island.
- There is limited space to house a construction crew in Diomedes. During recent construction to improve the school, the construction crew was housed in the school, including during periods of classes.
- Due to safety and environmental concerns, no construction material is available locally. Geology investigations confirm the unavailability.
- Seasonal sea ice constrains the shipping season for the importation of construction materials and equipment, and there are no offloading facilities other than the unimproved shore.
- Seasonal sea ice along with species specific environmental windows and subsistence activities would place restrictions upon permissible construction periods.
- There is very limited space available in Diomedes to serve as a staging area to store equipment or materials.

3.3.3 Economic Criteria

Principles and guidelines for Federal water resources planning require a plan to be identified that produces the greatest contribution to the NED plan. The NED plan is defined as the plan providing the greatest net benefits as determined by subtracting annual costs from annual benefits. Corps of Engineers' policy requires recommendation of the NED plan unless there is adequate justification to do otherwise. Selection of a locally preferred plan is allowed if the local sponsor either identifies a physical constraint that necessitates the selection of a plan smaller than the NED plan, or is willing to fully pay for the increment larger than the NED plan.

Alternatives considered should be presented in quantitative terms where possible. Benefits attributed to a plan must be expressed in terms of a time value of money and must exceed equivalent economic costs for the project. To be economically feasible each separate portion or purpose of the plan must provide benefits at least equal to the cost of that unit. The scope of development must be such that benefits exceed project costs to the maximum extent possible.

If a plan includes NER benefits, the analysis should include a cost effectiveness and incremental cost analysis. The cost effectiveness analysis determines if the plan is a "best buy" or provides the "best benefit for the buck." The incremental cost analysis determines if each additional increment of NER benefit is worth the additional increment of cost.

As mentioned in the specific study authority and elsewhere within this document, Section 2006 of the WRDA 2007 allows for the decision to recommend a project without the need to demonstrate that the project is justified solely by NED benefits. This determination is based on the elements stated in the authorization and frames the analysis that is presented.

3.3.4 Environmental Criteria

Current planning guidance specifies the Federal objective of water and land resources planning is to contribute to national economic development consistent with protecting the nation's environment, pursuant to national environmental statutes and applicable executive orders. Protecting the nation's environment is achieved when damage to the environment is eliminated or avoided.

4.0 WITHOUT-PROJECT CONDITIONS

The without-project condition provides a benchmark for comparison of the various navigations improvements considered.

4.1 Potential Future Scenarios

The Corps of Engineers requires that planning studies and engineering designs over the project life cycle, for both existing and proposed projects, consider alternatives that are formulated and evaluated for the entire range of possible future rates of sea-level change represented by three scenarios of “low,” “intermediate,” and “high” sea-level change. As detailed in the Hydraulic Appendix, the sea level rise predictions as listed in Table 3 were calculated at Little Diomed.

Table 3. Sea Level Rise Prediction for a 50-Year Project Life.

Risk	Low	Intermediate	High
Sea Level Rise (ft)	0.54	1.2	2.5

Sea level rise is unlikely to impact the future operation of the breakwater because it is designed to be an overtopping breakwater. The number of launch days would not change due to sea level rise; they would change if there was an increase or decrease in storminess, a change in sea ice conditions, or if animal migration patterns changed. As for other changes in climate, such as temperature increases or decreases and any resulting changes of ice cover; there will be no impacts on the future operation of the breakwater; although it may allow additional subsistence opportunities.

4.1.1 Future Demand for Moorage

The future without-project condition for Diomed does not include an increase in demand for moorage of vessels. Existing vessels are hauled out of the water across the rocky beach by hand after each use. There is very limited storage area for boats; usable flat land is a premium on the island.

4.1.2 Future of Commercial Fleet

The existing small boat fleet in Diomed is composed of aluminum outboard skiffs of various makes. Specific boat characteristics are listed as:

- 20-foot Star Trek Aluminum boat with an Evinrude 150 horsepower outboard
- 20-foot fiberglass boat with a 90 horsepower outboard
- 18-foot Ocean Pro aluminum boat with a Yamaha 70 horsepower outboard
- 16-foot Crestline aluminum boat with a Tohatsu 40 horsepower outboard
- 20-foot Bering Sea aluminum boat with a Tohatsu 40 horsepower motor
- Several smaller aluminum boats
- Two traditional skin boats

There are no projections of future increase in the commercial fleet of vessels for the residents of Diomedede. The existing fleet is primarily used for subsistence activities. The existing fleet is projected as representative of the future fleet.

4.1.3 Summary of Without-Project Condition

This section summarizes the major without-project conditions that have created, and continue to cause, negative impacts to the community and residents of Diomedede. Access to the offshore marine environment is probably the most critical requirement for continued existence of the community. Although this requirement is undisputed, there are no known future actions to be implemented by the Sponsor, Village, or State. Therefore for this project, there are no improvement projects under consideration, making the baseline and future without-project conditions similar. Diomedede is in an extremely difficult location to provide wave protection. Because of its remote location and difficult conditions, Diomedede has had no scheduled freight deliveries for more than a decade. Diomedede residents produce a very large proportion of their food both by necessity as well as cultural preference. Diomedede residents' high level of dependence on subsistence produced foods for their very survival makes the community unique, even compared with other villages in the region. Table 4 contains information on key aspects of the current project conditions at Diomedede and the outlook for the future. The information concerning subsistence days available to launch vessels is a key factor in comparing alternative plans. Further information can be found in a technical report titled "A Summary of Without Project Conditions and Impacts to Diomedede" compiled by Jim Richardson of ResourceEcon for the U.S. Army Corps of Engineers, Alaska District, dated May 2012, included in Appendix A.

Table 4. Without Project Conditions, Key Factors

Item	Trend	Discussion/information
Resident Population	Decline	178 in 1990 to 107 in 2011; steady decline over 20 yrs.
Subsistence – Walrus Harvest # Reported	Decline	Average is 118 annually over 23 yrs. Average over most recent 10 yrs is 42. Average most recent 5 yrs is 33.
Boat Damages	Steady	Fleet continues to sustain damages from being landed and hauled across rocks
Subsistence – Launch Days Available	Steady	50 available days to launch vessels safely on an annual basis.

5.0 ALTERNATIVE FORMULATION

5.1 Project Site Selection

Potential locations for navigation improvements are limited to the current village site. There are two options for the location of a rubble mound breakwater: north of the helipad or south of the helipad. Residents indicated that they preferred the breakwater to be located south of the helipad, where their current crude launch is. It was also observed during a site visit that a shoal exists off of the helipad. This shoal was observed to have a distinct current over it that would make an entrance channel dangerous if it was in the area of the fast current.

5.2 Initial Measures Screening

There are three basic methods of transporting people and goods: land based travel provided by roads and rail, air based travel provided by airplanes and helicopters, and water based travel provided by boats, barges, and other marine vessels. Since Little Diomed Island is 27 miles from mainland Alaska across open ocean, travel by land based means is not an economically viable option.

Currently, Diomed is served by a small helicopter and a small helipad at sea level. The Alaska Department of Transportation and Public Facilities has studied improved air travel by means of airplanes and a larger helicopter. Runways would have to be built offshore in deep water or on top of the island. Either location is cost prohibitive and is not a cost effective transportation method at this time. A larger helipad and larger helicopter would be costly, would not increase reliability, and would not help with the transportation of bulk goods and fuel.

Community relocation as an alternative was also deemed too costly based on extensive studies and estimates performed for village relocation for Shishmaref, Alaska, a community similar to Diomed and within the general region. Two specific reports on Shishmaref relocation, one covering the physical costs involving infrastructure and services and another covering cultural and social impact, were researched. Based on these sources and others, detailed studies for relocation were not performed specifically for Diomed; however, the estimated cost range was determined to be over \$1.5 million per person, equating to over \$200 million for the total village relocation.

This leaves improvements to water based transportation as the only potentially economically viable alternatives for study. Therefore, water-based transportation alternatives at Diomed will be evaluated.

Options considered for navigation improvements include off shore mooring systems, floating breakwaters, and rubble mound breakwaters. Analysis, as detailed in Appendix A, showed that only rubble mound breakwaters are suitable for consideration at Diomed. The use of a rubble mound breakwater to provide wave protection in an arctic environment that is susceptible to ice and severe wave action is a proven concept. Rubble mound breakwaters have been successfully used at Nome and Saint Paul, Alaska. Rubble mound revetments have been successfully used at

Kivalina and Shishmaref, Alaska, and a rubble mound revetment currently protects the Diomedé helipad.

5.3 Description of Alternatives

The characteristics of the fleet proposed to utilize the various navigation improvement alternatives are shown in Table 5. Proposed plans were laid out to accommodate vessels that need to access the shore at Little Diomedé.

Table 5. Fleet Characteristics

Vessel	Vessel Length [ft]	Design Beam [ft]	Design Draft [ft]
Subsistence boat	20	7.5	3
Rescue/Emergency boat	54	17	5.25

The design vessel utilized is established as the subsistence boat because the rescue vessel would only require occasional usage. Several project features are common to all the alternatives and include the following:

- All would provide a protected launch area, not a harbor providing moorage.
- Target protection would be for waves between 1.7 and 3.3 feet.
- Breakwaters would be periodically overtopped by large waves.

5.3.1 No Action Alternative

This alternative would leave the community without a safe place to launch or take out their boats or for rescue vessels to land. Vessels would continue to sustain damages as they try to launch and opportunities to subsistence hunt or fish would be lost. There would be no known opportunities for the cultural and subsistence activities of the present community to remain viable under the no action alternative.

5.3.2 Alternative N1 – North of Helipad

Alternatives on the north side of the helipad were not the locally preferred location because there was little room available to take out and store boats. Only one alternative was looked at north of the helipad, and it was designed to provide adequate take out area and boat storage.

This plan consists of two rubble mound breakwaters that would provide shelter from storms from the south and prevent shore side boulders from being transported into the landing area (Figure 3). The north breakwater was designed wider to provide a flat staging area for the community. A large area would be dredged and filled to provide an adequate take out area. The two breakwaters would require approximately 20,600 cubic yards of core rock, 24,400 cubic yards of B rock, and 28,600 cubic yards of armor stone.

This alternative would require a small near-shore area to be dredged to -10 feet Mean Lower Low Water (MLLW) to provide boats a rock free approach to shore and room to turn around

once launched. It is assumed that the dredging would include boulders and could possibly require blasting. Approximately 2,000 cubic yards would need to be removed for this alternative.

The breakwater was not designed to provide protection from storm waves; rather it was designed to make launching and retrieval safer in the average wave climate, not during storm events. Using the dominant southerly direction ($168.75^{\circ} - 191.25^{\circ}$), this breakwater configuration would reduce waves that are 8 seconds or less to 2.5/10 of the wave height at the boat launch area.




Figure 3. Alternative N1

5.3.3 Alternative S1 – South of Helipad

This plan consists of two rubble mound breakwaters that would provide shelter from storms from the north and prevent shore side boulders from being transported into the landing area (Figure 4). The south breakwater was widened at its base to try to provide an area for boat storage once the boats were removed from the water. The size of the armor stone took up the majority of space that could be used as a storage area. The two breakwaters would require approximately 12,600 cubic yards of core rock, 24,800 cubic yards of B rock, and 25,500 cubic yards of armor stone.

This alternative would require a small near-shore area to be dredged to -10 feet MLLW to provide boats a rock free approach to shore and room to turn around once launched. It is assumed that dredging would include boulders and could possibly need blasting. Approximately 3,000 cubic yards would need to be removed for this alternative.

The breakwater was not designed to provide protection from storm waves; rather it was designed to make launching and retrieval safer in the average wave climate, not during storm events. Using the dominant northerly wave direction ($348.75^{\circ} - 11.25^{\circ}$), this breakwater configuration would reduce waves of 8 seconds or less to 2.5/10 of the wave height at the boat launch area.




Figure 4. Alternative S1


5.3.4 Alternative S2 – South of Helipad with Hooked Breakwater

This plan consists of two rubble mound breakwaters. One breakwater is perpendicular to the shore and the other is hooked off the helipad (Figure 5). This alternative would provide shelter for waves from the north and give a little more protection from waves from the west than Alternative S3. This alternative would also prevent shore side boulders from being transported into the landing area. The two breakwaters would require approximately 23,400 cubic yards of core rock, 24,200 cubic yards of B rock, and 32,900 cubic yards of armor stone. This alternative provides no area to store boats taken from the water.

This alternative would require a small near-shore area to be dredged to -10 feet MLLW to provide boats a rock free approach to shore and room to turn around once launched. It is assumed that dredging would include boulders and could possibly need blasting. Approximately 3,000 cubic yards would need to be removed for this alternative.

The breakwater was not designed to provide protection from storm waves; rather it was designed to make launching and retrieval safer in the average wave climate, not during storm events. Using the dominant northerly wave direction ($348.75^{\circ} - 11.25^{\circ}$), this breakwater configuration would reduce waves of 8 seconds or less to 2/10 of the wave height at the boat launch area.



 ALASKA DISTRICT
CORPS OF ENGINEERS

LITTLE DIOMEDE
NAVIGATION IMPROVEMENT
LITTLE DIOMEDE, ALASKA

SCALE: Not to Scale
DATE: DEC 2011
DRAWN/DMG
ALTERNATIVE S2 DRAFT

Figure 5. Alternative S2

5.3.5 Alternative S3 – South of Helipad with Boat Storage Area


This plan consists of two rubble mound breakwaters that would provide shelter from northerly storms and prevent shore side boulders from being transported into the landing area (Figure 6). The south breakwater was designed wider compared with those in Alternatives S1 and S2 to provide a flat staging area for the community. The two breakwaters would require approximately 19,000 cubic yards of core rock, 23,100 cubic yards of B rock, and 36,400 cubic yards of armor stone.

This alternative would require a small near-shore area to be dredged to -10 feet MLLW to provide boats a rock free approach to shore and room to turn around once launched. It is assumed that dredging would include boulders and could possibly need blasting.

Approximately 2,500 cubic yards would need to be removed for this alternative.

The breakwater was not designed to provide protection from storm waves; rather it was designed to make launching and retrieval safer in the average wave climate, not during storm events. Using the dominant northerly wave direction ($348.75^{\circ} - 11.25^{\circ}$), this breakwater configuration would reduce waves of 8 seconds or less to 2.5/10 of the wave height at the boat launch area.



	ALASKA DISTRICT CORPS OF ENGINEERS
---	--

LITTLE DIOMEDE NAVIGATION IMPROVEMENT LITTLE DIOMEDE, ALASKA
--

SCALE: Not to Scale
DATE: DEC 2011
DRAWN/DMG
ALTERNATIVE S3 DRAFT

Figure 6. Alternative S3

5.3.6 Environmental Considerations of Alternatives

The Corps has been working with the USFWS on proposed navigation improvement projects at Diomedes for a number of years. Many of the concerns stated in their 1992 Fish and Wildlife Coordination Act Report, 2008 Planning Aid Letter, and recent correspondence (Boldenow 2012) are discussed in the attached environmental assessment. The 2008 Planning Aid Letter and recent coordination letters and emails are in Appendix 3, Correspondence. The 1992 Coordination Act Report is included in the Diomedes EA by reference, and relevant information from the 1992 report regarding biological resources, potential impacts, and recommendations are summarized in the EA. Specific recommendations from the above coordination include:

- Prohibiting construction or other activities that may potentially result in the taking of migratory birds between 1 May and 30 September
- Ensuring that any outdoor lighting used during construction minimizes the potential for disorienting birds and luring them into collisions with ships or equipment
- Requiring contractors to observe appropriate measures to avoid transporting rats and other invasive species to the island on project vessels, as promoted by State and Federal agencies
- Managing food waste and other possible attractants so as to not draw increased numbers of gulls, foxes or other seabird predators to the island
- Following polar bear interaction guidelines as promulgated in the USFWS ESA Coordination Letter dated July 2013

Mitigation during construction would include the observance of site-specific recommendations from the U.S. Fish and Wildlife Service (USFWS) and other resource agencies, to include selecting a construction timing window that poses the least risk of impact to sensitive resources such as bird nesting colonies.

Strict observance of the 1 May to 30 September no-construction period recommended by the USFWS may not be entirely feasible given the very limited working season at Little Diomedes. However, the Corps will continue to work with USFWS and other agencies to develop construction timing windows that protect wildlife but also allow the project to move forward. For both practical and environmental reasons, the Corps is studying the possibility of performing some construction work, such as dredging, during the winter. Some project tasks, such as the delivery of rock for the breakwaters, can only be done during the open-water season, which overlaps with the USFWS-recommended no-construction period.

Many of these concerns were developed with onshore construction in mind; through consultation with USFWS, risk to migratory bird habitat was minimized by utilizing offshore construction techniques versus the initial plan of land-based construction. Continued coordination of the construction activity will occur in the planning and engineering design phase.

5.3.7 Dredge Material Disposal Alternatives

Dredged material quantities are relatively small for the alternatives, ranging from 2,000 to 3,000 cubic yards and comprising boulders. For each alternative, boulder and rock debris would be incorporated into the breakwater structures as fill material to the extent practicable. An evaluation of the effects of its proposed discharge under Section 404(b)(1) of the Clean Water Act is available as an appendix to the Environmental Assessment. Compliance with Section 401 for water quality certification from the State of Alaska Department of Environmental Conservation has been received. Because of the small size of proposed discharge, and the similarity of the discharged material (i.e., large rock placed for the construction of the breakwaters) to the existing sediments, the determination has been made that compensatory mitigation under Section 404 is not warranted. Furthermore, no compensatory mitigation is needed as there are no impacts to significant resources.

6.0 EVALUATION OF ALTERNATIVES

6.1 Cost of Alternatives

Each alternative has a cost estimate prepared utilizing MCASES and CDEPS found in the Cost Appendix. For evaluation purposes the following costs are used for each alternative as presented in Tables 6, 7, and 8.

Table 6. Project First Costs

Alternative	Description	Cost
N1	North of helipad - two rubble mound breakwaters with laydown/boat storage area	\$27,161,000
S1	South of helipad - two rubble mound breakwaters	\$24,187,000
S2	South of helipad - two rubble mound breakwaters with hooked breakwater and dredging	\$28,146,000
S3	South of helipad - two rubble mound breakwaters with laydown/boat storage area	\$30,366,000

Note: Alternative S3 costs certified as of 27 January 2014 with an effective price level date of 1 October 2014. All cost values include LSF.

Table 7. Periodic Maintenance and Repair Costs

ALT.	Mobilization (a)	Topo Survey (b)	Rock Quantity (CY) (c)	Rock Price (per CY) (d)	Frequency (years)	OMRR&R (a + b + c * d)	Avg. Annual Cost
N1	\$ 1,500,000	\$ 8,300	1,430	\$ 208.38	10	\$ 1,806,000	\$ 154,000
S1	\$ 1,500,000	\$ 8,300	1,275	\$ 208.38	10	\$ 1,774,000	\$ 151,000
S2	\$ 1,500,000	\$ 8,300	1,645	\$ 208.38	10	\$ 1,851,000	\$ 158,000
S3	\$ 1,500,000	\$ 8,300	1,820	\$ 208.38	10	\$ 1,888,000	\$ 161,000

Note: Average annual costs based on 50-year project period of analysis and FY14 Federal discount rate of 3.5 percent; for GNF. There are no projected OMRR&R costs for LSF.

Table 8. Total Cost of Alternatives

Alternative	Description	Cost (includes OMRR&R and IDC)	Average Annual Cost
N1	North of helipad - two rubble mound breakwaters with lay-down/boat storage area	\$ 31,729,000	\$1,353,000
S1	South of helipad - two rubble mound breakwaters	\$ 28,585,000	\$1,219,000
S2	South of helipad - two rubble mound breakwaters with hooked breakwater and dredging	\$ 32,838,000	\$1,400,000
S3	South of helipad - two rubble mound breakwaters with lay-down/boat storage area	\$ 35,169,000	\$1,499,000

Note: Cost includes periodic repair and maintenance of 5% of the armor stone every 10 years for the 50-year period of analysis and interest during the 2-year construction period. Costs include initial dredging, but periodic maintenance dredging is not anticipated. Periodic repair and maintenance have been discounted using the Federal FY14 discount rate of 3.5 percent. Interest during construction (IDC) has been calculated based on a 2-year construction window with an interest rate of 3.5 percent. Alternative S3 costs certified as of 27 January 2014 with an effective price level data of 1 October 2014.

6.2 Benefits of Alternatives

Each alternative offers the same quantifiable benefits – increased acquisition of preferred foods. Other potential benefits could include decreased fuel consumption if long journeys to harvest walrus can be avoided, increased certainty for medical evacuations, the potential for decreased freight costs, efficiencies in harvest preparation if lay-down area is included in the alternative, erosion protection/peace of mind during storms, and opportunity to house Search and Rescue equipment near the proposed offshore Arctic drilling. Not enough is known about the harvest practices to determine if shorter trips to harvest food would decrease fuel consumption or just be offset by the additional time spent harvesting so no benefits are claimed for this category. Freight operators for the region have indicated they will not change their current delivery practices. They would not use the protected harbor but would instead time deliveries to Little Diomedé during relatively calm weather. Winter freight arrives by airplane and would not be affected by the proposed harbor improvements. No attempt was made to quantify increased certainty for medical evacuations or peace of mind for the erosion protection afforded by the proposed alternatives.

The harvesting season for Diomedé residents runs from June to October. Typical harvest operations most often involve the following actions (not an all-inclusive listing of activities):

1. A decision to go is made, which is complicated and requires the consideration of multiple factors such as weather and wave climate, sightings of target species, availability of crew, recent success, among much more.
2. After decision, and taking into account many of the factors, the crew assembles and plans the details of the hunt.
3. The subsistence vessels are dragged and carried over the steep rocky shore to the water for launching.
4. The crew maneuvers the vessel towards the planned areas where previous sightings and trip planning have influenced; making any required adjustments.
5. The target species, if encountered, is taken – or whatever becomes available – usually by rifle, and made ready for transport by appropriate means available considering items such as the mode, weather, and subsistence type. The crew travels back to the village, usually in the vicinity of the launch and retrieval area.
6. Initial processing is carried out usually at the shore, based on the subsistence type and size, with refined operations performed once portioned to the community. Final processing can be of many forms – based on subsistence type, and be done in various ways, such as utilizing drying racks typically found among the housing structures.

An analysis of storms suggests that with protection, Diomedes residents could gain between 17 and 21 days annually in safe launch and retrieval of vessels. This would allow residents to harvest subsistence foods when the food source is close to the community rather than traveling great distances or avoiding the harvest altogether.

Table 9 details the average wave height conditions by month and direction for Little Diomedes. Residents are currently able to launch when wave heights are 1.7 feet or less. The alternatives proposed would provide protection in the 3.3-foot wave height or less climate. The percent of wave constraint column in this table indicates the average percent of the month when Little Diomedes residents are unable to launch and retrieve vessels. June is the least constrained at 40.9 percent, and October is the most constrained at 92.6 percent.

Table 9. Wave Heights by Month and Direction at Diomedes, AK

	Waves from:	No waves	Up to 1.7 feet	1.7 to 3.3 feet	3.3-6.6 feet	Over 6.6 feet	Percent of wave constraint
June	north	7.1	14.4	11.5	7.5	6.5	40.9
	south		37.6	12	3.4		
July	north	1.1	12.6	10.8	7.6	9.7	52.3
	south		34	17.3	6.9		
August	north	0.8	9.5	14.3	14.8	19.6	74.1
	south		15.6	14	11.4		
September	north	0.1	8.2	17	25.3	31.6	87.1
	south		4.6	8.4	4.8		
October	north	0	4.5	15.5	26.6	39.3	92.6
	south		2.9	5.4	5.8		

Note: Numbers in cells represent the proportion of time (percent) waves come from the specified direction. Also note that southerly alternatives will provide protection from northerly waves and the north alternative will provide protection from the southerly waves.

Table 10 shows the number of days of increased ability to launch and retrieve for Little Diomedes residents with a project. The days without a project column depict the days the wave height is up to 1.7 feet. The proposed project would provide launch and retrieve protection for the 3.3-foot wave height. The percentage increase for the north alternative (protects from southerly waves) is 35.4 percent (north and south total days plus south additional days divided by north and south total days without a project). The percentage increase for the south alternatives (protects from northerly waves) is 42.7 percent (north and south total days plus north additional days divided by north and south total days without a project). These percentages are used for the NED calculation of possible benefits to more clearly compare the NED evaluation with the CE/ICA evaluation, which follows:

Table 10. Wave Heights by Month and Direction at Diomedes, Alaska

	Waves from:	Days without project	Additional days with project
June	north	6.45	3.45
	south	13.41	3.60
July	north	4.25	3.35
	south	10.88	5.36
August	north	3.19	4.43
	south	5.08	4.34
September	north	2.49	5.10
	south	1.41	2.52
October	north	1.40	4.81
	south	0.90	1.67
Total annual days	north	17.78	21.14
	south	31.68	17.50
Percent increase	north		42.73%
	south		35.38%

Estimates for the amount of increased food acquisition in Diomedes, if a wave protection project was developed, show that subsistence could increase from 35.4 percent to 42.7 percent over current levels. The 2010 subsistence valuation estimate for Diomedes was \$651,000. Using the Producer Price Index for Finished Consumer Foods from the U.S. Bureau of Labor Statistics, the 2013 value subsistence effort at Little Diomedes is \$742,000.

- An increase of 35.4 percent represents an annual with-project benefit of \$262,000.
- An increase of 42.7 percent represents an annual with-project benefit of \$317,000.

These amounts are based on point estimates of the economic value of Diomedes's subsistence production in 2013 dollars and use the percentage increase in days as a proxy for the increased production. The range of total benefits given a 50-year project life and using the Fiscal Year 2014 discount rate of 3.5 percent is between \$6.2 million and \$7.4 million. All of the alternatives have estimated costs in excess of these potential benefits; therefore, none of the alternatives serve as the most likely recommended NED plan. See Table 11.

Table 11. Benefit/Cost Evaluation by Alternative

Alt.	Cost with OMRR&R	Low Case Scenario			High Case Scenario		
		Total Benefits (PV)	Net Benefits	B/C Ratio	Total Benefits (PV)	Net Benefits	B/C Ratio
N1	\$31,729,000	\$4,985,000	\$(26,744,000)	0.16	\$ 6,021,000	\$ (25,708,000)	0.19
S1	\$28,585,000	\$6,158,000	\$(22,427,000)	0.22	\$ 7,438,000	\$ (21,147,000)	0.26
S2	\$32,838,000	\$6,158,000	\$(26,680,000)	0.19	\$ 7,438,000	\$ (25,400,000)	0.23
S3	\$35,169,000	\$6,158,000	\$(29,011,000)	0.18	\$ 7,438,000	\$ (27,731,000)	0.21

As mentioned previously, Section 2006 of WRDA 2007 allows for further analyses of viable alternatives based on subsistence variables. Further plan comparisons in accordance with the Section 2006 authority follow.

7.0 COMPARISON AND SELECTION OF PLANS

7.1 Comparison of Plans

7.1.1 Comparison of Costs

Of the four design alternatives, S1 is the least costly with a total project cost of \$28,585,000 but does not include a lay-down area. Alternative S3, with an estimated total project cost of \$35,169,000, is the least cost plan identified that includes the maximum protection and provides a lay-down area.

7.1.2 Comparison of Benefits

All the alternatives offer the same quantifiable benefits – increased acquisition of preferred subsistence foods. Other benefits that have not been quantified include decreased fuel consumption if long journeys to harvest walrus can be avoided, increased certainty for medical evacuations, the potential for decreased freight costs, efficiencies in harvest preparation for lay-down areas, erosion protection during storms, and opportunity to house Search and Rescue equipment.

7.2 Selection of Plan

Navigation improvements at Diomedede would meet the criteria of Remote and Subsistence Harbors as defined in the Water Resources Development Act of 2007 (WRDA 2007), Section 2006 as indicated below.

(1)(A) the community to be served by the project is at least 70 miles from the nearest surface accessible commercial port and has no direct rail or highway link to another community served by a surface accessible port or harbor; or

(B) the project would be located in the State of Hawaii, the Commonwealth of Puerto Rico, Guam, the Commonwealth of the Northern Mariana Islands, the United States Virgin Islands, or American Samoa;

The nearest surface accessible port to Diomedede is in Anchorage approximately 685 air miles from Diomedede. Diomedede is an isolated island village lacking any direct rail or highway access to any other communities.

(2) the harbor is economically critical such that over 80 percent of the goods transported through the harbor would be consumed within the community served by the harbor and navigation improvement; and

Lacking any sort of access to any other communities, 100 percent of goods transported to Diomedede would be consumed within the community.

(3) the long-term viability of the community would be threatened without the harbor and navigation improvement.

WRDA 2007, Section 2006 formally recognizes the importance of harbors and navigation improvement projects serving isolated communities. These harbors and projects are the lifelines of the communities, without which, the very existence of the communities would be threatened.

(b) Justification- In considering whether to recommend a project under subsection (a), the Secretary shall consider the benefits of the project to—

(1) public health and safety of the local community, including access to facilities designed to protect public health and safety;

Potential safety boat could serve as back up to the helicopter during poor visibility or mechanical breakdowns.

(2) access to natural resources for subsistence purposes;

Increased subsistence effort/harvest

(3) local and regional economic opportunities;

Alternate mode of access between the island and mainland could increase opportunity for locals to seek seasonal employment and/or to travel to sell their art

(4) welfare of the local population; and

Reduce time away from island, people more likely to travel to island to provide services, people more likely to travel from island to seek routine medical treatment

(5) social and cultural value to the community.

Maintaining a viable community at Diomedes will preserve their unique culture.

Improved access will allow more social and cultural interaction between residents and their relatives in other communities, contributing to preservation of a broader regional cultural identity.

7.2.1 Identification of Recommended Plan

The Implementation Guidance for Section 2006 of the Water Resources Development Act of 2007 (WRDA 2007, dated 22 Jul 2008) – Remote and Subsistence Harbors states that the following policy and procedures will be used to implement Section 2006:

- a. Decision documents addressing harbor and/or related navigation improvements may address the criteria and considerations listed above in the formulation, evaluation and selection of alternatives. The analysis will be incorporated into the existing four accounts (see EC 1105-2-409) and ER 1105-2-100.
- b. Decision documents will continue to present the NED analysis for all viable alternatives and identify the NED Plan when alternatives exist with net positive NED benefits.
- c. A decision document may recommend a plan other than the NED Plan based on a full description of the benefits of the project to public health and safety of the local community; access to natural resources for subsistence purposes; local and regional economic opportunities; welfare of the local population, and social and cultural value to the community.
- d. If there is no NED Plan and/or the selection of a plan other than the NED Plan is based in part or whole on the non-monetary units (Environmental Quality (EQ) and Other Social Effects (OSE) accounts), then the selection will be supported by a cost effectiveness/incremental cost analysis consistent with ecosystem restoration

evaluation procedures (see Appendix E, Section V, ER 1105-2-100). The decision document will present the tradeoffs of impacts in the four accounts for the plan in the final array and describe the compelling justification for any plan that is not the NED Plan.

None of the alternatives for Little Diomedede have net positive NED benefits. Public health and safety, access to natural resources for subsistence purposes, economic opportunities, welfare of the local residents, and social and cultural value to the community have been described previously in this document. The following section uses the cost effectiveness/incremental cost analysis (CE/ICA) methodology to determine a recommended plan.

CE/ICA. Cost effectiveness/incremental cost analysis is typically used for environmental studies where the cost of the solution is compared with changes in habitat. Little Diomedede, however, is not an environmental study. The problem concerns navigability to and from the community. Improved navigability will allow the residents of Little Diomedede to engage in subsistence activity more frequently, thereby increasing the overall harvest and allowing residents to harvest their preferred foods. So the comparisons to costs for the CE/ICA evaluation were established as increased days of navigability and increased flat land for processing of harvest and boat storage. The criteria used in the analysis are as follows:

- a. **Total Project Costs** – including materials, labor, mobilization and demobilization, engineering, and contingencies. Repair and maintenance are calculated as 5 percent replacement of the armor rock every 10 years. Interest During Construction is calculated for a 2-year construction period at the FY14 discount rate of 3.5 percent.
- b. **Additional Subsistence Days Available** – the north alternative provides protection from southerly wind and waves, while the south alternatives provide protection from northerly wind and waves. Based on engineering calculations and historic storm data, the north alternative would provide an additional 17 days annually that Little Diomedede residents could safely launch and retrieve vessels. The south alternatives provide an additional 21 days of protection. Additional days for the south alternatives occur primarily August through October as this is when northerly waves are predominant. The presence of ice during June and July is a major reason the wave climate is dominated by 0.3 to 3.2-foot waves; the ice acts essentially as breakwater protection and facilitating subsistence activities. Table 12 provides the additional launch days that would be available for each alternative. The values were compiled by utilizing existing wave information calculated from the data found in the engineering appendix.

Table 12. Additional Launch Days Available (waves less than 3.3 feet)
***N1 data uses only south waves**

Month	N1*	S1	S2	S3
June	3.6*	3.5	3.5	3.5
July	5.4*	3.3	3.3	3.3
August	4.3*	4.4	4.4	4.4
September	2.5*	5.1	5.1	5.1
October	1.7*	4.8	4.8	4.8
Totals	17.5*	21.1	21.1	21.1

- c. **Lay-down/Boat Storage Area** – two of the alternatives (one north and one south, N1 and S3, respectively) were designed to provide new flat land for Little Diomed residents to store/repair boats or conduct subsistence activity (i.e. skinning mammals, preparing for hunts). The sheer cliff environment at Little Diomed makes flat land very valuable and a desirable navigation feature. The existing areas for these activities are within the village along the steep slopes and amongst loose boulders, and comprise a calculated area of 0.325 acre. The additional subsistence area provided for in alternative N1 is 0.38 acre; alternative S3 is 0.14 acre. Only the area provided in alternative S3 is a gain since the N1 area was determined necessary for the movement and storage of the existing subsistence vessel fleet. For alternative S3, it was determined that an increase of 2 vessels (0.07 acre each) would be appropriate for calculation of the subsistence vessel day (see Table 13). Existing area available was determined from a number of photos of the community which includes flat areas used for skin and meat drying racks found on slopes and within structures equaling ~0.325 acre. This area was apportioned to the existing vessel count (5) to determine vessel usage per existing subsistence area; the existing subsistence value was found to be around 3000 sq.ft per vessel (rounding prevalent in conversions). The flat area resulting from the with-project condition was measured and equated to the existing flat area usage – this calculation was determined as 0.14 acre, or an additional 2 subsistence vessel days – since 3000 sq.ft. is slightly more than 0.07 acres.
- d. **Improved Safety** – all alternatives would improve the ability of boat owners to launch and retrieve vessels and would also allow a larger vessel to access the community for emergency evacuations. Using a dominant north wave (348.75° – 11.25°), the south alternatives have slight differences in reducing wave heights near the launch area. Alternatives S1 and S3 provide the same level of reduction, with S2 providing slightly more due to the bent breakwater configuration. Despite these slight differences, there would be no discernible difference among the south alternatives for additional days; all provide the same 21 days. The north alternative N1 would not provide any protection from the dominant north waves, which occur during the months of August through October; neither would it serve beneficially the current barge/cargo movement activities and existing storage facilities.

The alternatives would eliminate near shore rocks that damage the small vessels as they approach through the surf zone. Supply vessels such as landing craft would be able more safely land without concern of hull punctures on the rocks. Community vessels would be able to lighter supplies from larger vessels more frequently.

Improved safety will be accomplished by providing better access to the mainland because residents will be able to launch boats more frequently to either make the crossing to the mainland or to lighter to larger boats. This vessel access to the mainland would improve the community's access to health, dental, and social services available only on the mainland. The current practice of evacuating expectant mothers months prior to due dates would be decreased with the greater access reliability.

- e. **Existing Road** –Little Diomedede has few roads. However, there is a frontage road on the island that would benefit the south helipad alternatives as vehicles and heavy equipment can maneuver in this area, while the north alternative does not have this same access.

These criteria were taken into account with respect to available vessel days so that a measurement could be given and incremental justification could be accomplished. Additional Subsistence Days Available, Lay-down/Boat Storage Area, and Improved Safety (items b, c and d) were given a value and combined for each alternative and a “subsistence vessel day” (SVD) amount calculated. Each alternative adds days that vessels can be launched, increasing the subsistence opportunities. The additional lay-down area increases the number of vessels that can be utilized, and the flat areas were equated with the daily subsistence values found in a technical report titled “A Summary of Without Project Conditions and Impacts to Diomedede” compiled by Jim Richardson of ResourcEcon for the U.S. Army Corps of Engineers, Alaska District, dated May 2012, included as Appendix A. The criteria categories for each alternative are displayed in Table 13.

Table 13. Criteria for Little Diomed CE/ICA

Alt	Total Project Cost ¹	Additional Days ²	Lay-down/Boat Storage Area (Acres)	Safety from North Waves	Existing Road ³	Additional Subsistence Vessel Days (Calc.) ⁴
N1	\$31,729,000	17*	0.38	No	No	87
S1	\$28,585,000	21	0	Yes	Yes	106
S2	\$32,838,000	21	0	Yes	Yes	106
S3	\$35,169,000	21	0.14	Yes	Yes	247

1. Cost: TPCS estimate dated 4/8/2013 (see also Table 6). Alternative S3 project costs certified as of 27 January 2014. Includes OMRR&R and IDC.

2. Additional Days: North alternative protects from southerly wind and wave conditions; south alternatives protect from northerly wind and wave conditions. These are additional days that boaters can launch and retrieve with protections from waves up to 3.3 feet.

3. Existing Road: The northern alternative does not include construction of a road to access the lay-down area. Southern alternatives have a road adjacent to the lay-down area.

4. Subsistence Vessel Days: Additional days multiplied by number of subsistence vessels with consideration of additional subsistence area for S3. Currently, there are about five active subsistence vessels in the community and the lay-down area (additional acreage) is given a value of 2 for the S3 alternative. So for Alt S2, there are an additional 21 days to launch and retrieve for 5 vessels for a total Subsistence Vessel Day value of 106 ($21 * 5 = 106$). For S3, the additional lay-down area has a value of 2 and would apply to all the available launch and retrieval days, not just the additional days. So the calculation for SVD on Alternative 3 is the additional lay-down area times the total launch and retrieve days ($70.6 \text{ days} * 2$) plus the additional launch and retrieve days times the number of vessels ($21 \text{ days} * 5 \text{ vessels}$) for a total change in SVD of 247 ($70.6 * 2 + 21 * 5 = 247$).

In processing the criteria for incremental analysis, the north alternative (N1) was eliminated from further consideration since it fell short on important characteristics that would provide the study objective. It was clear that N1 lacks viable access and does not provide protection from northerly waves that are dominant in August, September, and October. In contrast, each of the south alternatives provides protection for the dominant wave condition. The N1 alternative is also impractical because of a reef area between Big and Little Diomed that hinders safe navigation and is unworkable considering the existing storage and movement of cargo in the southern area of the village. Lack of road access was another relevant factor. The three southern alternatives, S1, S2, and S3 remained viable.

The goal for the Little Diomedé project is to improve navigation for the community so they will have safe and reliable access to emergency and routine medical care, and assist in the long-term viability of the community with regards to subsistence activities per Section 2006. So the added criteria of additional days to launch and retrieve vessels and the lay-down/boat storage area will help achieve this goal.

The project cost for S3 is found to be the best investment on a subsistence vessel day basis. The construction cost is \$35,169,000 and it provides 247 subsistence vessel days at an average annual cost \$6,072. The least costly alternative is S1 at \$28,585,000; however, it only provides 106 additional subsistence vessel days and has a greater average annual cost of \$11,535. Alternative S2 provides the same output for higher cost so it was eliminated from further evaluation.

Table 14 shows the three alternatives along with total project cost, average annual cost, the output in subsistence vessel days (SVD), and the average cost per subsistence vessel day.

Table 14. Output and Cost of Alternatives

Alternative	Total Project Cost	Average Annual Cost	Output (SVD)	Average Cost per SVD
S1	\$28,585,000	\$1,219,000	106	\$11,535
S2	\$32,838,000	\$1,400,000	106	\$13,248
S3	\$35,169,000	\$1,499,000	247	\$6,072

The cost, output, and average costs are used along with the incremental cost and output in Table 15. This provides the incremental cost per subsistence vessel day that helps answer whether or not the increased project cost is worth the investment. The incremental analysis shows that S1 provides 106 additional subsistence vessel days, each costing \$11,535. Having S3 in place provides 141 more subsistence vessel days than S1, at a smaller incremental cost of \$1,983 per unit.

Table 15. Alternative Plans with Incremental Cost per SVD

ALT.	Cost	Output (SVD)	Average Annual Cost	Incremental Cost (Average Annual)	Incremental Output	Inc. Cost per SVD
No-Action	\$0	247	n/a	n/a	n/a	n/a
S1	\$28,585,000	353	\$1,219,000	\$1,219,000	106	\$11,535
S3	\$35,169,000	494	\$1,499,000	\$280,000	141	\$1,983

Note: Additional lay-down area provides benefit to the total days for launch and retrieval of vessels, not just the additional days.

As a visual aid the following graphic (Figure 7) depicts the incremental cost and output clearly showing that alternative S3 is a worthwhile investment over S1 because it provides more output at less cost.




Figure 7. Incremental Analysis Cost Graphic

7.2.2 Four Accounts Evaluation

USACE planning guidance establishes four accounts to facilitate and display effects of alternative plans. Previous studies have relied primarily on the use of the National Economic Development account showing the changes in economic value of the national output of goods and services. A benefit/cost ratio and an indication of the change in net benefits is the output of the NED evaluation and for this study formed the basis for proceeding with the Cost/Effectiveness Incremental/Cost analysis.

Included as part of the remaining four accounts are the Environmental Quality (EQ), the Regional Economic Development (RED), and Other Social Effects (OSE) indicators. Environmental Quality depicts the natural environment and the potential the project has to cause a negative or positive effect. All alternatives are expected to have no significant

positive or negative effect.. The Regional Economic Development (RED) account typically displays the changes in employment and income to the region as a result of the selected alternative. However, for a limited cash society such as Little Diomed, these changes are difficult to quantify. In all cases, the alternatives will provide additional opportunity for the residents of Little Diomed to engage in subsistence harvest activity which is their employment. Other Social Effects (OSE) displays the non-monetary effects of the alternatives and is depicted here as the change in subsistence vessel days as a result of any of the alternatives. Alternative S3 provides the highest net change in subsistence vessel days, measures the beneficial and adverse effects on social well-being from the federal project. In all cases, safety of vessel operators launching and retrieving will be improved with the project. In addition, food security will be enhanced as residents will be able to harvest their preferred foods on a more regular basis. See Table 16 for the four account evaluations by alternative.

Table 16. Four Accounts Evaluation for Little Diomed Navigation Improvement

Alternative	NED ¹	EQ ²	RED ³	OSE ⁴
North Alternative				
N1 - North of helipad - two rubble mound breakwaters with laydown/boat storage area	\$ (26,744,000) 0.18	No effect	Increased subsistence harvest opportunities.	87 SVD
South Alternatives				
S1 - South of helipad - two rubble mound breakwaters	\$ (21,787,000) 0.24	No effect	Increased subsistence harvest opportunities.	106 SVD
S2 - South of helipad - two rubble mound breakwaters with hooked breakwater and dredging	\$ (26,040,000) 0.21	No effect	Increased subsistence harvest opportunities.	106 SVD
S3 - South of helipad - two rubble mound breakwaters with laydown/boat storage area	\$ (28,371,000) 0.20	No effect	Increased subsistence harvest opportunities.	247 SVD

Notes:

1. NED is the average net benefits of the low and high scenarios with the benefit/cost ratio following. A desirable benefit/cost ratio is greater than one.
2. EQ is positive or negative effect of the project.
3. Regional economic development changes affect income and employment. For remote Alaska communities, this is all related to subsistence as food, clothing, education, and other cultural implications all apply.
4. Other social effects is the number of additional subsistence vessel days achieved with the project and pertains to the health and safety of the residents, and in all cases these improvements would benefit the community in this regard.

8.0 RECOMMENDED PLAN

8.1 Plan Components

The alternative that offers the most benefit to the community for the cost is S3, a southern breakwater along with a rubble mound lay-down/boat storage area.

8.1.1 Basin

A small near-shore area would be dredged to -10 feet MLLW, requiring removal of approximately 3,000 cubic yards of material.

8.1.2 Breakwaters

The breakwaters would require approximately 78,400 cubic yards of assorted rock. The breakwater configuration would reduce waves from the north with periods of 8 seconds or less to about a third of the wave height at the current boat launch area. Plan S3 is shown in Figure 8.




Figure 8. Alternative S3

8.1.3 Dredged Material Disposal and Dredged Material Maintenance Plan

To the extent practicable, the Corps would incorporate the rocky material dredged from between the breakwaters as fill in the expanded breakwater and lay-down areas. The enforcement agency for Section 404 is the U.S. Army Corps of Engineers; the Corps does not issue permits to itself, but has prepared an evaluation of the effects of its proposed discharge under Section 404(b)(1), available in Appendix 1. The Corps has complied with Section 401 and has received a water quality certification from the State of Alaska Department of Environmental Conservation. Because of the small size of proposed discharge, and the similarity of the discharged material (i.e., large rock placed for the construction of the breakwaters) to the existing sediments, the Corps determines that compensatory mitigation under Section 404 is not warranted. Also, no compensatory mitigation is needed as there are no impacts to significant resources.

8.1.4 Local Service Facilities

The recommended plan consists of two distinct items: a protective breakwater and a “flat area.” The purpose of the “flat area” is to provide area needed to store vessels, maintain/repair vessels and subsistence gear, and to perform subsistence food processing activities. All of these actions provide the community an increased ability to perform subsistence activities and thus accrue project benefits. The breakwater provides protection to the “flat area” and also serves as part of providing protection for the safe launch and retrieval area for boats.

When compared to a more typical small boat harbor, the breakwater acts as a typical breakwater in providing protection to the area for which the benefits are accruing. The “flat area” acts as moorage facilities on which the activities occur from which the economic benefits arise which would therefore be considered LSF. Figure 9 shows a depiction of what project features are LSF.

8.2 Plan Benefits and Accomplishment

The proposed construction of breakwaters and a boat launching area at Diomedes, Alaska, as discussed in this document, would have some minor, largely controllable short-term impacts, but in the long term would help improve the overall quality of the human environment. The recommended plan also meets study authorization criteria of Remote and Subsistence Harbors as defined in the Water Resources Development Act of 2007 (WRDA 2007), Section 2006 as indicated below. A project specific response to each element is given.

(1)(A) the community to be served by the project is at least 70 miles from the nearest surface accessible commercial port and has no direct rail or highway link to another community served by a surface accessible port or harbor; or

(B) the project would be located in the State of Hawaii, the Commonwealth of Puerto Rico, Guam, the Commonwealth of the Northern Mariana Islands, the United States Virgin Islands, or American Samoa;

The nearest surface accessible port to Diomedes is in Anchorage approximately 685 air miles from Diomedes. Diomedes is an isolated island village lacking any direct rail or highway access to any other communities.

(2) the harbor is economically critical such that over 80 percent of the goods transported through the harbor would be consumed within the community served by the harbor and navigation improvement; and

Lacking any sort of access to any other communities, 100 percent of goods transported to Diomedé would be consumed within the community.

(3) the long-term viability of the community would be threatened without the harbor and navigation improvement.

Lack of safe and reliable access has resulted in a life threatening shortage of emergency and routine medical care, significant restrictions on travel both to and from the community, shortages of basic commodities, and lack of materials to repair deteriorating infrastructure. Long-term continued viability of the community is in jeopardy. WRDA 2007, Section 2006 formally recognizes the importance of harbors and navigation improvement projects serving isolated communities. These harbors and projects are the lifelines of the communities, without which, the very existence of the communities would be threatened.

(b) Justification- In considering whether to recommend a project under subsection (a), the Secretary shall consider the benefits of the project to—

(1) public health and safety of the local community, including access to facilities designed to protect public health and safety;

Potential safety boat could serve as back up to the helicopter during poor visibility or mechanical breakdowns.

(2) access to natural resources for subsistence purposes;

Increased subsistence effort/harvest by increasing the opportunities to launch/land vessels is accomplished – a main objective for Diomedé.

(3) local and regional economic opportunities;

Alternate mode of access between the island and mainland could increase opportunity for locals to seek seasonal employment and/or to travel to sell their art.

(4) welfare of the local population; and

Reduce time away from island, people more likely to travel to island to provide services, people more likely to travel from island to seek routine medical treatment.

(5) social and cultural value to the community.

Maintaining a viable community at Diomedé will preserve their unique culture.

Improved access will allow more social and cultural interaction between residents and their relatives in other communities, contributing to preservation of a broader regional cultural identity.

Thirdly, cultural funders invest in assets that have significance beyond their economic value. The assets – whether a painting, a performance or a historic building – are often unique and almost always incapable of being replicated, replaced or exchanged. Furthermore, cultural assets and activities have a worth beyond cost or realizable value and that worth is difficult to

articulate, let alone calculate. Competing investment claims do not rest on straightforward comparisons; funders are rarely comparing like with like.

The project would significantly improve the quality of life for the residents of Little Diomede as well as provide life/safety benefits, which include the following:

- Improve resident's quality of life through better access to:
 - health care and emergency services
 - education and employment opportunities
 - subsistence resources
 - manufactured goods
- Improvements to standards of living and sustainability of the community from reductions in the delays and costs of delivery of passengers, freight, and supplies
- Improved quality of life and health by improving waste disposal practices
- Accommodation of larger, more sea-worthy local vessels providing for increased subsistence harvests and safer travel to nearby communities.
- Providing a level area suitable for the staging of goods and subsistence harvest support activities (net mending, butchering, skin stretching, etc.)
- Accommodation of a search and rescue vessel
- Regularly scheduled boat service to nearby communities providing reliable access to Diomede
- Reduced damages to locally owned boats
- Increased economic opportunity through more frequent visitation by cruise vessels passengers (via zodiac boat)

Realizing any of these identified items will improve the sustainability of the community and help maintain its unique social and cultural values and traditions.

8.3 Plan Costs

The certified estimate of the total cost of the recommended plan is \$30,366,000.

Construction cost share is 90 percent Federal and 10 percent non-Federal for the general navigation features (GNF). There is also a requirement for an additional 10 percent of the navigation features to be paid over a period not to exceed 30 years of which any applicable LERRs may be credited. Local service facilities (LSF) are the responsibility of the non-Federal Sponsor. The project has identified \$1,406,000 of the total cost as LSF; typical cross-section of the southern breakwater depicted in **Figure 9**. The non-Federal Sponsors for implementation of the project are expected to be the City of Diomede and the Native Village of Diomede, with financial assistance from Kawerak, Inc, the Norton Sound Economic Development Corporation, and the State of Alaska. The ultimate cost share allocation for the

recommended plan is \$23,179,000 Federal and \$7,187,000 Non-Federal. The estimated PED costs are projected as \$3.6 million and will be cost shared with Kawerak, Inc. (Table 17).




Figure 9. Typical Cross-section of Southern Breakwater LSF

Table 17. Cost Apportionment (1 Oct 2014 price level)

WBS	ITEMS	Total Project Cost	Implementation Costs			
			Federal	%	Non- Federal	%
10	BREAKWATER & SEAWALLS	23,456	21,111		2,346	
12	NAVIGATION PORTS & HARBORS	152	137		15	
30	PLANNING, ENGINEERING & DESIGN	3,469	3,122		347	
31	CONSTRUCTION MANAGEMENT	1,828	1,645		183	
	GNF Sub-total	28,905	26,015	90	2,891	10
01	LANDS AND DAMAGES (LERR)	54			54	100
	Project Sub-total	28,960	26,015		2,945	
10	BREAKWATER & SEAWALLS LSF	1,186	-		1,186	
01	LANDS AND DAMAGES (LERR) LSF	5	-		5	
30	PLANNING, ENGINEERING & DESIGN LSF	141	-		141	
31	CONSTRUCTION MANAGEMENT LSF	74	-		74	
	LSF Sub-total	1,406	-		1,406	100
	Additional Local Funding Requirement		Federal		Non- Federal	
	10% of GNF		(2,891)		2,891	
	GNF LERR credit (RE, Admin, Relocation)		54		(54)	
	Adjustment for GNF with LERR credit		(2,836)		2,836	
	FINAL (Ultimate) COST ALLOCATION		Federal		Non- Federal	
		30,366	23,179		7,187	
	Cost Share Percentage		76%		24%	
	Project First Cost Total		28,960		2,945	
	Non-Federal First Cost Responsibility				4,351	

Present Value Calculation uses FY14 discount rate of 3.5 percent. PED values are based on a set percentage of construction cost; actual amounts will vary. Values may include round-off because of significant digit percentage calculation.

9.0 PUBLIC AND AGENCY INVOLVEMENT

9.1 Public Involvement

A public scoping meeting with the residents of Diomedes was held in Diomedes on February 28, 2007. Alternatives and potential environmental impacts of those alternatives were discussed.

Additional site visits were made later in 2007 and in subsequent years to gather data and gain additional input from the local residents.

The EA was released for a 30-day public review period in November 2013. Only one comment letter was received.

9.2 Agency Coordination

The EA was sent to the following agencies as part of the 30-day public and agency review process in November 2013. No comments were received from any of the resource agencies. As of April 2014, coordination activities with major resource agencies stood as follows:

Alaska Department of Fish and Game: A letter describing the project and inviting ADFG to participate in project coordination was sent to ADFG (attn: William Morris) on 10 January 2012. The Corps received an email response from ADFG (Todd Nichols) dated 23 January 2012, stating that the ADFG had found no issues of concern and had no preference of one alternative over the other.

Alaska Department of Natural Resources, Office of History and Archaeology: The Corps used online resources offered by this office to study potential impacts of the project and develop a determination of effect. The Corps sent a letter of determination to the State Historic Preservation Officer on November 25, 2013, requesting their concurrence on our finding of no adverse effect, as required under Section 106 of the NHPA. The SHPO responded in a letter dated December 13, 2013, concurring with our finding of no adverse effect. This letter is in the Correspondence Appendix.

Alaska Department of Environmental Conservation. The Corps received a 401 Certificate of Reasonable Assurance under the Clean Water Act in March 2014. The letter and certification are in Appendix 3, Correspondence.

National Marine Fisheries Service: A letter requesting a list of endangered and threatened species under the ESA and the initiation of informal ESA consultation was mailed to the NMFS Protected Resources Division (attn: Brad Smith) on 10 January 2012. No response was forthcoming; the Corps re-sent an electronic copy of the letter in an email to Mr. Smith on 21 June 2013, and followed up with a telephone call on 27 June 2013. The Corps was assured during the telephone conversation that NMFS would provide the requested ESA information, but to date the Corps has received no further response.

The Corps sent a separate letter to the NMFS Habitat Conservation Division (attn: Jeanne Hanson) on 10 January 2012, describing the proposed project and inviting coordination on EFH issues. No response was received; however, Division member Matt Eagleton had

explained in an earlier email (3 January 2012) that his office preferred to comment on EFH assessments as part of the NEPA process, so a response to the 10 January letter was not expected. The Corps sent NMFS a copy of the draft feasibility report and EA for their review during the 30-day public review process in November 2013. NMFS did not comment.

U.S Fish and Wildlife Service: The Corps mailed a letter on 10 January 2012 to the USFWS Fairbanks Field Office (attn: Sarah Conn), requesting a re-initiation of informal consultation under the ESA, and also inviting resumption of coordination under the FWCA. The Corps received an ESA consultation letter from USFWS on 28 June 2013, in which it determined that the project is not likely to adversely affect ESA-listed species under USFWS jurisdiction (polar bears, Steller’s eiders, and spectacled eiders), and that further Section 7 consultation or preparation of biological assessments is not necessary. The Corps has continued working closely with the Fairbanks Field Office Conservation Planning Assistance Branch on an informal basis.). USFWS has declined to reinitiate informal consultation under the ESA and coordination under the FWCA. The Corps has continued informal coordination with USFWS on migratory bird issues. All recent emails, correspondence, and the 2008 Planning Aid letter are in the Correspondence Appendix. The 1992 Coordination Act Report is included in the EA by reference.

US Environmental Protection Agency. There is no regulatory requirement to coordinate with USEPA because the project does not involve in-water disposal, and no Marine Protection, Research, and Sanctuaries Act authorization is needed.

9.3 Status of Environmental Compliance

Table 18. Status of Environmental Compliance.

ACTS and EO's	Status	Notes
Archeological & Historical Preservation Act of 1974	In Compliance	
Clean Air Act	In Compliance	
Clean Water Act	In Compliance	
Coastal Zone Management Act of 1972	NA	
Endangered Species Act of 1973*	In Compliance	
Fish and Wildlife Coordination Act	In Compliance	
National Environmental Policy Act	In Compliance	
Marine Protection, Research & Sanctuaries Act of 1972	In Compliance	
National Historic Preservation Act	In Compliance	
River and Harbors Act of 1899	In Compliance	
Magnuson-Stevens Fishery Conservation & Mgt. Act	In Compliance	
Marine Mammal Protection Act	In Compliance	
Executive Order 11593, Protection of Cultural Environment	In Compliance	

Executive Order 12898, Environmental Justice	In Compliance
Executive Order 13045, Protection of Children	In Compliance
STATE AND LOCAL	
State Water Quality Certification	In Compliance
Alaska Coastal Mgmt. Program	NA

9.4 Views of the Sponsor

The non-Federal sponsors for implementation of the project are the City of Diomedes and the Native Village of Diomedes, with financial assistance from Kawerak, Inc, the Norton Sound Economic Development Corporation, and the State of Alaska. Letters of intent from the City of Diomedes and a combined letter from Kawerak Inc and the Native Village of Diomedes have been included in the Correspondence Appendix. The Native Village of Diomedes was sent a letter dated September 23, 2009 that offered continued coordination and consultation through the government-to-government consultation process. Formal government-to-government consultation was not requested.

10.0 CONCLUSIONS AND RECOMMENDATIONS

10.1 Conclusions

The studies documented in this report indicate that Federal construction of navigation improvements as described in the recommended plan is technically possible, environmentally and socially acceptable, and in accordance with Section 2006 of the Water Resources Development Act of 2007. Thus, it is concluded that the navigation improvements described herein should be pursued by the Federal government in cooperation with the non-Federal sponsor.

10.2 Consistency with the Environmental Operating Principles

The Corps civil works mission has traditionally focused on its principal areas of responsibility: navigation, flood control, storm damage protection, and most recently environmental restoration. Water resources projects look to address society's need to encourage economic growth consistent with a healthy environment and national security. Key to integrating these goals, which in the past were often viewed as conflicting, is developing projects and systems that are sustainable in the long term from each perspective. Integrated water resources management requires an examination of proposed projects in a manner that comprehensively examines outputs and potential to integrate other purposes to achieve overall sustainability. The Corps has reaffirmed its commitment to the environment in a set of "Environmental Operating Principles". These principles foster unity of purpose on environmental issues and reflect a positive tone and direction for dialogue on environmental matters. By implementing these principles within the framework of Corps regulations, the Corps continues its efforts to evaluate the effects of its projects on the environment and to seek better ways of achieving environmentally sustainable solutions in partnership with stakeholders. The seven "Environmental Operating Principles" are as follows:

1. Foster sustainability as a way of life throughout the organization.
 - The improvements provide sustainable subsistence way of life for the community.
2. Proactively consider environmental consequences of all Corps activities and act accordingly.
 - Throughout the development of alternatives the foundational concepts consider avoidance and minimization of environmental impacts.
3. Create mutually supporting economic and environmentally sustainable solutions.
 - The potential opportunities identified in the study represent a balance between development and the environment.
4. Continue to meet our corporate responsibility and accountability under the law for activities undertaken by the Corps, which may impact human and natural environments.
 - The project will comply with all Federal and State laws and regulations, notably in the areas of environmental impacts, review, and comment.

5. Consider the environment in employing a risk management and systems approach throughout the life cycles of projects and programs.

- All study elements consider risk management and have incorporated factors such as varying contingency amounts.

6. Leverage scientific, economic, and social knowledge to understand the environmental context and effects of Corps actions in a collaborative manner.

- Throughout the study process a wealth of information was researched and shared.

7. Employ an open, transparent process that respects views of individuals and groups interested in Corps activities.

- This study was fully coordinated in a collaborative manner.

For large-scale navigation improvements, the EOP requires a view that does not end with merely minimizing and mitigating the impacts of dredging and dredged material disposal, but looks further to examine how a project might incorporate features, methods, and procedures that synergistically incorporate these mission goals. Towards that end, management measures are developed to address such opportunities, and where appropriate, these are incorporated into project plans. Other procedures are evaluated and incorporated into project design at later stages when project recommendations are more defined.

The recommended plan maximizes the balance of human need and impacts to the environment. The community and users were involved in the planning process and endorse the recommended plan. Avoidance of impacts to the environment was incorporated in the placement plan for dredged material to a location in need of such material. The breakwater layout maximizes circulation within the harbor to provide sustainable water quality.

10.3 Corps of Engineers Campaign Plan

The USACE Campaign Plan guides Corps policy decisions on how we organize, train, and equip our personnel; how we plan, prioritize, and allocate resources; and how we respond to emerging requirements and challenges. Implementation of the goals and objectives from this Campaign Plan will lead to actual change in the Corps organization moving the Corps from “good to great.” The Corps strategic plan effort towards improvement began in August 2006 with the “12 Actions for Change” and has evolved to four goals and associated objectives. Although the effort originally developed with a focus on missions that seek to manage risk associated with flooding and storm damage, the Campaign Plan Goals and Objectives are applied to all aspects of the Corps including the navigation mission.

USACE Campaign Plan Goals and Objectives are derived, in part, from the Commander’s Intent, the Army Campaign Plan, and Office of Management and Budget guidance. The four goals with associated objectives applicable to this civil works navigation improvement are:

- Goal 1: Deliver USACE support to combat, stability, and disaster operations through forward deployed and reach back capabilities.
- Goal 2: Deliver enduring and essential water resource solutions through collaboration with partners and stakeholders.
 - Objective 2a: Deliver integrated, sustainable, water resources solutions.

- Objective 2b: Implement collaborative approaches to effectively solve water resource problems.
- Goal 3: Deliver innovative, resilient, sustainable solutions to the Armed Forces and the Nation.
- Goal 4: Build and cultivate a competent, disciplined, and resilient team equipped to deliver high quality solutions.
 - Objective 4b: Communicate strategically and transparently.

The study provides opportunities for agency technical review and involvement of the Corps established Centers of Expertise, and technical and policy expertise available through the vertical chain of command at the Alaska District, Pacific Ocean Division, and Corps Headquarters, Office of Water Policy Review, Washington D.C.

The Little Diomedede project is a unique example of sustainability, resiliency, innovation and collaboration. The project provides a solution that allows a remote and subsistence community to sustain their cultural heritage and pass along their subsistence lifestyle to future generations. The solution is designed for resiliency against the harsh climate conditions and ice floe of Little Diomedede. The remote location required innovated logistical considerations of accessing the site and how best to construct efficiently. And finally, this project displays tremendous collaboration between the Corps, the Native village, the city, and Tribal agencies to develop a holistic plan to which each stakeholder contributes.

10.4 Recommendations

I recommend that the navigational improvements at Little Diomedede, Alaska, be constructed generally in accordance with the plan herein, and with such modifications thereof as in the discretion of the Chief of Engineers may be advisable at an estimated project first cost of \$28,960,000, consisting of a Federal cost of \$26,015,000 and a non-Federal cost of \$2,945,000, provided that prior to construction the local sponsor agrees to the following:

- a. Provide, during the period of design, 10 percent of design costs allocated by the Government to commercial navigation in accordance with the terms of a design agreement entered into prior to commencement of design work for the project; and provide, during the first year of construction, any additional funds necessary to pay the full non-Federal share of design costs allocated by the Government to commercial navigation in accordance with the cost sharing as set out in paragraph b. below;
- b. Provide, during construction, 10 percent of the total cost of construction of the general navigation features attributable to dredging to a depth not in excess of 20 feet; plus 25 percent of the total cost of construction of the general navigation features attributable to dredging to a depth in excess of 20 feet but not in excess of 45 feet; plus 50 percent of the total cost of construction of the general navigation features attributable to dredging to a depth in excess of 45 feet;
- c. Pay with interest, over a period not to exceed 30 years following completion of the period of construction of the project, up to an additional 10 percent of the total cost of construction of the general navigation features. The value of lands, easements, rights-of-

way, and relocations provided by the non-Federal sponsor for the general navigation features, described below, may be credited toward this required payment. If the amount of credit exceeds 10 percent of the total cost of construction of the general navigation features, the non-Federal sponsor shall not be required to make any contribution under this paragraph, nor shall it be entitled to any refund for the value of lands, easements, rights-of-way, and relocations in excess of 10 percent of the total cost of construction of the general navigation features;

d. Provide all lands, easements, and rights-of-way, and perform or ensure the performance of all relocations determined by the Federal Government to be necessary for the construction or operation and maintenance of the general navigation features (including all lands easements, and rights-of-way, and relocations necessary for dredged material disposal facilities);

e. Accomplish all removals determined necessary by the Federal Government other than those removals specifically assigned to the Federal Government;

f. Provide, operate, maintain, repair, replace, and rehabilitate, at its own expense, the local service facilities designed for the recommended project in a manner compatible with the project's authorized purposes and in accordance with applicable Federal and State laws and regulations and any specific directions prescribed by the Federal Government;

g. Shall not use funds from other Federal programs, including any non-Federal contribution required as a matching share thereof, to meet any of the non-Federal obligations for the project unless the Federal agency providing the Federal portion of such funds verifies in writing that expenditure of such funds for such purpose is authorized;

h. Shall prepare and implement a harbor management plan that incorporates best management practices to control water pollution at the project site and to coordinate such plan with local interests;

i. Comply with all applicable provisions of the Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, Public Law 91-646, as amended (42 U.S.C. 4601-4655), and the Uniform Regulations contained in 49 CFR Part 24, in acquiring lands, easements, and rights-of-way required for construction or operation and maintenance of the general navigation features and the local service facilities, including those necessary for relocations, the borrowing of materials, or the disposal of dredged or excavated material and inform all affected persons of applicable benefits, policies, and procedures in connection with said Act;

j. Give the Federal Government a right to enter, at reasonable times and in a reasonable manner, upon property that the non-Federal sponsor owns or controls for access to the project for the purpose of operating and maintaining the general navigation features;

k. Hold and save the United States free from all damages arising from the construction or operation and maintenance of the project, any betterments, and the local service facilities, except for damages due to the fault or negligence of the United States or its contractors;

l. Keep and maintain books, records, documents, or other evidence pertaining to costs and expenses incurred pursuant to the project, for a minimum of 3 years after completion of the accounting for which such books, records, documents, or other evidence are required, to the extent and in such detail as will properly reflect total costs of construction of the general navigation features, and in accordance with the standards for financial management systems set forth in the Uniform Administrative Requirements for Grants and Cooperative Agreements to State and Local Governments at 32 Code of Federal Regulations (CFR) Section 33.20;

m. Comply with all applicable Federal and State laws and regulations, including, but not limited to: Section 601 of the Civil Rights Act of 1964, Public Law 88-352 (42 U.S.C. 2000d) and Department of Defense Directive 5500.11 issued pursuant thereto; Army Regulation 600-7, entitled “Nondiscrimination on the Basis of Handicap in Programs and Activities Assisted or Conducted by the Department of the Army”; and all applicable Federal labor standards requirements including, but not limited to, 40 U.S.C. 3141- 3148 and 40 U.S.C. 3701 – 3708 (revising, codifying and enacting without substantial change the provisions of the Davis-Bacon Act (formerly 40 U.S.C. 276a *et seq.*), the Contract Work Hours and Safety Standards Act (formerly 40 U.S.C. 327 *et seq.*) and the Copeland Anti-Kickback Act (formerly 40 U.S.C. 276c *et seq.*);

n. Perform, or ensure performance of, any investigations for hazardous substances that are determined necessary to identify the existence and extent of any hazardous substances regulated under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA), Public Law 96-510, as amended (42 U.S.C. 9601-9675), that may exist in, on, or under lands, easements, or rights-of-way that the Federal Government determines to be required for construction or operation and maintenance of the general navigation features. However, for lands that the Federal Government determines to be subject to the navigation servitude, only the Federal Government shall perform such investigations unless the Federal Government provides the non-Federal sponsor with prior specific written direction, in which case the non-Federal sponsor shall perform such investigations in accordance with such written direction;

o. Provide the non-Federal share of that portion of the costs of mitigation and data recovery activities associated with historic preservation that are in excess of 1 percent of the total amount authorized to be appropriated for the project; and

p. Assume, as between the Federal Government and the non-Federal sponsor, complete financial responsibility for all necessary cleanup and response costs of any hazardous substances regulated under CERCLA that are located in, on, or under lands, easements, or rights-of-way that the Federal Government determines to be required for construction or operation and maintenance of the general navigation features;

q. To the maximum extent practicable, perform its obligations in a manner that will not cause liability to arise under CERCLA; and

r. Comply with Section 221 of Public Law 91-611, Flood Control Act of 1970, as amended (42 U.S.C. 1962d-5b), and Section 101(e) of the Water Resources Development Act of 1986, Public Law 99-662, as amended (33 U.S.C. 2211), which provides that the Secretary of the Army shall not commence the construction of any water resources project, or separable element thereof, until each non-Federal sponsor has entered into a written agreement to furnish its required cooperation for the project or separable element.

The recommendations for implementation of navigation improvements at Little Diomedé, Alaska reflect the policies governing formulation of individual projects and the information available at this time. They do not necessarily reflect the program and budgeting priorities inherent in the local and State programs or the formulation of a national civil works water resources program. Consequently, the recommendations may be changed at higher review levels of the executive branch outside Alaska before they are used to support funding.



Christopher D. Lestochi, P.E.
Colonel, U.S. Army Corps of Engineers
District Commander

20140317

Date

**ENVIRONMENTAL ASSESSMENT
and
FINDING of NO SIGNIFICANT IMPACT**

**NAVIGATION IMPROVEMENTS
DIOMEDE, ALASKA**

**June 2014
Revised September 2014**

Prepared by
The Alaska District
U.S. Army Corps of Engineers

FINDING OF NO SIGNIFICANT IMPACT

Navigation Improvements Diomed, Alaska

The U.S. Army Corps of Engineers, Alaska District (Corps), has conducted an environmental analysis in accordance with the National Policy Act of 1969, as amended. The Final Feasibility Study and Environmental Assessment (FR/EA), dated June 2014 and revised November 2015 for Navigation Improvements, Diomed, Alaska addresses harbor and navigation improvements necessary to support subsistence activities in the remote island of Little Diomed, Alaska. The final recommendation is contained in the report of the Chief of Engineers, dated August 10, 2015.

The Final FR/EA, incorporated herein by reference, evaluated various alternatives that would improve navigation in the study area. The recommended plan includes:

- Placement of 78,400 cubic yards of associated rock for two rubble mound breakwaters;
- Excavation of a small near-shore area to -10 feet mean lower low water, requiring removal of approximately 3,000 cubic yards of material. The side slopes for the basin would be 1 Vertical (V) on 3 Horizontal (H) transitioning to a 1V on 10 H ramp.
- Excavated material from the launch area will be incorporated into the breakwater structures as fill material to the extent practicable.
- Rock will be brought in from an established quarry on the mainland.

The residents of Diomed rely on small open boats for transportation and subsistence hunting but lack a sheltered boat launching area. The village has no harbor, and boats must be launched from a rocky, unprotected shoreline at the risk of injury and property damage during even moderate wave action.

In addition to the "no action" alternative, four alternatives, similar in size, layout, and location, were evaluated for their impact on environmental resources and compliance with applicable laws and regulations, including the recommended plan. Based on an economic evaluation of alternative plan costs and economic benefits, none of the alternatives were economically justified. The recommended plan is the most cost-effective plan and the environmentally preferable alternative.

All practicable means to avoid and minimize adverse environmental effects have been incorporated into the recommended plan, including scheduling construction tasks to times of year that minimize risk to nesting seabirds and other sensitive resources. No compensatory mitigation is required.

Pursuant to section 7 of the Endangered Species Act of 1973, as amended, the Corps determined that the recommended plan may affect but is not likely to adversely affect federally listed species or their designated critical habitat that are under the jurisdiction of the U.S. Fish and Wildlife Service (FWS). The FWS concurred with the Corps' determination on June 28, 2015. The Corps determined that the recommended plan will have no effect on federally listed species or designated critical habitat under the jurisdiction of the National Marine Fisheries Service.

Pursuant to section 106 of the National Historic Preservation Act of 1966, as amended, the Corps determined that historic properties would not be adversely affected by the recommended plan. The Alaska State Historic Preservation Officer concurred with the determination on December 11, 2013.

Pursuant to the Clean Water Act of 1972, as amended, any discharge of dredged or fill material associated with the recommended plan have been found to be compliant with section 404(b)(1) Guidelines (40 CFR 230). The Clean Water Act Section 404(b)(1) Guidelines evaluation is found in Appendix 1 of the FR/EA. A water quality certification pursuant to section 401 of the Clean Water Act was obtained from the Alaska Department of Environmental Conservation, dated March 18, 2014. All conditions of the water quality certification shall be implemented in order to minimize adverse impacts to water quality.

Public review of the draft FR/EA was completed on December 6, 2013. All comments submitted during the public comment period were responded to in the Final FR/EA.

Technical, environmental, economic and cost-effective criteria used in the formulation of alternative plans were those specified in the Water Resource Council's 1983 Economic and Environmental Principles for Water and Related Land Resources Implementation Studies. All applicable laws, executive orders, regulations, and local government plans were considered in the evaluation of the alternatives. Based on these report, the reviews by other Federal, State and local agencies, Tribes, input of the public, and the review by my staff, it is my determination that the recommended plan would not significantly affect the human environment; therefore, preparation of an Environmental Impact Statement is not required.



Michael S. Brooks
Colonel, U.S. Army Corps of Engineers
District Commander

22 Dec 16
Date

Contents

1.0 PURPOSE AND NEED OF THE PROPOSED ACTION	1
1.1 Introduction.....	1
1.2 Authority	3
1.3 Proposed Action.....	3
2.0 DESCRIPTION OF ALTERNATIVES	4
2.1 No Action Alternative.....	4
2.2 Project Design Criteria and Navigation Improvement Options	4
2.3 Alternatives Considered in Detail.....	5
2.4 Recommended Alternative.....	6
2.5 Construction Considerations.....	6
2.6 Avoidance and Minimization of Environmental Impacts.....	7
3.0 EXISTING ENVIRONMENT.....	11
3.1 Community and People.....	11
3.1.1 History.....	11
3.1.2 Demographics	11
3.1.3 Economics and Infrastructure	11
3.1.4 Land Use	12
3.2 Physical Environment.....	12
3.2.1 Climate.....	12
3.2.2 Air Quality	12
3.2.3 Geology and Soils.....	12
3.2.4 Hydrology	13
3.2.5 Oceanography	14
3.2.6 Water Quality.....	15
3.3 Significant Resources.....	15
3.3.1 Terrestrial Habitat	15
3.3.2 Marine Habitat	16
3.3.3 Intertidal and Subtidal Biota	17
3.3.4 Birds.....	19
3.3.5 Mammals.....	22

3.3.6 Threatened and Endangered Species and Critical Habitat	24
3.3.7 Essential Fish Habitat	25
3.3.8 Special Aquatic Sites	25
3.3.9 Wetlands	25
3.3.10 Archaeological and Historical Resources	25
3.3.11 Subsistence Activities	28
4.0 Environmental Consequences	30
4.1 No-Action Alternative	30
4.2 Design Alternatives	30
4.3 Effects on Community and Economy	30
4.4 Effects on Air Quality and Noise	30
4.5 Effects on Geology and Hydrology	31
4.6 Effects on Oceanography and Water Quality	31
4.7 Effects on Significant Resources	31
4.7.1 Effects on Terrestrial Habitat	31
4.7.2 Effects on Marine Habitat and Near-shore Biota	32
4.7.3 Effects on Birds	32
4.7.4 Effects on Mammals	35
4.7.5 Effects on Threatened and Endangered Species	36
4.7.6 Effects on Essential Fish Habitat	38
4.7.7 Effects on Cultural and Historical Resources	38
4.7.8 Effects on Coastal Zone Resource Management	39
4.7.9 Effects on Environmental Justice	39
4.7.10 Cumulative Effects	40
4.8 Coordination and Compliance with Environmental Requirements	40
4.8.1 Relationship to Environmental Laws and Compliance	40
4.8.2 Status of Project Coordination	43
4.8.3 U.S. Fish and Wildlife Service Recommendations	45
5.0 Conclusion	45
6.0 Document Preparers	46
7.0 References	46

List of Figures

Figure 1-1. Location and vicinity of Little Diomede Island.	1
Figure 1-2. Location and vicinity of the Village of Diomede.	2
Figure 1-3. View of the village, with the existing small boat slips shown at the center of the photos, and the helipad at the extreme left.	4
Figure 2-1. Alternative N1.	7
Figure 2-2. Alternative S1.	9
Figure 2-3. Alternative S2.	8
Figure 2-4. Alternative S3.	10
Figure 3-1. Little Diomede Island, viewed from the south.	13
Figure 3-2. Bathymetry in the vicinity of Little Diomede Island (TerraSond 2007).	14
Figure 3-3. Typical boulder-field vegetation.	16
Figure 3-4. Screen-shots from the June 2007 underwater videos, showing typical near-shore marine algae.	17
Figure 3-5. Screen-shots from the June 2007 underwater videos, showing anemone-encrusted boulders (left), and a large gastropod on a sandy seafloor (right).	19
Figure 3-6. A swarm of auklets (right), and least auklets perched on a boulder (June 2007).	21
Figure 3-7. Prehistoric and historic village site at Little Diomede.	27
Figure 3-8. Map of subsistence use areas near Diomede village (adapted from Campbell 2008).	29

List of Tables

Table 3-1 Summary of Marine Fauna Observed near Diomede, 1990-1991	18
Table 3-2 Birds observed near the project site on Little Diomede, 1991	20
Table 3-3 Marine mammals in the vicinity of Little Diomede Island.	23
Table 4-1 Summary of Relevant Federal Statutory Authorities	43

Appendices

- Appendix 1: Evaluation under Section 404(b)(1) of the Clean Water Act
- Appendix 2: Essential Fish Habitat Evaluation
- Appendix 3: Correspondence

**Environmental Assessment
for
Navigation Improvements
Diomedes, Alaska**

1.0 PURPOSE AND NEED OF THE PROPOSED ACTION

1.1 Introduction

Diomede, also known as *Inalik*, is a village on the western shore of Little Diomedede Island in the middle of the Bering Strait (figure 1-1). The community has a population of about 120 people and includes members of the federally recognized tribe Native Village of Diomedede. The village is perched on an exposed rocky shoreline with no harbor, breakwater, or adequate barge landing area (figures 1-2, 1-3). Travel to and from Diomedede and the importation of goods is difficult as Diomedede has no year-round airstrip.




Figure 1-1. Location and vicinity of Little Diomedede Island.




Figure 1-2. Location and vicinity of the Village of Diomede.

Air travel is limited to an expensive seat on the weekly mail helicopter or other chartered helicopter, or to those months when a temporary airfield can be carved out of the sea ice offshore of the village. A fuel barge delivers diesel fuel once per year, and a supply barge arrives once per year, but barge operations at the village are difficult and risky (figure 1-2). A barge company that no longer provides service to Diomede lost three barges in 15 years because of navigation problems at Diomede, and companies now charge the village a cost premium for dangerous conditions, increased insurance costs, and for the possibility of having to wait for weather and sea conditions to permit delivery. Because of the lack of moorage at the village, the boats used

by residents for transportation must be limited to craft small enough to be manually hauled out of the ocean and stored on shore. Rough slips have been carved out of the shoreline boulders (figures 1-2 and 1-3), but no other protection from waves or storm surge exists. Launching these small open aluminum or skin boats from the exposed rocky shore can cause damage to the boats and be a hazard to the operators. Villagers use these small craft to travel the 26 miles to the mainland when the strait is sufficiently free of ice and when no other transportation options are available.

1.2 Authority

The authority for this General Investigation study is provided by the “Rivers and Harbors in Alaska” study resolution adopted by the U.S. House of Representatives Committee on Public Works on December 2, 1970, and the Water Resources Development Act (WRDA) of 2007, Section 2006 - Remote and Subsistence Harbors. The non-Federal Sponsors for implementation of the proposed project are expected to be the City of Diomed and the Native Village of Diomed, with financial assistance from Kawerak, Inc., the Norton Sound Economic Development Corporation, and the State of Alaska. Cost share for construction of the proposed project will be 90 percent Federal and 10 percent local.

1.3 Proposed Action

The intent of this project is to provide a basic protected launching and landing area at the community to accommodate the small craft used locally for subsistence and transport, as well as for larger rescue vessels. Previously studied concepts for navigation improvements at Diomed included larger breakwater structures and even an off-shore airfield. Those projects required the development of a source of rock at Little Diomed Island; however, studies on the creation of a rock quarry on the island revealed significant environmental and technical problems. The currently proposed alternatives assume that the rock would come from an established source on the mainland.



Figure 1-3. View of the village, with the existing small boat slips shown at the center of the photos, and the helipad at the extreme left.

2.0 DESCRIPTION OF ALTERNATIVES

2.1 No Action Alternative

The no-action alternative would leave in place the current hazards and difficulties in launching and landing small boats or rescue vessels.

2.2 Project Design Criteria and Navigation Improvement Options

The intent of the project is to provide an area of reduced wave action along the shore adjacent to the village and to limit damages to vessels trying to launch from or land on the shore. The physical limitations of the site do not allow for an entrance channel to provide protection from waves coming from all directions or for a sheltered moorage area. The launch area would need to be smoothed and widened, and the approach lane cleared of submerged boulders that might create a strike hazard in the trough of a wave.

The project alternatives were designed to accommodate two types of vessels:

- Small craft used for subsistence hunting and fishing, or for commercial fishing (approximately 20 feet long with a 7.5-foot beam and up to a 3-foot draft)
- An emergency rescue vessel capable of transporting residents to the mainland for medical care (approximately 30 feet long with a 10-foot beam and 5-foot draft)

Options considered for vessel protection included structures for off-shore mooring, a floating breakwater, and a rubble mound breakwater. An off-shore mooring system such as a dolphin

would provide larger vessels a structure to tie off to, but would not provide protection to the local fleet of small craft. A dolphin would have to be strong enough to withstand winter ice movement and would likely require regular maintenance. Difficulties were also anticipated in driving the steel pilings for a dolphin in areas of boulders and cobbles. For these reasons, the option of an off-shore mooring structure was dropped from further consideration.

A floating breakwater can provide wave protection in seas of up to 4 feet and must be anchored to the sea floor with chains or pilings. A floating breakwater would be vulnerable to damage from sea ice and would have to be removed from the water and stored on shore during much of the year. However, there is no existing place on shore to store such a large structure. Because of these practical considerations, and the fact that waves at Diomedes are frequently greater than the limits of protection provided by a floating breakwater, this option was not pursued further.

While expensive and time-consuming to build, rubble mound breakwaters have a proven performance record in arctic conditions of heavy sea ice and severe wave action. Rubble mound breakwaters have been built at Nome and St. Paul Island, and rubble mound revetment has protected the helipad at Diomedes for over a decade. For these reasons, the alternatives retained for further consideration all feature rubble mound breakwaters in different configurations to provide near-shore protection.

2.3 Alternatives Considered in Detail

A description of the wave environment at Diomedes and detailed descriptions of the four alternative designs are provided in the Corps' hydraulic design document (Ginter 2012). The two general locations for a boat landing area at Diomedes are north and south of the helipad. Residents have indicated a strong preference for the boat landing area to be located south of the helipad as that is the side from which small craft are currently launched. The racks for skin boats are also south of the helipad, as is much of the available flat, unoccupied land suitable for the lay-down, storage, and transfer of gear and cargo. A boat landing area built on the north side of the heliport may require boat operators to more frequently cross the often-turbulent waters overlying the reef that extends west of the helipad. All alternatives feature a 35-foot-wide entrance channel to maximize wave protection at the shore landing area and the dredging of a small near-shore area to clear boulders and rocky debris, but no moorage space. These alternatives were not designed as protection from storm waves, but to make launching and retrieving boats in an average wave climate safer (Ginter 2012).

Alternative N1 (figure 2-1): This alternative is the only one located north of the helipad. It would consist of two rubble mound breakwaters; the northern breakwater would be expanded to provide a boat storage area on its top surface. A small near-shore area would be dredged to 10 feet below Mean Lower Low Water (MLLW), requiring removal of approximately 2,000 cubic yards of material. The breakwaters would require approximately 73,600 cubic yards of assorted

rock. This breakwater configuration would reduce waves from the south with periods of 8 seconds or less to about a third of the wave height at the current boat launch area (Ginter 2012). The expanded northern breakwater would incorporate all rocky dredged material as fill within the boat storage area (Ginter 2013).

Alternative S1 (figure 2-2): This alternative on the south side of the helipad would consist of two rubble mound breakwaters; the base of the southern breakwater would be widened to allow for a limited boat storage area on its top surface. A small near-shore area would be dredged to -10 feet MLLW and would require the removal of approximately 3,000 cubic yards of material. The breakwaters would require approximately 62,900 cubic yards of assorted rock. This breakwater configuration would reduce waves from the north with periods of 8 seconds or less to about a third of the wave height at the current boat launch area (Ginter 2012). This alternative could incorporate little of the rocky dredged material as fill, and much of the dredged material may require disposal elsewhere (Ginter 2013).

Alternative S2 (figure 2-3): This alternative provides a little more protection than the other alternatives, but allows no boat storage surface. A small near-shore area would be dredged to -10 feet MLLW and would require removal of approximately 3,000 cubic yards of material. The breakwaters would require approximately 80,900 cubic yards of assorted rock. This breakwater configuration would reduce waves from the north with periods of 8 seconds or less to about a third of the wave height at the current boat launch area and would provide some small additional protection from waves from the west (Ginter 2012). The unmodified breakwaters in this alternative may not be able to incorporate all the rocky dredged material as fill, and much of the dredged material would require disposal elsewhere (Ginter 2013).

Alternative S3 (figure 2-4): This alternative is similar to S1, but expands the southern breakwater to allow for a large storage area on the upper surface. A small near-shore area would be dredged to -10 feet MLLW, requiring removal of approximately 3,000 cubic yards of material. The breakwaters would require approximately 78,400 cubic yards of assorted rock. This breakwater configuration would reduce waves from the north with periods of 8 seconds or less to about a third of the wave height at the current boat launch area (Ginter 2012). The expanded southern breakwater would incorporate all rocky dredged material as fill within the boat storage area (Ginter 2013).

2.4 Recommended Alternative

The Corps has identified Alternative S3 as the design that offers the most benefit to the community for the cost.

2.5 Construction Considerations

The Corps anticipates that construction would occur over 2 years. Sea ice and severe weather would limit construction activities to an estimated 100 days each year. All equipment, supplies,

and fuel would have to be brought in, primarily by barge, and logistics would need to be planned well in advance. Flat land suitable for equipment and material lay-down, and facilities for providing worker room and board, are extremely limited on the island.

The stone for the breakwaters would most likely come from a quarry near Nome; no local material source on Little Diomed Island would be developed.

The Corps expects the material dredged from between the breakwaters to consist primarily of large boulders and cobbles, perhaps with small amounts of silty sand. Boring logs from the area around the Diomed School provide the best available information on local shoreline soils. Dredging may be accomplished with land-based excavators. If the contractors encounter boulders too large to be moved or bedrock outcroppings during dredging, explosives or other means may be necessary to break up the rock. Any such use of explosives would be done on a contingency basis to address a specific problem with a boulder or outcropping, so it is difficult to speculate at this time on the size of charge, depth of placement, or other factors that would affect the environmental impact of the blast. The Corps and its contractors may explore the possibility of dredging during winter months. This would extend the effective work season and lessen some environmental concerns regarding blasting.

Expanding the breakwaters to provide storage under Alternatives N1 and S3 offers an opportunity to incorporate the rocky dredged material into the breakwater structures, thereby eliminating or greatly reducing the quantity of dredged material requiring disposal. The dredged rock, while not currently well-characterized, should be adequate to serve as general fill under the boat storage areas of the expanded breakwaters. Upland placement is not feasible for the bulk of the dredged material as accessible, flat, unoccupied land is very scarce on the island. The Corps does not expect the dredged material to be chemically contaminated. Rocky substrate is porous and subject to tidal flushing. As a result, contaminants rarely persist in these environments, especially with Bering Sea tide ranges and the scarcity of anthropogenic sources. If significant quantities of gravel or sand are collected during dredging, it may be placed upland for local use if space for such stockpiling is available, or perhaps it could be used as surfacing on the breakwater storage areas. Small quantities of excess rocky material could conceivably be placed with similar material along the shoreline. Open water disposal of the dredged material would be avoided. The baseline of the territorial sea is at MLLW at Diomed, so any non-beneficial, in-water disposal would fall under the Marine Protection, Research, and Sanctuaries Act (MPRSA), and potentially would require development of a U.S. Environmental Protection Agency (USEPA) approved disposal site.

2.6 Avoidance and Minimization of Environmental Impacts

Impacts to the environment during construction would be avoided and minimized by observing site-specific recommendations from the U.S. Fish and Wildlife Service (USFWS) and other

resource agencies (Section 4.8.1). These recommendations include selecting a construction timing window that poses the least risk of impact to sensitive resources such as bird nesting colonies (Section 4.8.2). Obtaining the rock for the breakwaters from a mainland source, rather than quarrying the rock on Little Diomedede Island (as proposed in earlier navigation improvement studies), also represents a minimization of project impacts in response to input from agencies.

To the extent practicable, the Corps would incorporate the rocky material dredged from between the breakwaters as fill in an expanded breakwater (as described under Alternatives N1 and S3). This would eliminate or greatly reduce the need for disposal of the dredged material.

The Corps will propose that an archaeological monitor be present on site at key points during construction to examine dredged material for evidence of cultural resources and to help identify existing cultural resources for avoidance during construction activities.




Figure 2-1. Alternative N1.




Figure 2-2. Alternative S1.




Figure 2-3. Alternative S2.




Figure 2-4. Alternative S3.

3.0 EXISTING ENVIRONMENT

3.1 Community and People

3.1.1 History

The community of Diomedes is a traditional Ingalikmiut Eskimo Native village with a long history of continuous habitation. The village was well-established when a Russian expedition visited the Diomedes Islands (also known as Inalik and Imaqliq) in 1728 and named them for Saint Diomedes. The community was incorporated as the City of Diomedes in 1970, but remains outside an organized borough (ADCRA 2010).

3.1.2 Demographics

As of the 2010 census, 115 people lived on Little Diomedes, with 94 percent identifying themselves as all or part Alaska Native. The population was 178 in 1990, and estimated at 110 in 2006. The community has a long history and a relatively stable population, with 146 inhabitants counted as early as 1779, but the downward trend in population noted over the last decade has been attributed to the lack of economic opportunity on the island. There has been some sentiment within the community towards relocating the village to a site on the mainland (ADCRA 2010; Ellana 1983).

3.1.3 Economics and Infrastructure

The villagers of Diomedes rely heavily on subsistence for their livelihood (described further in section 3.4). There are a limited number of employed positions in the community, and some of those are temporary or on an as-needed basis. Some villagers take temporary jobs on the mainland or in the fishing industry. Others carve ivory or make other traditional crafts for sale.

Travel between Little Diomedes and the mainland is difficult; Diomedes has no airfield and no boat harbor. The options for travel depend on the condition of the sea ice in the Bering Strait. When the sea ice becomes stable and sufficiently thick (generally, January to May), an airstrip is plowed on the surface of the ice, allowing fixed-wing aircraft to serve the community. Barges are rarely brought to Little Diomedes's exposed shoreline, so the importation of large items such as snowmachines and construction materials must sometimes await ice airstrip conditions allowing large cargo aircraft to land. Snowmachines are also used in winter to traverse the 26 miles from the village to the mainland.

A chartered helicopter travels between Diomedes and Wales once a week, carrying mail and limited freight. Light open boats with outboard motors are also used to cross the Bering Strait to the mainland. With no moorage or even a boat ramp, any watercraft used at Diomedes must be light enough to be hauled manually out of the water and up onto land for storage.

A fuel barge delivers diesel fuel once per year, and a supply barge arrives once per year to deliver dry-goods and some equipment. The village water supply consists of seasonal spring

water stored in a 434,000-gallon tank, which supplies the washeteria, clinic, and school. Individual households must haul water to their homes from outlets to this tank. The tank is filled during the spring and summer for winter use, but this water supply typically runs out around March. The washeteria is then closed, and residents are forced to melt ice and snow for several months. The washeteria, clinic, and school are served by septic systems, but all households dispose of human waste via honeybuckets. The community has no landfill or incinerator; refuse is disposed of in the ocean or in burn barrels.

3.1.4 Land Use

The severe landscape and lack of ground suitable for construction tends to limit land use on Little Diomed Island to the same use that it has seen for centuries, as a base for subsistence hunting and gathering. A few scientific organizations have explored using Little Diomed Island as a platform for meteorological and oceanographic studies.

3.2 Physical Environment

3.2.1 Climate

The climate at Little Diomed is subarctic and dominated by the movements of weather systems and sea ice through the Bering Straits. Prevailing winds are from the north and average 15 knots with gusts of 70 knots. The island receives about 10 inches of precipitation a year; fog and 30 inches of snow are common. Temperatures average from -10 to 6 degrees F in the winter to 40 to 50 degrees F in summer. The Bering Strait is generally ice-free from July through September, with maximum sea ice coverage occurring in late winter to early spring. Snow banks may persist on the island's northern slopes into July (ADCRA 2010, Gualtieri 2001).

3.2.2 Air Quality

Little Diomed presumably enjoys good air quality because of the community's isolation, the small number of pollutant emission sources, and persistent winds. The primary source of air pollutants would be the community's diesel electric generator, along with individual fuel oil stoves, and a handful of small-engine vehicles such as outboard motors and snowmachines. There is no established ambient air quality monitoring program at Little Diomed, however, and little existing data to compare with the National Ambient Air Quality Standards (NAAQS) established under the Clean Air Act (CAA). These air quality standards include concentration limits on the "criteria pollutants" carbon monoxide, ozone, sulfur dioxide, nitrogen oxides, lead, and particulate matter. The city is not in a CAA "non-attainment" area, and the "conformity determination" requirements of the CAA would not apply to the proposed project at this time (ADCRA 2011, ADEC 2010).

3.2.3 Geology and Soils

The flat-topped shape of Little Diomed Island is attributed to either the result of lava extruding through an ice sheet (a *tuya*) or the remains of an uplifted marine terrace that has been eroded and weathered by frost cycles in the subarctic climate. The island is roughly 2.7 square miles,

much of which is a relatively flat plateau, 1,150 to 1,190 feet above sea level (figure 3-1). The island's margins range from sheer rocky cliffs to steep slopes studded with boulders and granite outcroppings. The island consists primarily of a medium to coarse-grained Cretaceous granite called the Diomedea Pluton, which is believed to be of the same age and type as found at Big Diomedea Island, King Island, and western portions of the Seward Peninsula (Gualtieri 2001). A seismic survey conducted in 2007 revealed an overburden layer estimated to vary from 1 to 18 feet thick overlying weathered granite bedrock. The overburden consisted of boulders with gravel, sand, and silt filling the voids in between (R&M 2007). What little surface soil is present is augmented with guano from the island's large seabird colonies and decomposing vegetation. Surface boulders are heavily encrusted with lichens, which are presumably weathering the stone and contributing to soil formation.

The village occupies a small bench of relatively flat land along the island's western shore. The shoreline is made up of boulders and large cobbles, with no sand or silt beach apparent anywhere. The boulders and cobbles continue offshore and compose much of the near-shore sediments. The submerged boulders have a smooth rounded or subangular appearance, suggesting that they may be frequently tumbled about by ice movement and strong currents. A rocky reef extends hundreds of feet westward from the point occupied by the village. It is unclear whether the reef is made up entirely of boulders or is underlain by a bedrock dike. Broad, flat areas of sand exist to the north and south of the reef, but it is not known how far these extend (Floyd and Hoffman 2007).



Figure 3-1. Little Diomedea Island viewed from the south.

3.2.4 Hydrology

Little Diomedea Island does not possess a true aquifer or persistent bodies of fresh water. However, melting snow and ice percolate through the talus and boulder fields to emerge as springs and transient streams. Treated water from one such spring is collected over the summer

and stored in a 434,000-gallon holding tank at the village. This water supply typically lasts the community until March (DCRA 2010).

3.2.5 Oceanography

The Diomede Islands are in the Bering Strait, which is the sole conduit between the Bering Sea/Pacific Ocean and the Arctic Ocean. The relatively shallow (with maximum depths of about 165 feet below mean sea level) strait is about 50 miles across at its narrowest point. An enormous volume of water, calculated to be 380 to 595 cubic miles, flows annually through the strait, primarily northward from the Pacific Ocean into the Arctic Ocean. This migration of nutrient-rich oceanic water into the Arctic drives much of the productivity of the Chukchi Sea and Arctic Ocean (Cooper 2006). The northward current varies from 1 to 3 knots; the current at the surface can be increased by winds from the south and slowed or even reversed by strong northerly winds. The tides at Diomede are not substantial, with only about 12 inches difference between Mean Higher High Water and Mean Lower Low Water.

Little Diomedede and Big Diomedede Islands are themselves separated by a strait roughly 2.5 miles wide. The islands are created by separate uplift plateaus, and the seafloor drops away rapidly from their coastlines to a depth of roughly 100 to 150 feet below mean sea level in the inter-island strait (figure 3-2; Cooper 2006; TerraSond 2007). A rocky reef extends several hundred yards into the strait from the western point of Little Diomedede Island occupied by the village. The general northerly flow in the Bering Strait creates a strong current running between the islands. Where this current interacts with the reef, a broad area of turbulence with visible upwelling is often evident in the waters offshore of the village.




Figure 3-2. Bathymetry in the vicinity of Little Diomedede Island (TerraSond 2007).

The Bering Strait is generally covered with ice between mid-December and mid-June. Whereas most of the winter ice in Bering Strait is mobile floe ice, the waters between Little and Big Diomedes Islands will typically freeze solid, forming a fixed, stable body of ice 6 to 10 feet thick (Cooper 2006).

During the months of open water, stormy conditions affecting wave height are common. Waves less than 2 feet in height occur only 2 to 3 days per month. The significant wave height for a 50-year storm is estimated to be 11.5 feet, with major storms coming from either the north or the south. The lack of shallows or protective shoals around the island leaves its shoreline vulnerable to the brunt of Bering Sea storms.

The Corps' hydraulic design (Ginter 2012) studied the wave environment at Little Diomedes. The average wave climate in the area of the Diomedes Islands is dominated by waves from the north and from the south. Wave heights between 0.3 to 3.2 feet dominate the wave climate in June and July. By August the climate is fairly evenly split between the north and south for all wave heights evaluated, and by September and October the wave dominance has switched to the north along with an increase in the percentage of occurrence of the larger waves (3.3 to 6.6 feet).

3.2.6 Water Quality

Little direct information exists on general water quality at Little Diomedes Island. There is a prevailing northerly flow of ocean water through the Bering Straits, which is readily apparent as a strong current in the pass between Little Diomedes and Big Diomedes islands. This rapid movement of water, and the lack of protected bays or coves along the Little Diomedes coastline, suggests that the water quality in the Little Diomedes near-shore waters probably reflects that of the Bering Sea in general, with little opportunity for localized degradation of coastal water through oxygen depletion or sedimentation. This is supported by physical measurements, such as salinity, collected at Little Diomedes as part of regional studies of Bering Sea conditions (Cooper 2006). Current practices of disposing of solid waste in near-shore waters might lead to localized degradation under certain circumstances. The coastal waters are not known to have been evaluated against State of Alaska water quality standards (ADEC 2009).

3.3 Significant Resources

3.3.1 Terrestrial Habitat

The terrestrial habitat on Little Diomedes Island consists largely of boulder fields, cliffs, and rocky spires. Vegetation is limited to a very low mat of mosses, grasses, and forbs growing amongst the exposed boulders and rock outcroppings (figure 3-3). Locally significant species include salmonberry (*Rubus spectabilis*), Eskimo potato (probably *Claytonia tuberosa*), and edible forbs (referred to generally as "greens") identified as brook saxifrage (*Saxifraga punctata*), mountain sorrel (*Oxyria digna*), and sourdock (*Rumex arcticus*; Jarvenpa and Brumback 2006). Most boulders are heavily encrusted with lichens.



Figure 3-3. Typical boulder-field vegetation.

As discussed in subsequent sections, nesting seabirds are the dominant animal life using the Little Diomedede terrestrial habitat. Arctic fox are the only mammal known to regularly use the island's interior, and they are presumably present mostly in spring and summer, drawn by the abundance of eggs and ground-nesting birds.

3.3.2 Marine Habitat

Large boulders and cobbles characterize the shoreline, intertidal, and near-shore habitat. The formation and movement of sea-ice strongly affects this habitat, and limits the colonization of rock faces as deep as 10 feet below the surface. No vegetation is present along the boulder-covered shoreline. Offshore, marine algae are able to grow amongst the boulders where they are sheltered against the worst of the local currents. An underwater video survey in 2007 showed short tufts of a dark filamentous algae growing on the sides of submerged boulders and bladed kelp (*Laminaria* sp.) emerging from gaps between the boulders (figure 3-4). At depths where the boulders are not subject to ice-scouring, they support dense growths of anemones and other epilithic organisms. As the distance from the shoreline increases, flat patches of sand or pulverized shell appear amongst the boulders, and broad areas of sand are present several hundred feet offshore.




Figure 3-4. Screen-shots from the June 2007 underwater videos, showing typical near-shore marine algae.

3.3.3 Intertidal and Subtidal Biota

The intertidal zone at Little Diomed Island is narrow and sparsely inhabited. Shoreline boulders and cobbles are subjected to ice-scouring and severe temperatures much of the year, which discourages multi-year growth. A Corps survey in 2007 noted only a few *Littorina* marine snails and very small barnacles occupying the shoreline boulders in the intertidal zone.

The marine environment just offshore of Diomed was assessed by Alaska Department of Transportation and Public Facilities (DOTPF) geologist Hal Livingston during dives made in 1990 and 1991 (McIntosh 1992). Livingston described the bottom as consisting of several layers of coarse cobbles and boulders, up to 15 feet in diameter, nested on one another with small materials absent between the boulders. One exception was a 20-foot-diameter area composed of pulverized barnacle shells. Kelp and barnacles were common on all boulders to a depth of 40 feet, the maximum depth of his dive. Kelp holdfasts were rooted in the barnacles and occasionally in mussels that covered the boulders. All boulders in waters shallower than 30 feet had been scraped clear of epilithic organisms on their topmost surfaces by ice keels of the pressure ridges in sea ice. Marine organisms observed during Livingston's 1990 and 1991 dives are listed in Table 3-1

Corps of Engineers biologists conducted a survey with a surface-operated underwater video camera in June 2007. Swift currents and equipment limitations prevented observations as detailed as the 1990 and 1991 surveys, but the 2007 videos covered a broader area and essentially corroborated observations on environment and biota from the 1990-1991 dive surveys. One of the more complete underwater video transects began in 8 feet of water about 40 feet offshore of the village boat slip. The bottom initially consisted of large boulders encrusted with tufts of a green filamentous algae, small barnacles, and blades of kelp-like algae growing in the crevices. At a depth of approximately 15 feet, a thicker growth of kelp (*Laminara* sp.) appeared with blades long enough to conceal most of the boulders.

Table 3-1. Summary of Marine Fauna Observed near Diomede, 1990-1991

Major Taxa Observed	Scientific Name(s)	General Description
Cnidarians: - Hydrozoa	Family <i>Sertularidae</i>	Multibranched hydroid attached to boulders.
- Scyphozoa	<i>Cyanea capillata</i>	Jellyfish.
- Anthozoa	<i>Meretridium senile</i>	Sea anemone (tall stalked).
- Anthozoa	<i>Cribrinopsis fernaldi</i>	Sea anemone (squat, multi-colored to 10 in).
Platyhelminthes: - Turbellaria	Order <i>Polycladia</i>	Marine flatworm.
Mollusks - Polyplacophora	<i>Tunicella insignis</i>	Chiton.
- Gastropoda	<i>Lunatia lewisii</i>	Marine snail, 1 in.
- Gastropoda	<i>Succinum</i> spp.	Marine snail.
- Bivalvia	<i>Modiolus modiolus</i>	Horse mussel, 3-5 in.
Annelids: - Polychaeta	<i>Pectinaria granulata</i>	Conical sand-tube constructing marine worms, 1 in.
Crustaceans: - Malacostraca	Superfamily <i>Paguroidea</i>	Hermit crabs, small.
- Malacostraca	<i>Temessus chiragonus</i>	Crab.
- Cirripedia	Unidentified	Barnacles, small, found near-shore.
- Cirripedia	Unidentified	Barnacles, large, deep-water.
Echinoderms: - Echinoidea	<i>Strongylocentrotus franciscanus</i>	Green sea urchin, 2 in.
- Asteroidea	<i>Henricia sanginolenta</i> (?)	Seastar, five-armed, 6-8 in.
Osteichthyes: - Unidentified	Unidentified	Unidentified silvery fish, 1-2 in., in large schools.
- Cottidae	<i>Hemilepidotus hemilepidotus</i>	Red Irish lord, 12 in.

Adapted from McIntosh 1992.

The first anemones (*Meretridium senile*) appeared as the kelp began to thin out at a depth of approximately 22 feet. By 31 feet in depth, large numbers of squat, pale anemones (*Urticina* sp.; figure 3-5) could be seen on the boulders, along with a few *Evasterias* sea stars, *Meretridium* anemones, dense barnacles, and sparse patches of kelp. The sea floor began transitioning to a pale, flat sandy or silty bottom with scattered boulders at a depth of around 57 feet. A large crab, perhaps a lithodid, was seen at a depth of 63 feet; this was the only crab observed on any of the transects. The widely spaced boulders were still colonized by *Meretridium* and other anemones, and a large gastropod (resembling *Calliostoma* sp.; figure 3-5) was visible on a cobble. At a depth of 82 feet, the bottom was flat and shelly, with no boulders visible. The transect ended at a distance of 1,420 feet from shore at a depth of 82 feet (Floyd and Hoffman 2007).

As part of the 2007 survey, the Corps attempted to collect sediment samples from a broad sandy area about 700 feet southeast of the helipad. The small hand-operated dredge performed poorly in the strong current, but one sample contained numerous small bivalve shells, probably from *Hiatella arctica*, and pectinariid polychaetes. The pectinariids had constructed their characteristic conical tubes with grains of reddish sand. Another sample contained a few small live bivalves (*Macoma* sp.), a number of different small motile polychaetes, a possible sedentary polychaete in a long, thin leathery tube (too badly damaged to identify), and bluish weathered shell fragments from a species of large barnacle (Floyd and Hoffman 2007).




Figure 3-5. Screen-shots from the June 2007 underwater videos, showing anemone-encrusted boulders (left), and a large gastropod on a sandy seafloor (right).

Other marine organisms known or believed likely to be present in Little Diomede near-shore waters include blue king crab (*Paralithodes platypus*), tanner crab (*Chionoecetes opilio*), mysid shrimp (*Mysis* spp.), capelin (*Mallotus villosus*), Pacific herring (*Clupea harengus pallasii*), Pacific cod (*Gadus macrocephalus*), Arctic cod (*Boreogadus saida*), saffron cod (*Eleginus gracilis*), and Pacific sand lance (*Ammodytes hexaptera*). Approximately 300 species of fish are found in the Bering Sea and may be expected around the Diomede Islands. Bering Sea fishes have two distinct groups, those indigenous to cold arctic water temperatures and found in the northern Bering Sea, and the subarctic Pacific group, which is dominant throughout most of the Bering Sea (McIntosh 1992).

3.3.4 Birds

A survey of birds at Little Diomede Island between May 29 and August 28, 1991 found a total of 31 species (summarized in table 3-2). A number of additional species, such as the black guillemot (*Cepphus grylle*), sandhill crane (*Grus canadensis*), and snowy owl (*Nyctea scandiaca*) have been reported in the local subsistence take and may nest or be present on the island during various times of the year.

The steep boulder-studded slopes, rocky cliffs, rich surrounding waters, and relatively low predator pressure at Little Diomede Island create important breeding habitat for millions of seabirds, including auklets, kittiwakes, puffins, murre, and cormorants. The U.S. Fish and Wildlife Service (USFWS) publication “Catalog of Alaskan Seabird Colonies” (Sowls 1978) lists 13 species of seabirds as nesting at Little Diomede. The island is the site of the largest

Table 3- 2. Birds observed near the project site on Little Diomede, 1991

Taxa of Species Observed	Common Name	Spring	Summer	Fall	Frequency	Observed Nesting?
Procellariidae: - <i>Fulmarus glacialis</i>	northern fulmar	•			?	No
Phalacrocoracidae: - <i>Phalacrocorax pelagicus</i>	pelagic cormorant	•	•	•	C	Yes
Anatidae: - <i>Somateria mollissima</i>	common eider	•			?	No
- <i>S. spectabilis</i>	king eider	•			?	No
- <i>Histrionicus histrionicus</i>	harlequin duck	•			?	No
- <i>Clangula hyemalis</i>	long-tailed duck	•			?	No
- <i>Mergus serrator</i>	red-breasted merganser	•			?	No
Falconidae: - <i>Falco peregrinus</i>	peregrine falcon	•	•	•	U	Yes
Scolopacidae: - <i>Calidris mauri</i>	western sandpiper			•	?	No
- <i>C. melanotos</i>	pectoral sandpiper			•	?	No
- <i>C. alpina</i>	dunlin	•			?	No
Laridae: - <i>Larus hyperboreus</i>	glaucous gull	•	•	•	C	Yes
- <i>Rissa tridactyla</i>	black-legged kittiwake	•	•	•	C	Yes
Alcidae: - <i>Alle alle</i>	dovekie	•	•	•	U	Probable but unconfirmed in 1991 and 2007
- <i>Uria aalge</i>	common murre	•	•	•	C	Yes
- <i>U. lomvia</i>	thick-billed murre	•	•	•	C	Yes
- <i>Cephus columba</i>	pigeon guillemot	•	•	•	C	Yes
- <i>Cyclorhynchus psittacula</i>	parakeet auklet	•	•	•	C	Yes
- <i>Aethia pusilla</i>	least auklet	•	•	•	C	Yes
- <i>A. cristatella</i>	crested auklet	•	•	•	C	Yes
- <i>Fratercula cirrhata</i>	tufted puffin	•	•	•	C	Yes
- <i>F. corniculata</i>	horned puffin	•	•	•	C	Yes
Corvidae: - <i>Corvus corax</i>	raven	•	•	•	C	Yes
Muscicapidae: - <i>Phylloscopus borealis</i>	arctic warbler	•	•	•	U	Yes
- <i>Oenanthe oenanthe</i>	northern wheatear	•	•	•	U	Yes
Motacillidae: - <i>Motacilla flava</i>	yellow wagtail	•	•	•	?	No
- <i>M. alba</i>	white wagtail	•	•	•	?	No
- <i>Anthus cervinus</i>	red-throated pipit	•	•	•	C	Yes
Ernberizidae: - <i>Calcarius lapponicus</i>	Lapland longspur	•	•	•	C	Yes
- <i>Plectrophenax nivalis</i>	snow bunting	•	•	•	C	Yes
Fringillidae: - <i>Carduelis</i> spp.	redpoll	•	•	•	U	Yes

Adapted from McIntosh 1992

Frequency of occurrence: C = Common; U = Uncommon; ? - Unknown.

colony of black-legged kittiwakes (*Rissa tridactyla*) in the northern Bering Sea and hosts the largest population of auklets in Alaska. It may also be the only nesting area of the dovkie (*Alle alle*) within the United States (McIntosh 1992).

Least auklets (*Aethia pusilla*; figure 3-6) and crested auklets (*A. cristatella*) nest under boulders on the talus-covered slopes, while parakeet auklets (*Cyclorhynchus psittacula*) and puffins (*Fratercula* spp.) dig burrows in the vegetated slopes or nest in rock crevices. The steep cliffs provide excellent nesting conditions for cliff-nesting birds such as murres (*Uria* spp.), black-legged kittiwakes, and pelagic cormorants (*Phalacrocorax pelagicus*).



Figure 3-6. A swarm of auklets (right), and least auklets perched on a boulder (June 2007).

Seabird use of Little Diomed Island is seasonal. Migration to the island begins with the breakup of sea ice in April and continues until mid-June. Common (*Uria aalge*) and thick-billed (*Uria lomvia*) murres, black-legged kittiwakes, and pigeon guillemots (*Cephus columba*) have been reported offshore by the end of May, but the birds may not begin congregating on the island slopes until June. Auklet species may appear by mid-May and start exploring the island slopes by the end of May.

The timing of egg-laying on Little Diomed Island depends upon the pace of ice breakup and the availability of food, and by the availability of nest sites, which may vary from year to year due to snow cover. A 1991 field study of seabirds at Little Diomed Island (Fowler 1991) estimated a median egg-laying date of July 9 for crested auklets and July 4 for least auklets. The first black-legged kittiwake and murre eggs may be seen on cliffs by the end of June. The first black-legged kittiwake chicks were observed on Little Diomed Island cliffs on July 24; the first murre chicks were seen on July 31. The median hatch date was estimated to be August 11 for crested auklets and August 4 for least auklets. Murre chicks appeared to fledge around August 20, and adult murres were observed escorting young off the cliffs on the evening of August 27.

Based upon median nestling periods of 29 and 33 days for crested and least auklets, respectively, Fowler (1991) estimated the median fledging dates of crested auklets and least auklets to occur on September 13 and September 4, respectively. Black-legged kittiwakes were also thought to fledge by early September (Fowler 1991, McIntosh 1992).

The USFWS and the Corps conducted an additional bird survey in June 2007, with the specific goal of observing bird behavior during geotechnical seismic testing at two proposed quarry sites. The 2007 survey was a qualitative assessment of bird distribution and habitat based on foot surveys conducted at two elevations through each potential quarry area and during seismic monitoring efforts. As expected, in both the north and south quarry areas, auklet density was greatest on rocky substrates and lowest in vegetated areas, with very few birds observed in grassy areas. Smaller patches of boulders surrounded by vegetation appeared to be used more by least auklets, where rocks were small, and by parakeet auklets, where rocks were larger. In general, the amount of rocky substrate and, therefore, the number of auklets, was higher at the southern quarry site. The small (one-third pound) seismic charges created dramatic flushes of birds from the island slopes. In one observation, 10,000 or more auklets, probably all or most birds within 500 meters of the blast, left the slope in response to the detonation. Some returned to the slope almost immediately after the blast, although most appeared to have returned within 3 to 4 minutes, and after 10 minutes, activity levels appeared similar to pre-blast conditions. At another location, an observer noted that gulls and puffins were also flushed from lower slopes and rocky shoreline areas by the blasts. The puffins began returning to the slope within 1 to 3 minutes after the blast, but the kittiwakes and gulls flew 300 to 500 meters offshore and landed on the water, where they remained until after the second blast. They did not return to the island for at least a half-hour after the second blast (Zelenak 2007).

Boat surveys also indicated that more birds used the lower slope and shoreline of the south quarry site than the north (150 to 200 pigeon guillemots and 120 to 140 black-legged kittiwakes at the south site versus 5 guillemots and 5 to 15 kittiwakes at the north site). Kittiwakes were associated with the southern end of the south quarry area, in proximity to the cliffs just to the south of the quarry area. Smaller numbers of horned and tufted puffins and pelagic cormorants also were observed near the south end of the southern quarry site, and several common murrelets were observed on or over the water adjacent to the north quarry site.

3.3.5 Mammals

The Bering Strait provides the only passage for several marine mammal species that migrate between the Bering Sea and the Chukchi and Beaufort Seas. The concentration of nutrients and shallow depths within the Bering Strait provide unusually abundant, diverse, and accessible populations of marine invertebrates and fish for marine mammals to feed upon. Table 3-3 lists marine mammals known to appear around Little Diomedede Island. Many of these species are considered endangered or threatened, and are discussed further in a subsequent section. Other

species include the gray (*Eschrichtius robustus*), sei (*Balaenoptera borealis*), minke (*B. acutorostrata*), and beluga whales (*Delphinapterus leucas*); the Pacific walrus (*Odobenus rosmarus*); and several seals, including the ringed (*Phoca hispida*), spotted (*P. largha*), and bearded (*Erignathus barbatus*), also occur near Little Diomede. Gray whales commonly occur in the vicinity throughout the spring, summer, and fall months. Little Diomede Island is a known haul-out area for concentrations of Pacific walrus (McIntosh 1992).

Table 3-3. Marine mammals in the vicinity of Little Diomede Island

Scientific Name	Common Name	Spring	Summer	Fall	Winter	Frequency _b
Order: Cetacea						
Family: Balaenidae - <i>Balaena mysticetus</i>	bowhead	•		•		C
Family: Balaenopteridae - <i>Balaenoptera musculus</i>	blue whale		•			R
- <i>B. physalus</i>	fin whale		•			U
- <i>B. borealis</i>	sei whale		•			U
- <i>B. acutorostrata</i>	minke whale		•			U
- <i>Megaptera novaeangliae</i>	humpback whale		•			U
Family: Eschrichtiidae - <i>Eschrichtius robustus</i>	gray whale	•	•	•		C
Family: Monodontidae - <i>Delphinapterus leucas</i>	beluga	•		•		C
Family: Delphinidae - <i>Orcinus orca</i>	killer whale		•	•		C
Family: Phocoenidae - <i>Phocoena phocoena</i>	harbor porpoise		•			U
Order: Pinnipedia						
Family: Phocidae - <i>Phoca hispida</i>	ringed seal	•	•	•	•	C
- <i>P. fasciata</i>	ribbon seal		•	•		U
- <i>P. largha</i>	spotted seal		•	•		C
- <i>Erignathus barbatus</i>	bearded seal	•	•	•	•	C
Family: Otariidae - <i>Eumetopias jubatus</i>	Steller sea lion	•	•			U
Family: Odobenidae <i>Odobenus rosmarus</i>	Pacific walrus	•	•	•		C
Order: Carnivora						
Family: Ursidae <i>Ursus maritimus</i>	polar bear	•			•	C

Adapted from McIntosh 1992.

Frequency: C = Common; U = Uncommon; R = Rare

The only terrestrial mammal known to occur on Little Diomede is the arctic fox (*Alopex lagopus*), which is known to roam the sea ice many miles from shore. This small fox is an efficient predator on the eggs and young of seabirds (ADFG 2010).

3.3.6 Threatened and Endangered Species and Critical Habitat

On May 14, 2008, the polar bear (*Ursus maritimus*) was listed as threatened under the Endangered Species Act (ESA). Polar bears occur in the vicinity of and have denned on Little Diomede Island (McIntosh 1992). Critical habitat was designated for polar bears on November 24, 2010. At Diomede, critical habitat includes the island itself, a 1-mile “no disturbance zone” surrounding the island, as well as all sea ice, regardless of seasonal presence, out to the international border.

Little Diomede Island is within the migratory ranges of spectacled eiders (*Somateria fischeri*) and Steller’s eiders (*Polysticta stelleri*), both of which are listed as threatened under the ESA. Neither species breeds, molts, or overwinters at Little Diomede, nor are they known to stop-over in the vicinity of the island during migration. Critical habitat is not designated near Diomede for either spectacled or Steller’s eiders (McIntosh 1992).

Several endangered species of whales under the jurisdiction of the National Marine Fisheries Service (NMFS) may occur in the waters around the island during certain seasons of the year. These include the bowhead (*Balaena mysticetus*), humpback (*Megaptera novaeangiae*), fin (*Balaenoptera physalus*), and blue whales (*B. musculus*). Bowhead whales can be found in the area during migration from late March to May and from September to December. Humpback, fin, and blue whales may occur in the area from June through September (NMFS 2013a)

Bearded seals (*Erignathus barbatus*) and ringed seals (*Pusa hispida*) in the Arctic Ocean and adjacent Pacific Ocean waters (i.e., the Bering Sea) were listed by the NMFS as threatened under the ESA in December 2012. These “ice seal” species are regarded to be at heightened risk from climate change and changes in sea ice formation and distribution patterns. Critical habitat designations by the NMFS for these species are pending (NMFS 2013b).

The endangered Steller sea lion (*Eumetopias jubatus*) might occasionally be found in the area, but haul-outs and rookeries are not documented on Little Diomede Island, and no critical habitat areas are designated north of St. Lawrence Island, more than 100 miles to the south (NMFS 2013c).

The USFWS listed the Pacific walrus (*Odobenus rosmarus*) as a candidate species under the ESA in February 2011. The status of candidate species under the ESA are reviewed annually, and the USFWS has until October 2017 to propose the Pacific walrus as either threatened or endangered, or to remove it from candidate status. The current size of the Pacific Walrus population and its population trends are not known with any certainty: A 2006 aerial survey conducted by the USFWS estimated the population at 129,000, but, due to the difficulties in counting walruses, the confidence of that estimate is low and the possible range in population size is between 55,000 and 507,000. The population is believed to have increased between 1960 and 1980, and may have reached their environment’s carrying capacity. By the 1990s, the

population was believed to be stable or declining, and current trends are unclear but appear to be downward (ADFG 2013). Walrus need to haul out of the ocean onto ice or shore more frequently than seals, and the USFWS believes that this makes walrus more vulnerable to the loss of sea ice through climate change (USFWS 2011a, 2011b). Walrus in the Bering Straits region are co-managed by the USFWS and the Eskimo Walrus Commission (EWC; Kawerak 2013). The EWC was established in 1978 to represent coastal walrus hunting communities in Alaska, and has a cooperative management agreement with the USFWS for the conservation and management of walrus. The Alaska Department of Fish and Game (ADFG) and the U.S. Geological Survey (USGS) also participate in walrus research and management efforts (ADFG 2013).

3.3.7 Essential Fish Habitat

The National Marine Fisheries Service designated the waters surrounding Little Diomed Island as essential fish habitat (EFH) for “snow crab” (*Chionoecetes* spp.) and saffron cod (*Eleginus gracilis*; NOAA 2013d).

There are no Habitat Areas of Particular Concern (HAPC) near Little Diomed. The nearest HAPC is at Bower’s Ridge in the Bering Sea, more than 700 nautical miles southwest of Little Diomed. The island falls within the areas of both the Arctic Fisheries Management Plan and Crab Management Plan (NOAA 2013d).

3.3.8 Special Aquatic Sites

The U.S. Environmental Protection Agency (EPA) identifies six categories of special aquatic sites in their Clean Water Act Section 404 (b)(i) guidelines: Sanctuaries and refuges, wetlands, mudflats, vegetated shallows, coral reefs, and riffle and pool complexes. None of these categories appear to exist at the Little Diomed Island project site.

3.3.9 Wetlands

Little Diomed Island is not known to have been formally evaluated for wetlands; however, the steep slopes, very coarse substrate, and lack of vegetation along the island shoreline strongly suggest conditions that are unsuitable for the development of typical wetland soils or plant communities in the project area.

3.3.10 Archaeological and Historical Resources

Human use of Little Diomed Island goes back several thousand years, and its location in the center of the Beringia region between Asia and North America suggests that it may have been occupied continuously by several successive cultures as a hunting and trading center. Contact with European explorers began as early as 1648. As recently as the mid-1800s, the village at Little Diomed Island was reportedly located on a long sand or gravel spit extending westward toward Big Diomed Island; the rocky reef just off the village is presumably a remnant of this feature. Burials at that time were performed on Little Diomed Island about where the current

village is situated. As the spit eroded away or was otherwise submerged, the village moved to the rocky rim of the island (Potter 2002).

The Corps' 2007 underwater video survey at Little Diomedé included an examination of the near-shore reef area, looking for any evidence of past habitation. No such evidence was found. The reef area surveyed consisted of large tumbled boulders indistinguishable from the rest of the Little Diomedé near-shore environment. The video survey of the reef did spot a large timber projecting up from between the boulders. However, the timber appeared to be a weathered remnant of dimensional lumber and was located in waters shallow enough that sea ice should have sheared it off; therefore, the timber was reasoned to have been somehow wedged in the boulders since the previous winter and not associated with the old village site (Floyd and Hoffman 2007).

The Alaska Heritage Resources Survey (AHRs) identifies the broader prehistoric and historic village site at Little Diomedé as TEL-00014 (or 3330-6 Ignaluk). This site covers all prehistoric and historic cultural features and artifacts in the vicinity of the present-day village and extends to any offshore features that may remain on the submerged reef (Potter 2003; figure 3-8). Cultural deposits, including middens, caches, and former dwelling sites, have been excavated in the village and are believed to be scattered through the general village area, reflecting its many centuries of occupation. Artifacts and human remains are occasionally found on the surface, having eroded out of the soil or been exposed by construction work or other activities (Potter 2002). The State Historic Preservation Officer (SHPO) determined this site to be eligible for inclusion in the National Register of Historic Places (NRHP) in 2003.




Figure 3-7. Prehistoric and historic village site at Little Diomede

Much of the coarse shoreline material within TEL-00014 has been disturbed by construction of the school, helipad, and other infrastructure. Portions of the shoreline south of the helipad are occasionally reworked with heavy machinery to repair storm erosion and provide relatively level areas for storage and barge off-loading. Potter (2003) delineated an area of TEL-00014 (figure 3-7) in which the ground has been sufficiently disturbed or covered by extraneous materials that future surface disturbances are unlikely to adversely affect undiscovered cultural resources.

Most other AHRs-cataloged features are historic structures within the TEL-00014 area. These include the remains of a traditional semi-subterranean house called a *kugeri* (TEL-00054) located

in the village. The upper part of this structure was demolished in 1996, but subsurface portions are believed to remain, and the site is eligible for inclusion in the NRHP. Another eligible building in the village is the Federal Scout Readiness Center (TEL-00214), built in 1960 as a military observation post and still in use. Several other structures in the village have been cataloged in the AHRS, but were determined to be not eligible for inclusion in the NRHP.

3.3.11 Subsistence Activities

The residents of Diomedede continue a heavy reliance on subsistence. Major subsistence resources include walrus, seals, whales, and seabirds. Walrus are a principle target species that provide large quantities of meat, as well as skins for the traditional open boats (*umiaks*), and ivory for handicrafts. Migrating walrus are hunted from boats along the sea ice edge in spring and fall. In May and June, females and sub-adults migrate north with the receding sea ice past the Diomedede Islands. In October and November, the migration reverses as walrus follow the ice edge south. Depending on weather, sea, and ice conditions, the opportunities for a successful hunt during a given migration period may be limited. Heavy surf at the Little Diomedede landing site may keep hunters from launching their boats or make it difficult and dangerous to come ashore. The number of walrus harvested each year has been variable over the last several decades, ranging from 532 in 1991 to 8 in 2011. In general, the annual harvest at Diomedede appears to be trending downward. It is unknown if this is due to lower numbers of walrus available, less frequent hunting opportunities, or other variables (Richardson 2012).

Ice seals such as bearded, spotted, and ringed are also hunted along the ice edge, as well as from the shore of Little Diomedede Island (figure 3-8). A small number of beluga whales are taken, probably from boats during the whales' migration through the Bering Strait (Magdanz 1981; Campbell 2008).

The villagers harvest both meat and eggs from the extensive seabird colonies on Little Diomedede. Eggs are collected from nests on the talus slopes and accessible cliffs for a relatively brief period lasting about 7 to 10 days; eggs are not collected once the embryo starts to form. The larger murre eggs are preferred, but eggs from auklets, puffins, cormorants, kittiwakes, and guillemots are also collected. Adult birds, particularly auklets, are caught in long handled nets by hunters concealed in stonework "bird blinds" built along trails traversing the steep slopes (Campbell 2008).

Most fishing and crabbing takes place in the winter and spring through leads in the sea ice offshore of the village (figure 3-8). Most crabs are caught in waters 60 to 100 feet deep, roughly 250 to 300 feet offshore. The villagers once gathered seaweed and caught fish from the shoreline immediately south of the village, but that area is no longer used for subsistence due to concerns about contamination from septic systems and household waste (Campbell 2008).

Villagers gather plant materials during the short growing season, including berries, Eskimo potatoes, Eskimo cabbage, and greens (Campbell 2008).




Figure 3-8. Map of subsistence use areas near Diomedede village (adapted from Campbell 2008).

4.0 Environmental Consequences

4.1 No-Action Alternative

The no-action alternative would avoid the direct and indirect environmental impacts described below, but would leave in place the current hazards and difficulties in launching and landing small boats or rescue vessels. In addition, the no-action alternative would forgo any potential environmental benefits from a safer vessel landing area, such the reduced risk of fuel spills.

4.2 Design Alternatives

Of the four design alternatives discussed in section 2, the three located south of the helipad (S1, S2, and S3) differ slightly in layout and the size of the filled areas, but all occupy the same general location, would require the same construction practices, and would provide approximately the same degree of improved boat access; therefore, the discussions of consequences below will generally not distinguish between the three southern alternatives. The one alternative located north of the helipad (N1) would have larger breakwaters and require a broader area to be dredged than the south alternatives.

4.3 Effects on Community and Economy

The proposed boat landing area would not significantly change the types of watercraft operated by village residents or the activities for which they are used. The primary consequence would be to increase the number of days local watercraft could be safely launched and retrieved. The alternatives on the south side of the heliport (S1, S2, and S3) would protect against waves from the north, which predominate during the fall hunting season. This may increase subsistence hunting success as a result of providing a safer launch. A 2007 survey of Diomedes residents showed a consensus amongst the villagers that a protected launch and landing area would improve subsistence opportunities (Richardson 2012). The use of the boat landing area to bring in a rescue vessel would improve public safety and may allow some medically-vulnerable residents (such as the elderly or pregnant women) to stay in the village longer.

The N1 location appears not to be as convenient to the existing village layout as the southern options and would probably force some changes to patterns of movement and land use in the village. New pathways would have to be established around the school and clinic buildings to access the boat launch and the north breakwater storage site. The villagers would need to assess the suitability of the north breakwater as a storage and lay-down area for their boats and equipment.

4.4 Effects on Air Quality and Noise

Air quality may be affected during the construction period due to the use of heavy equipment, near-shore vessel operation, and electrical generators. The Corps believes any poor air quality conditions caused by the project would be transient and highly localized, and would dissipate

entirely at the end of the project. The Corps and its contractors would comply with all applicable air quality regulations and policies of the landowner, local authorities, and the State and Federal governments. The project would not provide moorage space for larger vessels nor alter the type of watercraft routinely operated at Diomedea.

The construction project would inevitably cause a temporary increase in noise at the village, as the project site is within a few yards of many village homes. Sources of noise would include the operation of heavy machinery on shore, unloading of rock and other materials, work site communications, and possibly blasting of underwater boulders. The Corps and contractors would need to coordinate closely with the village residents to find a balance between the need for an aggressive work schedule (to complete the project within the short construction season) and an acceptable level of disturbance within the community. Construction at the north alternative site would affect the school and other public buildings most immediately, and may create slightly less disturbance for individual homes. On the other hand, construction activities north of the helipad may require more frequent movement of equipment and personnel through or around the village.

4.5 Effects on Geology and Hydrology

None of the proposed small off-shore structures would have any significant effect on local geology, landforms, or surface water flow.

4.6 Effects on Oceanography and Water Quality

The breakwaters would have a small, localized effect on near-shore currents. The existing heliport riprap structure, constructed in 1993, projects directly out into the prevailing northerly current but has caused no evident disruptions to the near-shore environment such as sediment scouring. The proposed breakwaters would not project any farther out into the current than the existing heliport and would presumably not add to the obstruction of the prevailing current.

Dredging, blasting, and placement of rock during construction would cause a temporary increase in levels of suspended sediment in the water column. The local strong ocean currents would disperse the suspended sediments very quickly, but also render ineffective conventional sediment control measures, such as silt curtains.

4.7 Effects on Significant Resources

4.7.1 Effects on Terrestrial Habitat

Direct project impacts on terrestrial biological resources would be very limited. The currently proposed project would not involve upland blasting, quarrying, or removal of rock from the island, and the construction footprint would be almost entirely off-shore. Staging of materials and heavy equipment on shore would be limited by available space to shoreline areas already heavily used by the village for similar activities. Increased noise and activity during construction may conceivably have an impact on nesting seabirds, especially if underwater blasting is

required to move submerged boulders. The most disruptive activities may need to be scheduled to avoid the most sensitive periods of the birds' nesting and rearing season.

4.7.2 Effects on Marine Habitat and Near-shore Biota

Construction of the breakwaters and dredging of a boat approach lane would directly impact between 2.4 acres (alternative S2) and 3.6 acres (alternative N1) of existing shoreline and near-shore environment. Creation of the breakwaters would permanently alter the marine environment where the breakwaters were laid down. However, since that environment currently consists essentially of an expanse of large rocks, the addition of the breakwater structures would not represent a major change in habitat type. The Corps has observed that new rock breakwaters in other Bering Sea locations, such as St. Paul, Unalaska, and False Pass, have recolonized rapidly with marine algae and epilithic invertebrates, following a succession very similar to what would be expected on a naturally-occurring rock surface. The existing submerged boulders show signs of having been tumbled and weathered by wave action and ice, which presumably limits the amount of multi-year growth that the boulders can sustain. The greater stability of the breakwaters and the localized areas of reduced current velocity and wave action may encourage localized areas of greater diversity and productivity in the near-shore ecology.

Material would be dredged from a relatively small area, 0.2 to 0.7 acre, of shoreline and near-shore habitat to create a safe approach path for small vessels. This modified area may consist of finer material (smaller cobbles or gravel) than the surrounding boulders, especially if explosives were used to break apart subsurface boulders or bedrock outcroppings. Modification of this limited area would not represent a significant loss of habitat, as little marine life is able to thrive along the ice-scoured shoreline.

4.7.3 Effects on Birds

The Corps has consulted with the USFWS on previously proposed navigation projects at Diomedes under the Fish and Wildlife Coordination Act (FWCA). The USFWS produced a FWCA report in 1992 and a Planning Aid Letter (PAL) in 2008. Both documents were primarily concerned with the potential effects of upland blasting and quarrying (an activity that is no longer under consideration) on nesting seabirds. However, the USFWS has recently identified the following potential impacts to birds that apply to the currently proposed project (Boldenow 2012):

Invasive Species. The most serious potential indirect effect would be the introduction of invasive species, particularly rats, to Little Diomedes Island, brought in either on vessels directly involved in project construction or on vessels able to visit the island with greater frequency in the future due to improved landing conditions. Introduced rats have had devastating effects on seabird populations at other Alaska islands, especially on smaller burrow-nesting species such as auklets. Studies of rat-seabird interactions on Kiska Island in the Aleutians have found food

caches created by rats containing the remains of up to 148 auklets, and rat predation is thought to contribute to the greatly depressed auklet breeding success rates observed at Kiska Island (Frits 2007). The large auklet population on Little Diomedede Island would be especially vulnerable to the introduction of rats, given the lack of predators that might limit the rat population, and the absence of a port facility at which to implement rat interdiction measures.

While it is debatable whether rats could survive the severe winters at Little Diomedede Island, their chances of survival could increase if the winters become milder due to climate change. Rats have formed a breeding population at nearby Nome (Frits 2007), which is the primary transshipping point for goods headed to Diomedede. At Nome, rats presumably cohabit with humans and find enough to eat year round in human garbage and food supplies. Similarly, rats at Little Diomedede Island could conceivably find refuge in homes and other structures in the village, and thus be able to overwinter on the island.

Little Diomedede Island has been thus far protected from rat infestation in part because large vessels land there so infrequently. During the construction project, the Corps would require its contractors to observe appropriate measures to avoid transporting rats to the island on project vessels, as promoted by State and Federal agencies (Frits 2007, AMNWR 2008, AMNWR, *et al* 2011). Such measures may include setting traps and bait boxes onboard vessels en route to Little Diomedede Island as well as in any storage containers brought on shore, and educating the ship's crew and passengers. Once construction was complete, it would fall to local and regional authorities to assess the "rat-fall" risk posed by any increase in vessel traffic to the island and to implement suitable policies.

The risk of introducing other invasive species, such as noxious weeds, could be minimized by ensuring that the contractor's construction equipment is as clean as possible before landing it on the island. The risk of introducing aquatic invasive species via ballast water to the waters surrounding Little Diomedede Island during construction is low if the barges, tugs, or landing craft used are ones typically plying the Bering Sea. Construction vessels brought in from outside the Bering Sea could be required to change out ballast water away from shore. The proposed project would not accommodate deep draft vessels, so the risk from future ballast water discharge as a result of the finished project is low.

Helicopter Disturbance. Helicopter pilots flying the weekly mail delivery to Diomedede are acutely aware of the presence of dense flocks of seabirds in the area during the spring and summer months and, when possible, choose a flight path that avoids a close pass by the island's cliffs and minimizes the risk of bird-strikes. Some bird strikes are inevitable; Evergreen Aviation estimates that two bird strikes occurred in 2011 (Varnadoe 2012).

It is difficult to project how much extra helicopter traffic could be expected during construction. The expense of specially-chartered flights, plus the likelihood of weather-delays, suggests that the contractor would not choose to rely on them to move personnel and supplies around with any frequency, but would try to make use of boat transportation or of available space on scheduled helicopter flights as much as possible.

The finished project would not affect the location or usability of the existing helipad, and there is no reason to believe that it would increase the frequency of helicopter flights, post-construction. Improved access for an emergency boat or other medium-sized vessels might reduce the number of medically-related flights or chartered visits.

Solid Waste and Predator Attraction. Seabird predators such as foxes and gulls could potentially be attracted to the project area in greater numbers by improperly stored food or mishandled food waste. The community at Diomedede already has a significant challenge in managing its solid waste. The construction project would not be allowed to add to this problem. The contractor would be required to properly dispose of all solid waste, especially food waste, generated by the contractor in the course of the project.

Light Attraction. Seabirds can become attracted to artificial lighting and risk colliding with light-masts, antennae, or other structures. Auklets are particularly susceptible to light attraction (Boldenow 2012). The proposed project does not include any permanent illumination structures. Low-profile navigation beacons may be necessary at the seaward end of the breakwaters, but these are unlikely to create bird attraction or collision issues. If the contractor needs to employ work lights during part of the construction season, the lights would be shielded or otherwise used in a way that minimizes their affect on bird behavior.

Boat Traffic and Fuel Spills. The construction project would temporarily increase vessel activity and bring an increased risk of fuel spills, both at sea and along the shoreline. The contractor would be required to implement safe fuel handling procedures and to have adequate spill kits on hand to manage both marine and on-land releases of fuel and other chemicals.

The finished project would allow the residents of Diomedede to launch their small boats more frequently but would not cause a qualitative change in the types of vessels working in the waters off Diomedede. Safer launching and landing of boats would lessen the risk of spilled fuel from a damaged or capsized boat.

Loss of Habitat from Filling and Dredging. Corps personnel's observations of seabird behavior in June 2007 suggested that the dense flocks of auklets, murrelets, and puffins were largely heading out to or returning from feeding areas some distance offshore. The visible oceanic upwelling between Little and Big Diomedede Islands, several hundred yards west of the

village, seemed a particularly attractive destination. Murres and puffins were occasionally seen rafting near the cliffs north of the village, on the lee side of the reef. In contrast, the waters immediately offshore of the village did not appear to be heavily used by alcids, although gulls were often seen floating near shore. The underwater video surveys in the shallow, turbulent, boulder-strewn waters offshore of the village did not record obvious concentrations of small fish, squid, crustaceans, or other potential prey species. The proposed project would occupy at most about 3.6 acres, and extend a few hundred feet from shore into waters no more than about 30 feet deep. The Corps does not believe the finished product would impinge upon seabird feeding habitat in a significant way.

Use of Underwater Explosive Charges. Given the effects of the small seismic charges observed in 2007 on nesting seabirds (section 3.3.4), as well as the hazards and disruption that explosives use would pose to the community, the potential use of explosives during project construction to break up submerged boulders or rock outcroppings would require careful consideration and coordination. The use of explosives would be limited to the smallest effective charge necessary to yield the desired effect and may be restricted to as late in the construction season as possible, when impacts on nesting seabirds and their offspring would be minimized. The Corps and its contractors would also explore the possibility of dredging (along with any use of explosives) during the winter months.

4.7.4 Effects on Mammals

While marine mammals migrate through the Bering Strait and the waters surrounding Little Diomedé Island, none are known to routinely use the near-shore waters immediately off Diomedé. Construction of the project should have little direct effect on marine mammal habitat. The low-level noise and activity generated during construction may cause some mammals to avoid the area and use similar adjacent habitat. The potential effects of underwater explosives (if used) on marine mammals are difficult to assess, as the location, depth, and size of charge would be determined by conditions encountered during construction. Dredging would typically take place after the breakwaters were constructed, so the effects of any underwater detonation would be somewhat confined by the stone breakwaters.

The finished project would not alter the type of watercraft used by the villagers for hunting but should allow an increase in the number of safe boat launches in a given season. In principle, this should translate into proportionately greater hunting success and potentially greater hunting pressure on seals, walrus, and other prey. However, because of the high number of variables involved in a successful hunt, it is not possible to meaningfully quantify the potential increase in the number of animals taken. The number of walrus taken by Little Diomedé hunters, for example, appears to have been on a downward trend (Section 3.3.11), but it is unclear whether this is due to decreased hunting participation or opportunity, reduced walrus population, changes

in ice movement patterns making fewer walrus available, more frequent poor weather, or other factors or combination of factors.

The construction project would temporarily increase vessel activity and bring an increased risk of fuel spills both at sea and along the shoreline. The contractor would be required to implement safe fuel handling procedures and to have adequate spill kits on hand to manage both marine and on-land releases of fuel and other chemicals. The finished project would allow safer launching and landing of boats, which should lessen the risk of spilled fuel from a damaged or capsized boat.

4.7.5 Effects on Threatened and Endangered Species

The proposed project would occupy a small area immediately adjacent to the existing community that does not contain habitat important for the protected species discussed in Section 3.3.6, and the project would not have a direct effect on the widely dispersed marine animals in question.

The project site is within the range of polar bears, and within both Unit 1 (sea ice) and Unit 3 (barrier island) of critical habitat designated in 2010 (USFWS 2010). Polar bears have been reported to den at Little Diomed Island. Pregnant female polar bears select denning sites on land or on sea-ice in October or November, give birth in December or January, and then escort their cubs out to the edge of the sea ice, where prey species like seals are abundant (USFWS 1994). If some construction activities are carried out in winter to reduce impacts to migratory birds, that construction may overlap the polar bear denning period.

The residents of Diomed are avid subsistence hunters of polar bear and would be likely to take any bear that ventures close enough to the village to be directly affected by construction or the presence of the finished proposed project; however, the USFWS may require the preparation of a Polar Bear Interaction Plan for the project, especially if winter dredging operations are contemplated. The finished project would allow more frequent launching of the small craft used to hunt polar bear along the ice edge, which might in turn lead to marginally greater hunting pressure upon that species.

The Corps received an ESA informal consultation letter from USFWS on June 28, 2013, in which the USFWS stated, “the Service determines that the proposed action is not likely to adversely affect listed eiders or polar bears.” The USFWS reasoned that the proposed action could temporarily disturb listed eiders or polar bears, but due to the low densities of these species and the proposed minimization measures, the effects of disturbance would be insignificant. The Corps adopted the USFWS assessment and determined that the project may affect but not adversely affect, polar bears, Stellers eiders, or spectacled eiders.

The USFWS states that current subsistence harvest is not a threat to walrus populations; however, subsistence impacts may need to be re-evaluated if the population is found to be

declining, while harvest levels remain steady or increase (USFWS 2012b). When queried specifically about the effects on the proposed Little Diomedes project on walrus, USFWS biologist and walrus program supervisor James MacCracken stated that he did not believe that the proposed project would affect the success of walrus hunters and agreed that other variables beyond increased frequency of boat launches would have a greater influence on walrus take (McCracken 2013).

Bearded seals and ringed seals are both dependent on oceanic pack ice as a resting and pupping platform and would be expected in the project area only when substantial ice is present (generally, mid-December to mid-June). Both species exploit areas of open water occurring amongst the ice floes or otherwise must maintain access and breathing holes within the ice. The more solid, immobile shore-fast ice that forms offshore of Diomedes village during part of most winters would be less useful habitat to these seals than the fragmented, mobile ice floes that occupy the rest of the Bering Strait through the winter; therefore, bearded and ringed seals would be less likely to be found near the village when shore-fast ice is present than in the more dynamic ice environment elsewhere in the Bering Strait. Moving ice floes may carry bearded and ringed seals near the village during early and late winter, but no in-water construction work would be happening during those periods. As of the revision of this EA (September 2014), the NMFS had not designated critical habitat for these species.

The Corps expects the effects of the completed project on bearded and ringed seal populations to be similar to the effects on walrus: that is, very small to inconsequential, especially set against other regional variables and trends in the changing Bering Sea environment. The completed project would increase the number of safe boat launch and retrieval opportunities for several different activities, including subsistence, trade, and emergency transportation. However, the successful subsistence take of seals depends on numerous other variables, such as weather, visibility, the number of participating hunters, and the movement of seals in relation to shifting ice floes that are outside the scope of this study. It is not possible to develop a meaningful estimate of increased subsistence take of seals simply from an increase in boat launch opportunities.

Section 2.5 discusses the possibility of using explosives on a contingency basis to break up a boulder or rock outcropping that cannot be moved by mechanical means. The need for explosive charges would be evident only after dredging had begun and would be considered as a last resort to address a specific problem. Therefore, variables such as the size, number, and placement of any explosive charges are unknowable at this time, and their impacts on the environment cannot be evaluated.

Absent the use of explosives, the Corps determined that project construction would have no effect on bearded seals and ringed seals. If the use of explosives looked likely to be necessary,

the Corps would reopen coordination with the NMFS and the USFWS to help plan the use of explosives in a way that would cause the least environmental impacts.

Likewise, the Corps determined that, absent the use of explosives, the project would have no effect on humpback, fin, blue, and bowhead whales, and Steller sea lions. No critical habitat exists in the Diomede area for any of these species, and any individuals of these species found near Diomede would be in transit through the area. If the use of explosives looked likely to be necessary, the Corps would reopen coordination with the NMFS and the USFWS to help plan the use of explosives in a way that would cause the least environmental impacts.

4.7.6 Effects on Essential Fish Habitat

The National Marine Fisheries Service defines EFH as “those waters and substrate necessary for spawning, breeding, feeding or growth to maturity” for certain aquatic species. The two species with EFH identified in Little Diomede Island waters are saffron cod and snow crab. The NMFS states that insufficient information exists to describe EFH for saffron cod eggs, larvae, and early juveniles. EFH for late juvenile and adult saffron cod is described as “pelagic and epipelagic waters along the coastline, within near-shore bays, and under ice along the inner (0 to 50-meter) shelf throughout Arctic waters and wherever there are substrates consisting of sand and gravel” (NMFS 2005).

Similarly, insufficient information exists to describe EFH for larvae and early juvenile snow crab. EFH for late juveniles and adults is described as “bottom habitats along the inner (0 to 50-meter) and middle (50 to 100-meter) shelf in Arctic waters south of Cape Lisburne, wherever there are substrates consisting mainly of mud.” The NMFS presumes the EFH for snow crab eggs is the same as that of adult females (NMFS 2005).

The rocky, ice-scoured near-shore environment that would be occupied by the proposed project does not appear to resemble the essential habitat described by the NMFS for these species. The finished project would not alter the manner in which Diomede residents gather fish or increase harvest of these species. The Corps concludes that the project would not have an adverse impact on EFH.

4.7.7 Effects on Cultural and Historical Resources

The proposed project would have no adverse impact on any known cultural or historic sites at Diomede. While the footprints of the proposed alternatives overlap the boundary of the TEL-0014 site (section 3.3.10 and figure 3-7) to varying degrees, nearly all of that overlap is along shoreline recognized in the TEL-0014 site description as having been heavily modified by past erosion-control and construction activity. No sign of a submerged village site was observed in the proposed project areas during the underwater video survey. The Corps believes a more comprehensive archaeological investigation of the submerged project area, with its boulder-paved surface and powerful currents, is not feasible. The finished project is unlikely to encourage

greater visitation to Little Diomed Island and is thus unlikely to contribute to the risk of greater impact to cultural sites. The Corps will seek concurrence on a determination of no adverse effect with the SHPO and will propose that an archaeological monitor be present on site at key points during construction to examine dredged material for evidence of cultural resources and to help identify existing cultural resources for avoidance during construction activities.

4.7.8 Effects on Coastal Zone Resource Management

Alaska's Coastal Zone Management Program expired on 30 June 2011. Project proponents are no longer required to evaluate projects for consistency with enforceable standards of coastal management plans. Those plans do, however, offer useful criteria for evaluating projects in the coastal zone. Diomed is within the Bering Straits Coastal Resource Service Area (CRSA) and covered by the CRSA coastal management plan (Bering Straits CRSA Board 2011). The proposed project is consistent with the approved enforceable policies of that plan:

- Historical and Archaeological Sites: The Corps would coordinate this project with the State Historic Preservation Officer and would consult with local authorities on the identification and protection of historical and archaeological sites. If previously undiscovered artifacts or areas of historic, prehistoric or archaeological importance were encountered during development, the Corps would notify SHPO and local authorities, and protect the site from further disturbance until completion of a resource survey of the project site.
- Coastal Development: For economic as well as environmental reasons, the Corps would seek to minimize the extent of discharge to coastal waters to that necessary for the project.
- Sand and Gravel Extraction and Mining: The project would not involve sand or gravel extraction or mining.
- Energy Facilities: The project would not involve an energy generation facility.

The project is consistent with the coastal management plan's general goals of protecting and prioritizing subsistence and recreation uses, and limiting impacts on coastal resources and processes. If the Alaska Coastal Zone Management Program is reconstituted before construction of this project, the project would be submitted to the State of Alaska for coastal consistency review.

4.7.9 Effects on Environmental Justice

Executive Order 12898, "Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations," requires Federal agencies to identify and address any disproportionately high and adverse human health effects of its programs and activities on minority and low-income populations.

Diomed's population is about 96 percent minority (Alaska Native or combination), and 52 percent below the poverty line based on income (ADCRA 2011). However, the proposed

protected boat launching area should be an asset to the community that improves coastal resource access for all. The Corps does not foresee that construction of the project would create disproportionate adverse effects on the more vulnerable elements of the community.

4.7.10 Cumulative Effects

Federal law (40 CFR 651.16) requires that NEPA documents assess cumulative effects, which are the impact on the environment resulting from the incremental impacts of the action when added to other past, present, and reasonably foreseeable future actions.

No other similar water access projects are known to be in development at Diomedede. The proposed project is intended to improve safety for the types of small craft currently in use and allow for landings by a rescue boat, but is not designed to improve access by large craft, such as barges.

4.8 Coordination and Compliance with Environmental Requirements

4.8.1 Relationship to Environmental Laws and Compliance

National Environmental Policy Act (NEPA) of 1969 (42 USC 4341 et seq). This Act requires that environmental consequences and project alternatives be considered before a decision is made to implement a Federal project. NEPA established the requirements for preparation of an Environmental Impact Statement (EIS) for projects potentially having significant environmental impacts and an Environmental Assessment (EA) for projects with no significant environmental impacts. This EA has been prepared to address impacts and propose avoidance and minimization steps for the proposed project, as discussed in the CEQ regulations on implementing NEPA (40 CFR 1500-1508). This document presents sufficient information regarding the generic impacts of the proposed construction activities at the proposed Little Diomedede project to guide future studies and is intended to satisfy all NEPA requirements.

In accordance with NEPA and Corps policies, the EA and Finding of No Significant Impact (FONSI) was circulated for public and agency review, and the EA was made available on the USACE website to the interested public prior to the implementation of this proposed action.

Clean Water Act Of 1972 (33 USC 1251 et seq). The objective of the Clean Water Act (CWA) is to restore and maintain the chemical, physical, and biological integrity of the Nation's waters. Specific sections of the CWA control the discharge of pollutants and wastes into aquatic and marine environments.

The specific sections of the CWA that apply to the proposed project are Section 404, addressing discharges to waters of the United States, and Section 401, which requires certification that the permitted project complies with the State Water Quality Standards for actions within State waters. The enforcement agency for Section 404 is the U.S. Army Corps of Engineers. The Corps does not issue permits to itself but has prepared an evaluation of the effects of its proposed discharge under Section 404(b)(1), which is in Appendix 1. The Corps received a Section 401

water quality certification under the Clean Water Act from the State of Alaska Department of Environmental Conservation on March 18, 2014. This certification is in Appendix 3, Correspondence. Because of the small size of proposed discharge, and the similarity of the discharged material (i.e., large rock placed for the construction of the breakwaters) to the existing sediments, the Corps determines that compensatory mitigation under Section 404 is not warranted.

Rivers and Harbors Act of 1899 (33 USC 403 et seq). Section 10 of this Act prohibits the obstruction or alteration of navigable waters of the U.S. without a permit from the U.S. Army Corps of Engineers. The Corps does not issue permits to itself, so no specific permit is required under this act.

Endangered Species Act of 1973 (16 USC 1531 et seq). The Endangered Species Act (ESA) protects threatened and endangered species by prohibiting Federal actions that would jeopardize continued existence of such species or result in destruction or adverse modification of any critical habitat of such species.

The Corps requested from both the USFWS and the NMFS a list of threatened, endangered, and candidate species in the project area. The Corps received an ESA Coordination letter from USFWS on June 28, 2013, which concluded there would be no adverse effects on listed species under USFWS jurisdiction from the proposed action (letter in Appendix 3, Correspondence). NMFS had not responded to our repeated requests for ESA informal consultation. Based on available knowledge of Little Diomed Island and Bering Sea wildlife and ecology, the Corps determined that the proposed project would have no effect on listed species under NMFS jurisdiction and that consultation under Section 7 of the ESA would not be required.

Fish and Wildlife Coordination Act. The Fish and Wildlife Coordination Act (FWCA) requires the Corps to consult with the USFWS whenever the waters of any stream or other body of water are proposed to be impounded, diverted, or otherwise modified.

Specific comments were solicited from the USFWS, NMFS, and Alaska Department of Fish and Game concerning the proposed project. Comments and concerns from the USFWS on previously proposed Diomed projects have already been incorporated into this EA. Recent communications and coordination efforts are included in the Correspondence Appendix.

Magnuson-Stevens Fishery Conservation and Management Act Fishery Conservation Amendments of 1996, (16 USC 1801 et seq). The Magnuson-Stevens Fishery Conservation and Management Act provides for the conservation and management of all fishery resources between 3 and 200 nautical miles offshore. The 1996 amendments to this act require regional fisheries management councils, with assistance from the NMFS, to delineate Essential Fish Habitat (EFH) in Fishery Management Plans (FMPs) for all managed species. EFH is defined as an area that consists of “waters and substrate necessary for spawning, breeding, feeding or growth to maturity” for certain fish species. Federal action agencies that carry out activities that may

adversely impact EFH are required to consult with the NMFS regarding potential adverse effects of their actions on EFH.

The Corps has conducted an assessment of EFH (Appendix 2, EFH Assessment) for the proposed project using information provided on-line by the NMFS, and has sought further information from the NMFS. As discussed previously in this EA, the proposed project would be in waters declared EFH for snow crab and saffron cod, and in areas covered by two FMPs. Because of the small scope of this project, the dissimilarity between the project environment and the EFH descriptions for those species, and the fact that it is unlikely to alter fishing practices in the Little Diomed Island area, the Corps concludes that the project would have no adverse effect on EFH. NMFS did not comment during the 30-day public review period of the draft feasibility report and EA.

Marine Mammal Protection Act, (16 USC 1361 et seq). The Marine Mammal Protection Act (MMPA) provides protection to marine mammals in both the State waters (within 3 miles from the coastline) and the ocean waters beyond. As specified in the MMPA, the USFWS is responsible for the management of polar bears, walrus, and sea otters; the NMFS is responsible for all other marine mammals.

Based on available information, the Corps concludes that the proposed project would not have a significant adverse impact on marine mammals. The USFWS concurred with this finding in their letter dated June 28, 2013. This letter also included polar bear interaction guidelines. The letter is in Appendix 3, Correspondence.

Migratory Bird Treaty Act, (16 USC 703 et seq). The essential provision of the Migratory Bird Treaty makes it unlawful, except as permitted by regulations, “to pursue, hunt, take, capture, kill...any migratory bird, any part, nest or egg,” or any product of any bird species protected by the convention.

The seabirds that nest at Little Diomed Island are protected by this Act, and the Corps has worked closely with the USFWS to minimize any risk posed to migratory birds by the project and will continue to do so. For example, through consultation with the USFWS, risk to migratory bird habitat will be minimized by utilizing offshore construction techniques instead of land-based construction, prohibiting construction and other activities between 1 May and 30 September, ensuring outdoor lighting used during construction minimizes the potential for disorienting birds and luring them into collisions, and requiring contractors to observe appropriate measures to avoid transporting rats and other invasive species to the island .

National Historic Preservation Act of 1966, as amended (16 USC 470 et seq). The purpose of the National Historic Preservation Act (NHPA) is to preserve and protect historic and prehistoric resources that may be damaged, destroyed, or made less available by a project. Under this Act, Federal agencies are required to identify cultural or historic resources that may be affected by a

project and to consult with the State Historic Preservation Officer (SHPO) when a Federal action may affect cultural resources.

Based on available information, the Corps concluded that the proposed project would have no effect on known cultural resources under Section 106 of the NHPA. The Corps received concurrence with this determination from the SHPO on December 11, 2013 (Appendix 3, Correspondence). If previously unknown cultural resources are identified during project implementation, all activity will cease until requirements of 36 CFR 800.11, *Discovery of Properties During Implementation of an Undertaking*, are met.

Table 4- 1. Summary of Relevant Federal Statutory Authorities

Archaeological and Historic Act of 1974	FC
Clean Air Act, as amended	FC
Clean Water Act of 1977, as amended	FC
Coastal Zone Management Act of 1982	NA
Endangered Species Act of 1973, as amended	FC
Fish and Wildlife Coordination Act, as amended	FC
Marine Mammal Protection Act	FC
Marine Protection, Research, and Sanctuaries Act of 1972	FC
Migratory Bird Treaty Act of 1918	FC
Magnuson-Stevens Fishery Conservation and Management Act	FC
National Environmental Policy Act of 1969, as amended*	FC
National Historic Preservation Act of 1966, as amended	FC
Protection of Wetlands (Executive Order 11990)	FC
Rivers and Harbors Act of 1899	FC

*Public review completed December 2013.

Note: This list is not exhaustive.

4.8.2 Status of Project Coordination

The Corps received no comments from resource agencies on the EA, released in November 2013, as a result of public review. Kawerak Inc., one of the project sponsors, submitted comments on the EA during the public review period. Their letter is in the Correspondence Appendix.

As of April 2014, coordination activities with major resource agencies were as follows:

Alaska Department of Fish and Game: A letter describing the project and inviting ADFG to participate in project coordination was sent to ADFG (attn: William Morris) on January 10, 2012. The Corps received an email response from ADFG (Todd Nichols) dated January 23,

2012, stating that the ADFG had found no issues of concern and had no preference of one alternative over the other. The email is in the Correspondence Appendix

Alaska Department of Natural Resources, Office of History and Archaeology: The Corps used online resources offered by this office to study potential impacts of the project and develop a determination of effect. The Corps sent a letter of determination to the State Historic Preservation Officer on November 25, 2013, requesting their concurrence on our finding of no adverse affect, as required under Section 106 of the NHPA. The SHPO responded in a letter dated December 13, 2013, concurring with our finding of no adverse effect. This letter is in the Correspondence Appendix.

The Corps sent a letter, dated September 23, 2009, to the Native Village of Diomedes offering Government to Government consultation. The Native Village of Diomedes did not respond to this letter. However, the Corps continues to work directly with the Native Village of Diomedes.

National Marine Fisheries Service: A letter requesting a list of endangered and threatened species under the ESA and the initiation of informal ESA consultation was mailed to the NMFS Protected Resources Division (attn: Brad Smith) on January 10, 2012. No response was forthcoming; the Corps re-sent an electronic copy of the letter in an email to Mr. Smith on June 21, 2013, and followed up with a telephone call on June 27, 2013. The Corps was assured during the telephone conversation that NMFS would provide the requested ESA information, but to date the Corps has received no further response.

The Corps sent a separate letter to the NMFS Habitat Conservation Division (attn: Jeanne Hanson) on January 10, 2012, describing the proposed project and inviting coordination on EFH issues. No response was received; however, Division member Matt Eagleton had explained in an earlier email (January 3, 2012) that his office preferred to comment on EFH assessments as part of the NEPA process, so a response to the January 10 letter was not expected. The Corps sent NMFS a copy of the draft feasibility report and EA for their review during the 30-day public review process. NMFS did not comment.

U.S Fish and Wildlife Service: The Corps mailed a letter on January 10, 2012 to the USFWS Fairbanks Field Office (attn: Sarah Conn), requesting a re-initiation of informal consultation under the ESA and also inviting resumption of coordination under the FWCA. The Corps received an ESA consultation letter from USFWS on June 28, 2013, in which it determined that the project is not likely to adversely affect ESA-listed species under USFWS jurisdiction (polar bears, Steller's eiders, and spectacled eiders), and that further Section 7 consultation or preparation of Biological Assessments is not necessary.

The Corps has continued working closely with the Fairbanks Field Office Conservation Planning Assistance Branch on an informal basis. USFWS has declined to reinitiate informal consultation under the ESA and coordination under the FWCA. The Corps has continued informal coordination with USFWS on migratory bird issues. Pertinent emails are in the Correspondence Appendix

4.8.3 U.S. Fish and Wildlife Service Recommendations

The Corps has been working with the USFWS on proposed navigation improvement projects at Diomedes for a number of years, and the USFWS has provided the majority of input on environmental issues. Many of the concerns stated in their 1992 Fish and Wildlife Coordination Act Report, 2008 Planning Aid Letter, and recent correspondence (Boldenow 2012) are discussed in Section 4.7.3 above; their specific recommendations include:

- Prohibiting construction or other activities that may potentially result in the taking of migratory birds between 1 May and 30 September
- Ensuring that any outdoor lighting used during construction minimizes the potential for disorienting birds and luring them into collisions with ships or equipment
- Requiring contractors to observe appropriate measures to avoid transporting rats and other invasive species to the island on project vessels, as promoted by State and Federal agencies
- Managing food waste and other possible attractants so as to not draw increased numbers of gulls, foxes or other seabird predators to the island

Strict observance of a prohibition on potentially-disruptive activities during the 1 May to 30 September period recommended by the USFWS may not be feasible given the very limited working season at Little Diomedes. However, the Corps will continue to work with USFWS and other agencies to develop construction timing windows that protect wildlife but also allow the project to move forward. For both practical and environmental reasons, the Corps is studying the possibility of performing some construction work, such as dredging, during the winter. Some project tasks, such the delivery of rock for the breakwaters, can only be done during the open-water season, which overlaps with the USFWS-recommended no-construction period.

The USFWS, in their Section 7 Threatened and Endangered Species coordination letter , dated June 28, 2013, determined that the proposed action was not likely to adversely affect listed eiders or polar bears, and that preparation of a biological assessment or further consultation under Section 7 of the ESA was not necessary. This letter is in the Correspondence Appendix.

5.0 Conclusion

The proposed construction of breakwaters and a boat launching area at Diomedes, Alaska, as discussed in this document, would have some minor, largely controllable short-term impacts, but in the long term would help improve the overall quality of the human environment. This assessment supports the conclusion that the proposed project does not constitute a major Federal action significantly affecting the quality of the human environment; therefore, a finding of no significant impact will be prepared.

6.0 Document Preparers

This environmental assessment was prepared by Chris Floyd, Chris Hoffman, Diane Walters, and Michael Salyer of the Environmental Resources Section, Alaska District, U.S Army Corps of Engineers. The Corps of Engineers Project Manager is David Williams.

7.0 References

Alaska Department of Fish & Game (ADFG). 2013. Species Profile website, Pacific Walrus (*Odobenus rosmarus divergens*), <http://www.adfg.alaska.gov/index.cfm?adfg=walrus.main>.

ADFG. 2010. Online Wildlife Notebook Series for Arctic Fox, <http://www.adfg.state.ak.us/pubs/notebook/furbear/arcfox.php>

Alaska Division of Community and Regional Affairs (ADCRA). 2010. Alaska Community Database Online website: http://www.dced.state.ak.us/dca/commdb/CF_COMDB.htm

ADEC. 2010. Alaska 2011 Air Monitoring Network Plan, June 2010.

ADEC. 2009.18 AAC 70 Water Quality Standards, Amended as of September 19, 2009.

Alaska Maritime National Wildlife Refuge (AMNWR). 2008. Keep a Rat-Free Ship webpage, <http://alaskamaritime.fws.gov/whatwedo/bioprojects/restorebiodiversity/shipaid.htm>

AMNWR, *et al.* 2011. Stop Rats! website, <http://www.stoprats.org/index.htm>

Bering Straits Coastal Resource Service Area Board. 2011. Coastal Management Plan, Bering Straits Coastal Resource Service Area, Final Plan Amendment, January 2011.

Boldenow, Megan – U.S. Fish and Wildlife Service. 2012. Email dated 4 January 2012, subject: Little Diomedé correspondence (navigation improvements).

Campbell, Chris. 2008. Consolidated Responses to Survey Questions about Subsistence Use of Proposed Quarry Sites and Proposed Harbor/Landing site, Little Diomedé Island, U.S. Army Corps of Engineers, 31 March 2008.

Cooper, Lee, *et al.* 2006. The Potential for Using Little Diomedé Island as a Platform for Observing Environmental Conditions in Bering Strait, ARCTIC, Vol. 59, No. 2, p.129– 141, June 2006.

Ellanna, Linda J. 1983. Bering Strait Insular Eskimo: A Diachronic Study of Economy and Population Structure, Technical Paper No. 77, Subsistence Division, Alaska Department of Fish & Game, May 1983.

- Floyd, Chris, and Hoffman, Chris. 2007. Offshore Assessment, Little Diomed (U.S. Army Corps of Engineers, Civil Works Branch), August 2007.
- Frits, Ellen I. 2007. Wildlife and People at Risk – A Plan to Keep Rats Out of Alaska, Alaska Department of Fish and Game, October 2007.
- Fowler, A.C. 1991. Seabird use at proposed quarry sites, Little Diomed Island, Alaska. U.S. Fish and Wildlife Service Report, Anchorage, Alaska.
- Ginter, Deirdre. 2012. Draft Hydraulic Design, Little Diomed Navigation Improvements, 7 February 2012.
- Ginter. 2013. Conversation between Deirdre Ginter, Chris Floyd, and David Williams, Little Diomed PGM Actions meeting. 4 September 2013.
- Gualtieri, Lyn, and Birgham-Grette, Julie. 2001. The Age and Origin of the Little Diomed Upland Surface. ARCTIC, Vol. 54, No. 1, p.12–21. March 2001.
- Jarvenpa, Robert, and Brumbach, Hetty J. 2006. Circumpolar Lives and Livelihood: A comparative Ethnoarchaeology of Gender and Subsistence.
- Kawerak, Inc. 2013. Eskimo Walrus Commission webpage, <http://www.kawerak.org/ewc.html>
- Magdanz, James. 1981. Alaska Department of Fish and Game, North Bering Sea Subsistence Report, Technical Report No. 4. December 1981.
- MacCracken, James. 2013. Email dated 15 July 2013, subject: Re: Little Diomed navigation improvements - Questions for wrapping up EA.
- McIntosh, E. W. 1992. Navigation Improvement Project, Little Diomed Island, Alaska, Fish and Wildlife Coordination Act Report. U.S. Fish and Wildlife Service, Ecological Services, Fairbanks, AK.
- National Marine Fisheries Service (NMFS). 2013a. Protected Species; Cetaceans (Whales and Dolphins) in Alaska Waters website:
<http://alaskafisheries.noaa.gov/protectedresources/whales/default.htm>
- NMFS. 2013b. Protected Species; Ringed, Ribbon, Spotted, and Bearded Ice Seals website:
<http://alaskafisheries.noaa.gov/protectedresources/seals/ice.htm>
- NMFS. 2013c. Alaska Regional Office, Steller Sea Lion Critical Habitat and No Entry Zones website, <http://www.fakr.noaa.gov/protectedresources/stellers/habitat.htm>.
- NMFS. 2013d. Alaska Region Essential Fish Habitat (EFH) website,
<http://www.fakr.noaa.gov/habitat/efh.htm>

NMFS. 2005. Environmental Impact Statement for Essential Fish Habitat Identification and Conservation in Alaska. April 2005.

National Oceanic and Atmospheric Administration (NOAA). 2011. NOAA Essential Fish Habitat Mapper v2.0 website, <http://www.habitat.noaa.gov/protection/efh/habitatmapper.html>

Potter, Ben A. 2002. Cultural Resources Assessment Related to Transportation Route Upgrades in Diomedes, Alaska, Northern Land Use Research, Inc., August 2002.

Potter, Ben A. 2003. Cultural Resources Survey Relating to Fuel System Upgrades in Diomedes, Alaska, Northern Land Use Research, Inc. August 2003.

Richardson, Jim (ResourceEcon). 2012. Summary of Without Project Conditions and Impacts to Diomedes. May 2012.

R&M Consultants, Inc. (R&M). 2007. Geophysical Survey, Little Diomedes Material Site, Little Diomedes, Alaska, November 2007.

Sowls, A. L., S. A. Hatch and C. J. Lensink. 1978. Catalog of Alaskan Seabird Colonies. USDOI Fish and Wildlife Service, FWS/OBS-78/78.

TerraSond, Inc. 2007. Unpublished bathymetry and topography data.

U.S. Fish and Wildlife Service (USFWS). 2011a. Fact Sheet: Pacific Walrus and the Endangered Species Act. February 2011.

USFWS. 2011b. Fact Sheet: Pacific Walrus, *Odobenus rosemarus divergens*. January 2011

USFWS. 2010. Fact Sheet: Polar Bear Critical Habitat, Some Frequently Asked Questions, November 2010.

USFWS. 1994. Conservation Plan for the Polar Bear in Alaska, June 1994.

Varnadoe, Tim, Evergreen Aviation. 2012. Personal communication, helicopter flights to Little Diomedes Island, 12 January 2012.

Walther, Denise, USFWS. 2012. Personal communication, status of informal consultation, 17 January 2012.

Zelenak, Jim. 2007. U.S. Fish and Wildlife Service – Monitoring and Recording Seismic Blasts on Little Diomedes Island (unpublished trip report), June 2007.

APPENDIX 1

**EVALUATION UNDER SECTION 404(b)(1)
of the CLEAN WATER ACT**

**Navigation Improvements
Diomedes, Alaska**

Prepared by:

**DEPARTMENT OF THE ARMY
U.S. ARMY ENGINEER DISTRICT, ALASKA
P.O. BOX 6898
JOINT BASE ELMENDORF-RICHARDSON
ALASKA 99506-0898**

September 2013

**EVALUATION UNDER SECTION 404(b)(1)
of the CLEAN WATER ACT**

**Navigation Improvements
Diomedes, Alaska**

This is the factual documentation of an evaluation conducted under Section 404 of the Clean Water Act of 1977. This evaluation covers the placement of rock for the construction of breakwaters at the Village of Diomedes, Little Diomedes Island, Alaska, and the placement of rocky material removed from the construction site. The authority for this General Investigation study is provided by the “Rivers and Harbors in Alaska” study resolution adopted by the U.S. House of Representatives Committee on Public Works on December 2, 1970, and the Water Resources Development Act (WRDA) of 2007, Section 2006 - Remote and Subsistence Harbors.

I. PROJECT DESCRIPTION

A. Location: The project area is at the shoreline adjacent to the Village of Diomedes, on the western shore of Little Diomedes Island.

B. General Description: The environmental assessment (EA) to which this evaluation is appended contains a full discussion of the navigation problems and alternative solutions to address those problems. The intent of this project is to provide a basic, protected launching and landing area at the village to accommodate the small craft used locally for subsistence and transport, as well as larger rescue vessels. The four alternatives discussed in the EA are similar in scope and location, differing mainly in the configurations of two rubblemound breakwaters. The recommended alternative (S3) would be located south of the existing rubblemound helicopter pad and consist of two breakwaters requiring approximately 78,400 cubic yards of assorted rock imported from an off-island quarry. A small near-shore area would be dredged to -10 feet MLLW, requiring removal of approximately 2,000 to 3,000 cubic yards of existing shoreline material.

C. Authority: The authority for the project is discussed above and in the EA.

D. General Description of Dredged or Fill Material: Construction of the breakwaters would require the placement of approximately 19,000 cubic yards of core rock, 23,100 cubic yards of b-rock, and 36,400 cubic yards of armor stone. The breakwaters would occupy roughly 2 to 3 acres of submerged land. The material removed from in between the breakwaters is expected to consist primarily of granite boulders and bedrock, along with

some lesser amount of sand or silty sand. The dredged material is not expected to be chemically contaminated. The expanded breakwater storage areas proposed under Alternatives S3 (the preferred alternative) and N1 would be able to incorporate all or most of the dredged material as general fill under the storage areas.

E. Description of the Proposed Discharge Site: At the construction site, the shoreline is made up of boulders and large cobbles, with no sand or silt beach apparent. The boulders and cobbles continue offshore and compose much of the near-shore sediments. The submerged boulders have a smooth rounded or subangular appearance, suggesting they may be frequently tumbled about by ice movement and strong currents. A rocky reef extends hundreds of feet westward from the point occupied by the village; it is unclear whether the reef is made up entirely of boulders or is underlain by a bedrock dike. Broad flat areas of sand exist to the north and south of the reef, but it is not known how far these extend.

F. Description of Disposal Method: The rock used for construction would be delivered to the site by barg and placed with an excavator; the small dimensions of the project may allow most rock to be placed with shore-based equipment.

II. FACTUAL DETERMINATIONS

A. Physical Substrate Determinations: The near-shore seabed along the west shore of Little Diomedes Island consists of boulders and large cobbles, with occasional pockets of sand in between large boulders. There are no rivers or other significant sources of fine sediment on the island, and the strong, turbulent ocean currents would tend to loft and carry away any fine material.

B. Water Circulation, Fluctuation, and Salinity Determinations: The breakwaters would have an intentional localized effect on near-shore currents. The existing heliport riprap structure, constructed in 1993, projects directly out into the prevailing northerly current but has caused no evident disruptions to the near-shore environment such as sediment scouring. The proposed breakwaters would not project any farther out into the current than the existing heliport and would presumably not add to the obstruction of the prevailing current.

C. Suspended Particulate/Turbidity Determinations: The rock rubble to be placed at the disposal site would contain very little in the way of fines to be suspended in the water column, and little turbidity should be generated during disposal. The local strong ocean currents would both disperse the suspended sediments very quickly, but also render ineffective conventional sediment control measures, such as silt curtains.

D. Contaminant Determinations: The material to be placed for construction would be quarried rock from an established commercial source and would not be expected to introduce any chemical contamination. The existing material to be relocated from the construction site is expected to consist primarily of boulders and rocky debris dredged from the slipway. There is no history of significant chemical (e.g., fuel) releases in this area, and the very coarse material involved would not retain much in the way of any contaminants.

E. Aquatic Ecosystem and Organism Determinations: The intertidal zone at Little Diomed Island is very narrow and sparsely inhabited. The shoreline boulders and cobbles are subjected to ice-scouring and severe temperatures much of the year, which discourages multi-year growth. A Corps survey in 2007 noted only a few *Littorina* marine snails and very small barnacles occupying the shoreline boulders within the intertidal zone.

In the subtidal area where the seabed is deep enough to avoid ice-scouring, the boulders host a fairly rich assemblage of marine invertebrates, including anemones, barnacles, sea stars, and gastropods. Kelp is able to grow where anchored in the spaces in between boulders. Blue king crab is found farther off shore in numbers that make them an important food resource for the villagers.

Construction of the breakwaters and dredging of a boat approach lane would directly impact between 2.4 and 3.6 acres of existing shoreline and near-shore environment. Creation of the breakwaters would permanently alter the marine environment where the breakwaters are laid down. However, since that environment currently consists essentially of an expanse of large rocks, the addition of the breakwater structures would not represent a major change in habitat type. The Corps has observed that new rock breakwaters in other Bering Sea locations, such as St. Paul, Unalaska, and False Pass, have recolonized rapidly with marine algae and epilithic invertebrates, following a succession very similar to what would be expected on a naturally-occurring rock surface. The existing submerged boulders show signs of having been tumbled and weathered by wave action and ice, which presumably limits the amount of multi-year growth that the boulders can sustain. The greater stability of the breakwaters and the localized areas of reduced current velocity and wave action may encourage localized areas of greater diversity and productivity in the near-shore ecology.

Material would be dredged from a relatively small area, 0.2 to 0.7 acre, of shoreline and near-shore habitat to create a safe approach path for small vessels. This modified area may consist of finer material (smaller cobbles or gravel) than the surrounding boulders, especially if explosives are used to break apart subsurface boulders or bedrock outcroppings. Modification of this limited area does not represent a significant loss of habitat, as little marine life is able to thrive along the ice-scoured shoreline.

F. Proposed Disposal Site Determinations: The large rock material to be placed at the construction and relocation areas would descend immediately to its placement site with no dispersion and little or no suspension of fine sediments.

G. Determination of Cumulative/Secondary Effects: No cumulative or secondary effects are foreseen for this small project. No other similar water access projects are known to be in development at Diomedes. The proposed project is intended to improve safety for the types of small craft currently in use and allow for landings by a rescue boat, but is not designed to improve access by large craft, such as barges.

III. FINDINGS OF COMPLIANCE

A. Adaptation of the Section (404)(b)(1) Guidelines to this Evaluation: No adaptations of the guidelines were made relative to this evaluation.

B. Evaluation of Availability of Practical Alternatives: Non-fill alternatives, such as floating breakwaters, were studied for this project, but only a rubblemound breakwater would be sufficiently robust to survive the severe ice and wave environment at Diomedes. Dredged material removed from the construction site cannot be disposed of upland, as no area on the island large enough to receive the material is available.

C. Compliance with Applicable State Water Quality Standards: The disposal of the dredged material would not violate any applicable State water quality standards. The fill operation would not violate the Toxic Effluent Standards of Section 307 of the Clean Water Act.

D. Compliance with Endangered Species Act of 1973: The proposed action would not harm any endangered species or their critical habitat. The Corps would work with the U.S. Fish and Wildlife Service to minimize impacts on denning polar bears if construction work is pursued in winter.

E. Compliance with Specified Protection Measures for Marine Sanctuaries Designed by the Marine Protection Research and Sanctuaries Act of 1972: No action is associated with the proposed project that would violate the above Act.

F. Evaluation of Extent of Degradation of the Waters of the United States: There would be no significant adverse impacts to municipal and private water supplies, recreation and commercial fisheries, plankton, fish, shellfish, wildlife and/or aquatic sites caused by the proposed action. There would be no significant adverse effects on regional aquatic ecosystem diversity, productivity, and/or stability caused by the placement of the fill

material nor would there be significant adverse effects on recreation, aesthetic, and/or economic values caused by this project.

G. Appropriate and Practicable Steps Taken to Minimize Potential Adverse Impacts of the Discharge on Aquatic Ecosystems: All appropriate and practicable steps would be taken to minimize potential adverse impacts of the discharge on the aquatic ecosystem.

On the basis of the Guidelines for Specification of Disposal Sites for Dredged or Fill Material (40 CFR part 230), the proposed project has been specified as complying with the requirements of the guidelines for Section 404 of the Clean Water Act.

APPENDIX 2

ESSENTIAL FISH HABITAT ASSESSMENT

**NAVIGATION IMPROVEMENTS
DIOMEDE, ALASKA**

Prepared by:

**DEPARTMENT OF THE ARMY
U.S. ARMY ENGINEER DISTRICT, ALASKA
P.O. BOX 6898
JOINT BASE ELMENDORF-RICHARDSON
ALASKA 99506-0898**

September 2013

ESSENTIAL FISH HABITAT ASSESSMENT

Navigation Improvements Diomedede, Alaska

Preface

The 1996 amendments to the Magnuson-Stevens Fishery Conservation and Management Act set forth the essential fish habitat (EFH) provision to identify and protect important habitats of federally managed marine and anadromous fish species. Federal agencies that fund, permit, or undertake activities that may adversely affect EFH are required to consult with the National Marine Fisheries Service (NMFS) regarding the potential effects of their actions on EFH and respond in writing to NMFS' recommendations.

EFH is defined as those waters and substrate necessary to fish for spawning, breeding, feeding, or growth to maturity. "Waters" include aquatic areas and their associated physical, chemical, and biological properties that are used by fish, and may include aquatic areas historically used by fish where appropriate. "Substrate" includes sediment, hard bottom, structures underlying the waters, and associated biological communities.

Upon completing the Corps's EFH-coordination with the NMFS, the Corps will incorporate its EFH evaluation and findings and NMFS' conservation recommendations (if any) into the project's environmental assessment.

Project Purpose

The intent of this project is to provide a basic protected launching and landing area at the village of Diomedede to accommodate the small craft used locally for subsistence and transport, as well as for larger rescue vessels.

Project Authority

The authority for this General Investigation study is provided by the "Rivers and Harbors in Alaska" study resolution adopted by the U.S. House of Representatives Committee on Public Works on December 2, 1970, and the Water Resources Development Act (WRDA) of 2007, Section 2006 - Remote and Subsistence Harbors.

Project Description

Diomedede, also known as *Inalik*, is a village on the western shore of Little Diomedede Island in the middle of the Bering Strait (figure 1). The community of about 150 people is perched on an exposed rocky shoreline with no harbor, breakwater, or adequate barge landing area (figure 2). Travel to and from Diomedede and the importation of goods is difficult as Diomedede has no year-round airstrip. Because of the lack of moorage at the village, the boats used by residents for transportation must be limited to craft small enough to be manually hauled out of the ocean and

stored on shore. Rough slips have been carved out of the shoreline boulders (figure 2), but no other protection from waves or storm surge exists.




Figure 1. Location and vicinity of Little Diomede Island.



Figure 2. View of the village, with the existing small boat slips shown at the center of the photos, and the helipad at the extreme left.

The alternatives under study (figures 3 through 6) are for a protected boat launching area immediately adjacent to the village, consisting of a small (0.2 to 0.3 acre) area cleared of near-shore boulders to a depth of -10 feet below mean lower low water (MLLW) sheltered by two rubblemound breakwaters.




Figure 3. Alternative N1.



Figure 4. Alternative S1.



Figure 5. Alternative S2.



Figure 6. Alternative S3.

Essential Fish Habitat

The NMFS’ authority to manage EFH is directly related to those species covered under Fishery Management Plans (FMPs) in the United States. The Little Diomed Island project site is very near the boundary of the Arctic Management Area and the Bering Sea/Aleutian Island (BSAI) Management Area. Two species, snow crab and saffron cod, have designated EFH off the west coast of Little Diomed Island (NOAA 2013). Snow crab has EFH described both under the Arctic Fishery Management Plan and the BSAI Crab Fishery Management Plan (NPFMC 2009; NOAA 2005). Saffron cod EFH is described only in the Arctic Fishery Management Plan (NPFMC 2009).

No EFH “habitat areas of particular concern” are in the Corps’ project area. The waters off Nome are included in the Northern Bering Sea Research Area Bering Sea Subarea 514.

Table 1. Species with designated essential fish habitat in the project area.

Species	Lifestages expected at project location	FMP
Snow Crab	Late Juvenile	Arctic, BSAI Crab
Saffron Cod	Late Juvenile, Mature	Arctic

Assessment of Project Effects on Essential Fish Habitat

Short-term impacts include water quality impacts in the form of increased levels of turbidity, noise from dredging operations, pollution in the form of fuel or oils spilled from the dredging equipment, noise from the dredging equipment, and disturbance from the movement of equipment through the area.

Short-term Impacts

Water Quality. The material removed by dredging is expected to consist of boulders and rocky debris with little fines. Dredging, blasting, and placement of rock during construction would cause a temporary increase in levels of suspended sediment in the water column. The local strong ocean currents would both disperse the suspended sediments very quickly, but also render ineffective conventional sediment control measures, such as silt curtains.

Pollution. Neither the material to be dredged nor the rock placed for the breakwaters would be contaminated. The primary risk of introducing pollutants into the environment would be accidental releases of fuels or lubricants. The contractor would be required to prepare a spill prevention and response plan and have appropriate spill response materials at the work site.

Waterborne Noise. Sources of underwater noise would include the operation of heavy machinery on shore and in the water, dredging, unloading of rock and other materials, and possible blasting of underwater boulders or rock outcroppings. The low-level noise and activity generated during

construction may cause some fish to avoid the area and use similar adjacent habitat. The potential effects of underwater explosives (if used) on EFH species are difficult to assess, as the location, depth, and size of charge would be determined by conditions encountered during construction. Dredging would typically take place after the breakwaters were constructed, so the effects of any underwater detonation would be significantly confined by the stone breakwaters.

Construction-Related Vessel Traffic. The construction project would temporarily increase vessel activity and bring an increased risk of fuel spills, both at sea and along the shoreline. The contractor would be required to implement safe fuel handling procedures and to have adequate spill kits on hand to manage both marine and on-land releases of fuel or other chemicals.

Long-Term Impacts

Loss and Conversion of Marine Habitat. The existing habitat at the project site is dominated by large boulders and cobbles. Severe cold and annual scouring by sea ice limits the growth of marine algae and invertebrates in the intertidal zone and on rock surfaces submerged as deep as 10 feet below MLLW. Farther offshore, marine algae are able to grow amongst the boulders where they are sheltered against the worst of the local currents. At depths where the boulders are not subject to ice-scouring, they support dense growths of anemones and other epilithic organisms. As the distance from the shoreline increases, flat patches of sand or pulverized shell appear amongst the boulders, and broad areas of sand are present several hundred feet offshore.

Creation of the breakwaters would permanently alter the marine environment where the breakwaters were laid down. However, since that environment currently consists essentially of an expanse of large rocks, the addition of the breakwater structures would not represent a major change in habitat type. The Corps has observed that new rock breakwaters in other Bering Sea locations, such as St. Paul, Unalaska, and False Pass, have recolonized rapidly with marine algae and epilithic invertebrates, following a succession very similar to what would be expected on a naturally-occurring rock surface. The existing submerged boulders show signs of having been tumbled and weathered by wave action and ice, which presumably limits the amount of multi-year growth that the boulders can sustain. The greater stability of the breakwaters and the localized areas of reduced current velocity and wave action may encourage localized areas of greater diversity and productivity in the near-shore ecology.

Material would be dredged from a relatively small area, 0.2 to 0.7 acre, of shoreline and near-shore habitat to create a safe approach path for small vessels. This modified area may consist of finer material (smaller cobbles or gravel) than the surrounding boulders, especially if explosives were used to break apart subsurface boulders or bedrock outcroppings. Modification of this limited area would not represent a significant loss of habitat, as little marine life is able to thrive along the ice-scoured rocky shoreline.

Water Quality. The proposed dredging project would have no long-term impact on coastal water quality. The breakwaters would have a small, localized effect on near-shore currents. The existing heliport riprap structure, constructed in 1993, projects directly out into the prevailing northerly current but has caused no evident disruptions to the near-shore environment such as sediment scouring. The proposed breakwaters would not project any farther out into the current than the existing heliport and would presumably not add to the obstruction of the prevailing current.

Avoidance and Minimization Measures. Planned measures to limit the project's impact on fish habitat include:

- Any use of explosives would be limited to the smallest effective charge necessary to yield the desired effect and may be restricted to as late in the construction season as possible. If practicable, dredging (including the use of explosives) would be conducted after the breakwaters are in place, which would limit the propagation of noise.
- To minimize the danger to marine mammals from project-related vessels, speed limits (e.g. less than 8 knots) shall be imposed on vessels moving in and around the project area.
- Project-related vessels and barges shall not be permitted to ground themselves on the bottom during low tide periods, unless there is a human safety issue requiring it.
- A construction oil spill prevention plan shall be prepared.
- The Corps will conduct post-dredging bathymetry surveys to ensure that only the material identified to be dredged was removed to the authorized depth and that the design depth was achieved by the dredge action.

Conclusions and Determination of Effect.

The proposed project would have little or no short-term or long-term effects on EFH. The project would directly impact a small area (less than 4 acres) of marine habitat not believed to be valuable habitat for fish. The habitat eliminated, an expanse of large boulders, would be replaced by rock structures that would function similarly to the existing boulders in providing shelter for anchored kelp species and substrate for epilithic organisms. The dredging of up to 0.7 acre of near-shore habitat would not represent a significant loss of habitat, as little marine life is able to thrive along the ice-scoured shoreline.

Where descriptions of life-stage essential habitat are available for the two EFH species, snow crab and saffron cod, those essential habitats are quite different from what exists in the project area. Late juvenile and adult snow crab EFH is described as requiring primarily mud substrates,

DESCRIPTIONS OF ESSENTIAL HABITAT

Snow Crab

Eggs

Essential fish habitat of snow crab eggs is inferred from the general distribution of egg-bearing female crab (see Adults).

Larvae and Early Juveniles

Insufficient information is available to determine EFH for Larvae and Early Juveniles.

Late Juveniles

EFH for late juvenile snow crab is the general distribution area for this life stage, located in bottom habitats along the inner (0 to 50 m) and middle (50 to 100 m) shelf in Arctic waters south of Cape Lisburne, wherever there are substrates consisting mainly of mud.

Adults

EFH for adult snow crab is the general distribution area for this life stage, located in bottom habitats along the inner (0 to 50 m) and middle (50 to 100 m) shelf in Arctic waters south of Cape Lisburne, wherever there are substrates consisting mainly of mud.

Saffron Cod

Eggs, Larvae, and Early Juveniles

Insufficient information is available to determine EFH for Eggs, Larvae, and Early Juveniles.

Late Juveniles

EFH for late juvenile Saffron cod is the general distribution area for this life stage, located in pelagic and epipelagic waters along the coastline, within near-shore bays, and under ice along the inner (0 to 50 m) shelf throughout Arctic waters and wherever there are substrates consisting of sand and gravel.

Adults

EFH for adult Saffron cod is the general distribution area for this life stage, located in pelagic and epipelagic waters along the coastline, within near-shore bays, and under ice along the inner (0 to 50 m) shelf throughout Arctic waters and wherever there are substrates consisting of sand and gravel.

while that of late juvenile and adult saffron cod is described as requiring primarily sand and gravel substrates. Therefore, the boulder and large cobble substrate existing in the project area does not constitute EFH for either of these species at the late juvenile or adult life-stages, and the project would not cause a loss of EFH.

The finished project would allow the residents of Diomedes to launch their small boats more frequently but would not cause a qualitative change in the types of vessels working in the waters off Diomedes or alter fishing habits. Safer launching and landing of boats would lessen the risk of spilled fuel from a damaged or capsized boat.

References

National Marine Fisheries Service (NMFS). 2013. Alaska Region Essential Fish Habitat (EFH) website, <http://www.fakr.noaa.gov/habitat/efh.htm>

NMFS. 2005. Environmental Impact Statement for Essential Fish Habitat Identification and Conservation in Alaska. April 2005.

North Pacific Fishery Management Council (NPFMC). 2009. Fishery Management Plan for Fish Resources of the Arctic Management Area. August 2009.

APPENDIX 3

CORRESPONDENCE

NAVIGATION IMPROVEMENTS
DIOMEDE, ALASKA



THE STATE
of **ALASKA**
GOVERNOR SEAN PARNELL

Department of Environmental
Conservation

DIVISION OF WATER
Wastewater Discharge Authorization Program

555 Cordova Street
Anchorage, Alaska 99501-2617
Main: 907.269.6285
Fax: 907.334.2415
www.dec.alaska.gov/water/wwdp

March 18, 2014

Certified Mail: 7008-1830-0002-6349-1585

US Army Corps of Engineers, Alaska District
Attn: CEPOA-EN-G-ER (Chris Floyd)
PO Box 6898
JBER, Alaska 99506-0898

Re: Little Diomedede, Navigation Improvements
Reference No. ER-14-02

Dear Mr. Floyd:


In accordance with Section 401 of the Federal Clean Water Act of 1977 and provisions of the Alaska Water Quality Standards, the Department of Environmental Conservation (DEC) is issuing the enclosed Certificate of Reasonable Assurance for placement of fill material in waters of the U.S. in association with the navigational improvements located at Little Diomedede, Alaska.

DEC regulations provide that any person who disagrees with this decision may request an informal review by the Division Director in accordance with 18 AAC 15.185 or an adjudicatory hearing in accordance with 18 AAC 15.195 – 18 AAC 15.340. An informal review request must be delivered to the Director, Division of Water, 555 Cordova Street, Anchorage, AK 99501, within 15 days of the permit decision. Visit <http://www.dec.state.ak.us/commish/ReviewGuidance.htm> for information on Administrative Appeals of Department decisions.

An adjudicatory hearing request must be delivered to the Commissioner of the Department of Environmental Conservation, 410 Willoughby Avenue, Suite 303, PO Box 111800, Juneau, AK 99811-1800, within 30 days of the permit decision. If a hearing is not requested within 30 days, the right to appeal is waived.

By copy of this letter we are advising the U.S. Army Corps of Engineers of our actions and enclosing a copy of the certification for their use.

Sincerely,


James Rypkema
Section Manager, Storm Water and Wetlands

Enclosure: 401 Certificate of Reasonable Assurance

cc: (with encl.)
Michael Daigneault, ADF&G
USFWS Field Office Anchorage

Matthew LaCroix, EPA Operations, Anchorage

STATE OF ALASKA
DEPARTMENT OF ENVIRONMENTAL CONSERVATION
CERTIFICATE OF REASONABLE ASSURANCE

A Certificate of Reasonable Assurance, in accordance with Section 401 of the Federal Clean Water Act and the Alaska Water Quality Standards is issued to US Army Corps of Engineers, Alaska District, Attn: CEPOA-EN-G-ER (Chris Floyd), PO Box 6898, JBER, Alaska 99506-0898 for placement of fill material in waters of the U.S. in association with the navigational improvements located at Little Diomed, Alaska. The intent of this project is to provide a basic, protected launching and landing area at the village to accommodate the small craft used locally for subsistence and transport, as well as larger rescue vessels. The four alternatives discussed in the Environmental Assessment are similar in scope and location, differing mainly in the configurations of two rubble mound breakwaters. The recommended alternative (S3) would be located south of the existing rubble mound helicopter pad and consist of two breakwaters requiring approximately 78,400 cubic yards of assorted rock imported from an off-island quarry. A small near-shore area would be dredged to -10 feet MLLW, requiring removal of approximately 2,000 to 3,000 cubic yards of existing shoreline material. Construction of the breakwaters would require the placement of approximately 19,000 cubic yards of core rock, 23,100 cubic yards of b-rock, and 36,400 cubic yards of armor stone. The breakwaters would occupy roughly 2 to 3 acres of submerged land. The material removed from in between the breakwaters is expected to consist primarily of granite boulders and bedrock, along with some lesser amount of sand or silty sand. The dredged material is not expected to be chemically contaminated. The expanded breakwater storage areas proposed would be able to incorporate all or most of the dredged material as general fill under the storage areas. The project includes repair and maintenance to be performed once every 10 years for the 50-year project life.

A State Water Quality Certification is required under Section 401 because the proposed activity will be authorized by a U.S. Army Corps of Engineers, reference number ER-14-02, and a discharge of pollutants to waters of the U.S. located in the State of Alaska may result from the proposed activity. Public notice of the application for this certification was given as required by 18 AAC 15.180 in the Corps Public Notice reference ER-14-02 posted November 6, 2013.

The proposed activity is at the shoreline adjacent to the Village of Diomed, on the western shore of Little Diomed Island., near Latitude 65.7581, Longitude -168.9531.

The Department of Environmental Conservation (DEC) reviewed the application and certifies that there is reasonable assurance that the proposed activity, as well as any discharge which may result, will comply with applicable provisions of Section 401 of the Clean Water Act and the Alaska Water Quality Standards, 18 AAC 70, provided that the following alternative measures are adhered to.


1. Reasonable precautions and controls must be used to prevent incidental and accidental discharge of petroleum products or other hazardous substances. Fuel storage and handling activities for equipment must be sited and conducted so there is no petroleum contamination of the ground, surface runoff or water bodies.
2. During construction, spill response equipment and supplies such as sorbent pads shall be available and used immediately to contain and cleanup oil, fuel, hydraulic fluid, antifreeze, or other pollutant spills. Any spill amount must be reported in accordance with Discharge

Notification and Reporting Requirements (AS 46.03.755 and 18 AAC 75 Article 3). The applicant must contact by telephone the DEC Area Response Team for Northern Alaska at (907) 451-2121 during work hours or 1-800-478-9300 after hours. Also, the applicant must contact by telephone the National Response Center at 1-800-424-8802.

3. Construction equipment shall not be operated below the ordinary high water mark if equipment is leaking fuel, oil, hydraulic fluid, or any other hazardous material. Equipment shall be inspected on a daily basis for leaks. If leaks are found the equipment shall not be used and pulled from service until the leak is repaired.
4. Fill material must be clean sand, gravel or rock, free from petroleum products and toxic contaminants in toxic amounts.

This certification expires five (5) years after the date the certification is signed. If your project is not completed by then and work under U.S Army Corps of Engineers Permit will continue, you must submit an application for renewal of this certification no later than 30 days before the expiration date (18 AAC 15.100).

Date: March 18, 2014



James Rypkema, Section Manager
Storm Water and Wetlands



THE STATE
of **ALASKA**
GOVERNOR SEAN PARNELL

Department of Natural Resources

DIVISION OF PARKS AND OUTDOOR RECREATION
Office of History and Archaeology

550 West 7th Avenue, Suite 1310
Anchorage, Alaska 99501-3565
Web: <http://dnr.alaska.gov/parks/oha>
Phone: 907.269.8721
Fax: 907.269.8908

December 11, 2013

File No.: 3130-1R COE

Michael R. Salyer
Chief, Environmental Resources Section
U.S. Army Engineer District, Alaska
P.O. Box 6898
JBER, Alaska 99506-0898

Subject: Rubblemound Breakwaters, Little Diomede / *Ignaluk*

Dear Mr. Salyer:

The Alaska State Historic Preservation Office (AK SHPO) received your correspondence (dated November 21, 2013) on November 25, 2013. Following our review of the documentation, we agree that archaeological monitoring during ground-disturbing and dredging activities is appropriate given the nature and location of the proposed undertaking. Assuming these management measures are implemented, we concur that a finding of **no adverse effect** is appropriate for the proposed undertaking.

Please note that additional information provided by the local government, Tribes or other consulting parties may cause our office to re-evaluate our comments and recommendations.

Should unidentified archaeological resources be discovered in the course of the project, work must be interrupted until the resources have been evaluated in terms of the National Register of Historic Places eligibility criteria (36 CFR 60.4) or Alaska Landmarks Register in consultation with our office.

Thank you for the opportunity to comment. Please contact Shina duVall at 269-8720 or shina.duvall@alaska.gov if you have any questions or if we can be of further assistance.

Sincerely,

A handwritten signature in cursive script that reads "Judith E. Bittner".

Judith E. Bittner
State Historic Preservation Officer

JEB:sad



KAWERAK, INC. P.O. Box 948 Nome, Alaska 99762 (907) 443-5231 Fax: (907) 443-4452

December 30, 2013

David Williams
U.S. Army Corps of Engineers
Alaska District

Sent via email to: David.P.Williams@usace.army.mil

Subject: Draft Feasibility Report, Environmental Assessment and Finding of No Significant Impact for Navigation Improvements at Diomedé, Alaska

Dear Mr. Williams,

Thank you for the opportunity to review and provide comments on the *Draft Feasibility Report, Environmental Assessment and Finding of No Significant Impact for Navigation Improvements at Diomedé, Alaska*. Kawerak's Social Science Program has reviewed this document and has the following comments and recommendations.

Draft Feasibility Report

- Section 2.3: Because the decision to go hunting is a very complicated one that requires the consideration of multiple factors, it is possible that an improved harbor/launch area may not necessarily increase the number of hunting trips that Diomedé hunters can make in any given year. Residents of Diomedé, Wales and other Bering Strait communities have reported more frequent rough open-water conditions and a climate that has become, in general, harsher and less predictable over time. Even with the presence of a protected harbor, open-water travel in small skiffs may not be possible. Factors considered by hunters include wind speed and direction, wave heights, ice conditions, distance to ice, crew composition, the price of fuel, previous harvest success, other environmental conditions (e.g. fog), whether or not the location of walrus or other species is known, and the presence or absence of large vessels nearby, among others.

While the Corps conducted a survey with Diomedé residents in 2007, and many responded that a harbor would potentially increase the number of hunting-days available to them, we recommend using a semi-structured interview process to more thoroughly address this question with experienced hunters and elders. This method would allow for a more detailed examination of all the factors involved in hunting/boating decisions and a more accurate understanding of the benefits that a harbor would provide under different conditions.

- Section 2.3 (p.11): Many statements in the report about the potential benefits of a harbor are not backed up by any references or data. For example, on page 11: "Aside from subsistence foods

harvested directly for consumption by Diomedes residents, it is likely that increased ocean access would enable acquisition of food that could be traded to residents of nearby communities for food or other items not available at Diomedes.” There is no documented data on patterns of sharing of subsistence foods between Diomedes and other communities. These types of statements have important implications for communities and should be backed up by verified data. Again, we would suggest using a semi-structured interview method for obtaining this type of information.

Section 4.1.2 (p.20): This section discusses access to the marine environment and subsistence food production. While the statements made by the Corps are not necessarily incorrect, they are not supported by references or data. This information is important to the community of Diomedes and should be backed up by verified data.

- Section 5.1: The current over the shoal in front of the helicopter pad has been described as “very dangerous” by Diomedes residents. The Social Science Program has a forthcoming report (available in spring 2014) about currents in the Bering Strait region, including around Little Diomedes Island.
- Section 6.2: The Corps lists a potential benefit of the project as “increased certainty for medical evacuations”. Where would a vessel equipped to do medivacs be based out of? There is no discussion of this and there is currently no vessel dedicated to such activity. If there was a vessel, and it was home-ported in Diomedes, this might be an actual benefit – but the discussion does not give enough information for this to be evaluated as a realistic benefit.

The potential for decreased freight costs is also listed as a potential benefit. However, Table 5 seems to indicate that larger vessels, such as barges bringing freight, would not be accommodated by the size of harbor planned. Several sentences later, the Corps also notes that “freight operators for the region have indicated they would not change their current deliver practices” if a new harbor were built.

Another potential benefit of the project described by the Corps is an “opportunity to house Search and Rescue equipment near the proposed offshore Arctic Drilling”. It is not clear if the Corps has discussed this with Diomedes residents. Storage space on the island is very limited, and it is possible that Diomedes residents would prefer that such materials be stored on the mainland (closer to where drilling activities are taking place), or that only spill response equipment be stored on the island. It is not possible to say with certainty until the question has been investigated with Diomedes residents.

Additionally, the Corps notes in section 6.2 that “Not enough is known about the harvest practices to determine if shorter trips to harvest food would decrease fuel consumption or just be offset by the additional time spent harvesting so no benefits are claimed for this category.” This is a very important question and should have been addressed for this project; it should be investigated through semi-structured interviews with Diomedes hunters.

The potential gain of 17-21 days annually in safe launch and retrieval of vessels needs to be qualified (see comments above on Section 2.3) given the real-world conditions that hunters face.

- Section 7.1.2: It is unclear why any of the alternatives would decrease fuel consumption or lead to shorter-distance journeys for walrus hunts. Increases in travel distance for walrus hunting (and thus increased gas use) are almost entirely related to local ice conditions, not wave height or ability to launch.

- Section 7.2 (p.37): The Corps lists a “potential safety boat” which “could serve as back up to the helicopter during poor visibility or mechanical breakdowns” as a justification for the project. There is no discussion of who is buying, maintaining and operating a “potential safety boat”. Will it be ported in Diomedea? This seems impossible because all boats will still need to be stored on land and this would have to be a large vessel to be able to quickly and safely transport patients to Nome.

Also on p. 37 – the Corps suggests that with reduced time away from (and on) the island more people will travel off-island for medical treatment, and more service providers will be willing to go to the island. This implies that a medivac/Search and Rescue/other vessel (which does not currently exist), will also be able to provide regular passenger service. This does not seem feasible, or at least the Corps has not provided information to justify this potential benefit.

- Section 8.1.2: Will the construction of these breakwaters have any impact on water flow and ice formation in regards to shore ice (an important launching area for hunting when present) and the ability to build an ice runway? This is not discussed anywhere in the report, but is a very important consideration.
- Section 8.2 (p.46): In this section the Corps states that: “...cultural assets and activities have a worth beyond cost or realizable value and that worth is difficult to articulate, let alone calculate.” Kawerak agrees with this statement. We believe that research which attempts to value subsistence products, activities or values, or any type of cultural activities or values, cannot be accurate and that such attempts to monetize or value such things can cause harm to subsistence communities. We recommend a qualitative approach to determining what the importance, meaning and cultural value of such things are to community members and communities.

(p.46-47): The Corps outlines ways that the “project would significantly improve the quality of life for the residents of Little Diomedea as well as provide life/safety benefits...” Many of the items outlined were never discussed at length or at all, previously. For example, the reality of improvements to waste disposal and increased economic opportunities due to cruise vessel visitation, among others, were not discussed in any detail earlier in the report.

- Section 9.2: In regards to cultural resources, Kawerak recommends that an archaeological monitor be on site during on-land disturbance activities, as well as during dredging. While the shoreline has been disturbed by various activities in the past, there are some very large boulders along the shoreline, some of which may have never been disturbed, and are likely to be moved for this project. Additionally, a former village was located on the now-submerged shoal near the helicopter pad, which may be partially dredged for this project. Having an archaeological monitor on site during dredging and on-land disturbance will ensure that any previously undiscovered cultural resources are properly documented.
- Section 10.2.4: The Corps notes that they have contacted national experts in “formulation of small boat harbors and subsistence concerns...” The Corps should detail who was contacted, for what purpose, and what the result of the contact was.
- Section 10.3 (p.54): The Corps notes that the community endorsed the recommended plan, but does not say how they know this. Was a community meeting held? If so, how was it structured and what was the result?

EA and FONSI

- Summary page: The Corps says that they will continue to coordinate the project with various entities, but does not mention the Native Village of Diomed. The Corps should continue to coordinate with the Village.
- Section 1.3: This section notes that, “The intent of this project is to provide a basic protected launching and landing area at the community to accommodate the small craft used locally for subsistence and transport, *as well as for larger rescue vessels.*” The feasibility part of the documents does not adequately address the idea of “larger rescue vessels” using the proposed facility.
- Page 8: We agree with the Corps’ proposition that an archaeological monitor be on site to examine dredged material, and also recommend that a monitor be in place for on-land ground disturbing activities (see comment above re section 9.2 of the Draft Feasibility Report).

Thank you for the opportunity to comment. If you have any questions, please contact me at 907-443-4273 or juliery@kawerak.org.

Sincerely,

A handwritten signature in cursive script that reads "Julie".

KAWERAK, INC.

Julie Raymond-Yakoubian
Social Science Program Director
Anthropologist



TEL: (907) 443-5231 • FAX: (907) 443-4452

- SERVING THE
- VILLAGES OF:
- BREVIG MISSION
- COUNCIL
- DIOMEDE
- ELIM
- GAMBELL
- GOLOVIN
- KING ISLAND
- KOYUK
- MARY'S IGLOO
- NOME
- SAVOONGA
- SHAKTOOLIK
- SHISHMAREF
- SOLOMON
- STEBBINS
- ST. MICHAEL
- TELLER
- UNALAKLEET
- WALES
- WHITE MOUNTAIN

November 15, 2015

US ARMY CORPS OF ENGINEERS,
ALASKA DISTRICT
ATTN: CEPOA-DE
P.O. Box 6898
JBER, AK 99506-0898

Dear Colonel Lestochi:

We have reviewed the draft report you sent us on the viability of improving harbor and navigation conditions at Diomedede, Alaska. We concur with the findings in the draft report and support Corps continuation into design and construction. The Native Village of Diomedede and Kawerak understands that the design and construction work will each require a separate cost share agreement and that the initial cost to us will be 10% of the cost of the work, and 10% that can be paid over 30 years after completion of construction.

My staff has assigned this project a high priority in assisting you to complete the cost-sharing agreement over the next few months. We look forward to working with you to bring this project to a successful completion.

We understand that if this letter of intent is acceptable, you will develop the design cost-sharing agreement and the implementation PMP upon approval of the Feasibility Report by your Division Chief. We understand this letter is a statement of intent, not a binding contract.

Sincerely,

Melanie Bahnke
Melanie Bahnke
Kawerak, Inc.,
President

Karen Koyungak
Native Village of Diomedede
President

**NON-FEDERAL SPONSOR'S
SELF-CERTIFICATION OF FINANCIAL CAPABILITY
FOR AGREEMENTS**

I, Melanie Bahnke, do hereby certify that I am the President of Kawerak, Inc., (the "Non-Federal Sponsor"); that I am aware of the financial obligations of the Non-Federal Sponsor for the Navigation Improvements for Diomede, Alaska; and that the Non-Federal Sponsor has the financial capability to satisfy the Non-Federal Sponsor's obligations under the Navigation Improvement Study.

IN WITNESS WHEREOF, I have made and executed this certification this 20th day of November, 2013.

BY: M. Bahnke

TITLE: President


DATE: 11/20/13

Table 13. Cost Apportionment

Cost Sharing (\$) – FY2013 Program/Budget Year Cost - Escalated						
TSP – S3	Total Cost	Federal 90%	Sponsor 10%	10% GNF (Post- Construction)	LSF & LERRs	U.S. Coast Guard (ATON)
PED (Design for GNF)	3,323,000	2,990,700	332,300	332,300		
Total Construction (GNF)	23,570,000	21,213,000	2,357,000	2,357,000		
Construction Management	1,880,000	1,692,000	188,000	188,000		
Real Estate (LERR)	60,000			-60,000	60,000	
Aids to Navigation	30,000					30,000
TOTAL	28,863,000	25,976,700	2,877,300	2,817,300	60,000	30,000
OMRR&R	3,616,000					

*PED values are based on a set percentage of construction cost; actual amounts will vary

*OMRR&R consists of 5% replacement of armor rock, once every 10 years – 100% Federal



ID	Task Name	Description	Duration (Days)	Start	End
1	Task 1: Risk Assessment	3.25 days	Mon 01/13/14	Mon 01/13/14	
2	Task 2: Public Comment	0 days	Mon 01/13/14	Mon 01/13/14	
3	Task 3: Draft HERR Appendix	0 days	Mon 01/13/14	Mon 01/13/14	
4	Task 4: Subsequent Model Completion	0 days	Mon 01/13/14	Mon 01/13/14	
5	Task 5: Environmental Analysis (EA)	3 wks	Mon 01/13/14	Mon 02/03/14	
6	Task 6: Cost Estimate MCHCES	0 wks	Mon 01/13/14	Mon 01/13/14	
7	Task 7: Final EIR/EA	2 wks	Mon 01/13/14	Mon 01/27/14	
8	Task 8: BCR Check	2 wks	Mon 01/13/14	Mon 01/27/14	
9	Task 9: Site Visit to Prison Alternatives	1 day	Thu 01/23/14	Thu 01/23/14	
10	Task 10: Write Draft AFB Report	10 wks	Fri 01/17/14	Thu 01/16/14	
11	Task 11: Complete ECC/CECA	10.8 wks	Fri 01/17/14	Mon 01/06/14	
12	Task 12: Prepare Draft AFB Report	1 mon	Fri 01/17/14	Fri 01/17/14	
13	Task 13: Defense Quality Control	1 mon	Mon 01/13/14	Mon 01/13/14	
14	Task 14: AFB POM	2 wks	Mon 01/13/14	Mon 01/27/14	
15	Task 15: AFB POM	4 days	Tue 01/14/14	Fri 01/17/14	
16	Task 16: AFB POM	73 days	Fri 01/17/14	Wed 01/14/14	
17	Task 17: AFB POM	81 days	Fri 01/17/14	Sun 02/28/14	
18	Task 18: AFB POM	4.14 wks	Wed 01/15/14	Thu 01/16/14	
19	Task 19: AFB POM	1 day	Mon 01/13/14	Mon 01/13/14	
20	Task 20: AFB POM	7.20 wks	Mon 01/13/14	Wed 01/14/14	
21	Task 21: Complete Study and NEPA Documents	174 days	Fri 01/17/14	Thu 01/09/14	
22	Task 22: Assess Bathymetric Data to Basin	0 days	Fri 01/17/14	Fri 01/17/14	
23	Task 23: Prepare Data Response	45 days	Fri 01/17/14	Thu 01/09/14	
24	Task 24: Review Data Response	23 wks	Wed 01/15/14	Fri 01/17/14	
25	Task 25: Review Data Response	64 days	Wed 01/15/14	Tue 01/14/14	
26	Task 26: Public Review Period	60 days	Wed 01/15/14	Sun 01/14/14	
27	Task 27: ATR of Final Report/EA	1 mon	Sun 01/14/14	Tue 01/14/14	
28	Task 28: ATR of Final Report/EA	1 mon	Tue 01/14/14	Thu 01/16/14	
29	Task 29: ATR of Final Report/EA	1 mon	Thu 01/16/14	Fri 01/17/14	
30	Task 30: ATR of Final Report/EA	1 mon	Fri 01/17/14	Sat 01/18/14	
31	Task 31: ATR of Final Report/EA	1 mon	Sat 01/18/14	Sun 01/19/14	
32	Task 32: ATR of Final Report/EA	1 mon	Sun 01/19/14	Mon 01/20/14	
33	Task 33: ATR of Final Report/EA	1 mon	Mon 01/20/14	Tue 01/21/14	
34	Task 34: ATR of Final Report/EA	1 mon	Tue 01/21/14	Wed 01/22/14	
35	Task 35: ATR of Final Report/EA	1 mon	Wed 01/22/14	Thu 01/23/14	
36	Task 36: ATR of Final Report/EA	1 mon	Thu 01/23/14	Fri 01/24/14	
37	Task 37: ATR of Final Report/EA	1 mon	Fri 01/24/14	Sat 01/25/14	
38	Task 38: ATR of Final Report/EA	1 mon	Sat 01/25/14	Sun 01/26/14	
39	Task 39: ATR of Final Report/EA	1 mon	Sun 01/26/14	Mon 01/27/14	
40	Task 40: ATR of Final Report/EA	1 mon	Mon 01/27/14	Tue 01/28/14	
41	Task 41: ATR of Final Report/EA	1 mon	Tue 01/28/14	Wed 01/29/14	
42	Task 42: ATR of Final Report/EA	1 mon	Wed 01/29/14	Thu 01/30/14	
43	Task 43: ATR of Final Report/EA	1 mon	Thu 01/30/14	Fri 01/31/14	
44	Task 44: ATR of Final Report/EA	1 mon	Fri 01/31/14	Sat 02/01/14	
45	Task 45: ATR of Final Report/EA	1 mon	Sat 02/01/14	Sun 02/02/14	
46	Task 46: ATR of Final Report/EA	1 mon	Sun 02/02/14	Mon 02/03/14	
47	Task 47: ATR of Final Report/EA	1 mon	Mon 02/03/14	Tue 02/04/14	
48	Task 48: ATR of Final Report/EA	1 mon	Tue 02/04/14	Wed 02/05/14	
49	Task 49: ATR of Final Report/EA	1 mon	Wed 02/05/14	Thu 02/06/14	
50	Task 50: ATR of Final Report/EA	1 mon	Thu 02/06/14	Fri 02/07/14	

From: MacCracken, James [james_maccracken@fws.gov]
Sent: Monday, July 15, 2013 12:51 PM
To: Floyd, Christopher B POA
Subject: Re: Little Diomedede navigation improvements - Questions for wrapping up EA (UNCLASSIFIED)

Chris:

It's hard to imagine how this project would affect the success of walrus hunters. As noted in the EA, there are other variables that have a greater influence on hunting success than whether the hunters can successfully launch their boats.

Jim

On Mon, Jul 15, 2013 at 9:32 AM, Floyd, Christopher B POA <Christopher.B.Floyd@usace.army.mil> wrote:

Classification: UNCLASSIFIED
Caveats: NONE

Thanks, Jim -

I've attached a copy of the as-yet-unpublished draft EA, as the most handy way of relating the scope of the proposed project.

Chris Floyd
Environmental Resources
U.S Army Corps of Engineers
907-753-2700

-----Original Message-----

From: MacCracken, James [mailto:james_maccracken@fws.gov]
Sent: Monday, July 15, 2013 9:13 AM
To: Floyd, Christopher B POA

Cc: Shannon Torrence; Craig Perham
Subject: Re: Little Diomedede navigation improvements - Questions for wrapping up EA (UNCLASSIFIED)

Chris:

Shannon Torrence cc'd me on this. None of the attachments carried forward, so I'll need some more information on the exact nature of the

project. Walrus hunting success is being driven largely by ice dynamics, storms, and walrus migration patterns. On the surface, I don't think "navigation improvements" alone will have much of an effect on hunting success, but I'll need to know what those improvements are to say for sure.

Jim

--

James G. MacCracken, Ph.D.
US Fish & Wildlife Service
Marine Mammals Management
Walrus Program Supervisor
1011 E. Tudor Rd., MS-341
Anchorage, AK 99503
907-786-3803 office
907-952-3778 cell
907-786-3816 FAX

Classification: UNCLASSIFIED
Caveats: NONE

--

James G. MacCracken, Ph.D.
US Fish & Wildlife Service
Marine Mammals Management
Walrus Program Supervisor
1011 E. Tudor Rd., MS-341
Anchorage, AK 99503
907-786-3803 office
907-952-3778 cell
907-786-3816 FAX



United States Department of the Interior

U.S. FISH AND WILDLIFE SERVICE
Fairbanks Fish and Wildlife Field Office
101 12th Avenue, Box 19, Room 110
Fairbanks, Alaska 99701

June 28, 2013



Mr. Christopher Floyd
U.S. Army Engineer District, Alaska
P.O. BOX 6898
Elmendorf AFB, Alaska 99506-0898

Re: Little Diomedé Navigation
Improvements

Dear Mr. Floyd:

This responds to your request for information concerning endangered and threatened species and critical habitats pursuant to section 7 of the Endangered Species Act of 1973, as amended (Act).

THE PROPOSED ACTION

We understand that the U.S. Army Corps of Engineers (USACE) is proposing to permit a navigation improvement project at the village of Diomedé, on Little Diomedé Island. Currently, four alternatives are being evaluated.

All alternatives would involve barging material to construct small rubble-mound breakwaters on the west side of the island (Figures 1 and 2). Rock placement for the breakwaters would take place when shorefast ice is not present and prior to the onset of heavy autumn storms and arrival of new sea ice, from about 1 July through 1 October. Dredging and possible blasting in an area less than an acre would most likely take place on stable sea-ice from about March through mid-May. If blasting is required, the charge would be small such that it removes a particular rock and did not pose a hazard to the nearby village. During construction, vessel traffic would temporarily increase to include a barge periodically delivering rock, a small survey boat, and possibly a support ship to accommodate work crew lodging. Other equipment would likely include a large excavator working from shore, and possibly a second excavator on the barge to help manipulate the rock.

Polar Bear Minimization Measures

Field crews will incorporate relevant portions of the attached *Polar Bear Interaction Guidelines* into their operational plan. Additionally, a designated person(s) will scan the blast area prior to detonation to confirm no polar bears are in the vicinity. If one or more polar bears are in or adjacent to the blast area, the field crew will wait until no bears are present leave before blasting.

ACTION AREA

The action area includes the western portion of the island and marine environment where direct and indirect effects on listed species may occur. Boating activities consisting of skiffs and umiaqs currently take place in the Action Area. Thus, the Action Area currently experiences disturbance that may influence local distributions of listed species.

EFFECTS OF THE ACTION

Listed Eider Species

The Service listed the Alaska-breeding population of the Steller's eider as threatened on June 11, 1997 (62 FR 31748) and the spectacled eider on May 10, 1993 (58 FR 27474). The proposed project sites are within the migration corridors of these species. Threatened eiders typically migrate north through the Diomedea area en route to their breeding grounds in late April and early May and back south through the area to their wintering grounds anytime from late August to early November.

A few listed eiders may use the waters in the Action Area during migration and could experience disturbance from boating activities. However, we expect eiders to avoid this relatively small area due to ongoing and proposed activities. If eiders are present and are disturbed, they would most likely fly a short distance away and resume previous activities. Thus, we expect the proposed action would have, at most, minor, temporary, and insignificant effects on listed eiders.

Polar Bears

The Service listed the polar bear (*Ursus maritimus*) as a threatened species under the Act on May 15, 2008 (73 FR 28212). Polar bears may occasionally pass/swim through the area, although their density is low and encounters are expected to be infrequent. Transient bears that enter the Action Area could be disturbed by the presence of humans or equipment/vessel noise. We expect disturbances would be minor and temporary because transient bears would be able to respond to human presence or disturbance by departing the area. Furthermore, personnel would follow their polar bear interaction plan should human-polar bear interactions occur.

Because (1) the density of polar bears in the Action Area is low; (2) encounters with polar bears are expected to be infrequent; (3) behavioral effects to transient bears would be minor and temporary; and (4) mitigation measures are included in the interaction plan to minimize potential impacts in the event that transient polar bears are encountered; we expect effects of the proposed action on polar bears would be insignificant.

Pacific Walrus

The Pacific walrus (*Odobenus rosmarus divergens*) can occur in the Action Area and is protected under the Marine Mammal Protection Act. To minimize impacts to this species, please coordinate with Craig Perham (craig_perham@fws.gov, 907-786-3810) and Jim MacCracken (james_maccracken@fws.gov, 907-786-3816) in the Service's Marine Mammal Management office.

CONCLUSION

The proposed action could temporarily disturb listed eiders and polar bears in the project area; however, due to low densities of these species and minimization measures in place, we expect the effects of disturbance to be insignificant. Therefore, the Service determines that the proposed action is not likely to adversely affect listed eiders or polar bears. Preparation of a Biological Assessment or further consultation under Section 7 of the ESA is not necessary at this time. Thank you for the opportunity to comment on this project. If you need further assistance, please contact Shannon Torrence at (907) 455-1871.

Sincerely,

Ted Swem

Ted Swem,
Branch Chief, Endangered Species

Cc: Craig Perham, MMM





Figure 1. Location of proposed project.




Alternative N1.



Alternative S1.



Alternative S2.



Alternative S3.

Figure 2. Four alternatives for the proposed project.

POLAR BEAR INTERACTION GUIDELINES

These Polar Bear Interaction Guidelines (Guidelines) were developed to ensure that activities are conducted in a manner that avoids conflicts between humans and polar bears. Polar bears are protected under the Marine Mammal Protection Act (MMPA), and were listed as a threatened species under the Endangered Species Act (ESA) in 2008. The MMPA and ESA both prohibit the “take” of polar bears without authorization. Take includes disturbance/harassment, as well as physical injury and killing of individuals.

In addition to sea ice, polar bears use marine waters and lands in northern Alaska for resting, feeding, denning, and seasonal movements. They are most likely to be encountered within 25 miles of the coastline, especially along barrier islands during July-October. Polar bears may also be encountered farther inland, especially females during the denning period (October-April). Polar bears may react differently to noise and human presence. The general methods for minimizing human-bear conflicts are to: 1) avoid detection and close encounters; 2) minimize attractants; and 3) recognize and respond appropriately to polar bear behaviors. These Guidelines provide information for avoiding conflicts with polar bears during air, land, or water-based activities.

Unusual sightings or questions/concerns can be referred to: Susanne Miller or Craig Perham, Marine Mammals Management Office (MMM Office), 1-800-362-5148; or to Sarah Conn (907) 456-0499 of the Fairbanks Fish & Wildlife Field Office (FFWFO).

When operating aircraft:

- If a polar bear(s) is encountered, divert flight path to a minimum of 2,000 feet above ground level or ½ mile horizontal distance away from observed bear(s) whenever possible.

When traveling on land, ice, or water:

- Avoid surprising a bear. Be vigilant—especially on barrier islands, in river drainages, along bluff habitat, near whale or other marine mammal carcasses, or in the vicinity of fresh tracks.
- Between October and April special care is needed to avoid disturbance of denning bears. If activities are to take place in that time period the MMM Office should be contacted to determine if any additional mitigation is required. In general, activities are not permitted within one mile of known den sites.
- Avoid carrying bear attractants (such as strongly scented snacks, fish, meat, or dog food) while away from camp; if you must carry attractants away from camp, store foods in air-tight containers or bags to minimize odor transmission until you return them to “bear-resistant” containers.*
- If a polar bear(s) is encountered, remain calm and avoid making sudden movements. Stay downwind if possible to avoid allowing the bear to smell you.

Do not approach polar bears. Allow bears to continue what they were doing before you encountered them. Slowly leave the vicinity if you see signs that you've been detected. Be aware that safe viewing distances will vary with each bear and individual situation. Remember that the closer you are to the animal, the more likely you are to disturb it.

- If a bear detects you, observe its behavior and react appropriately. Polar bears that stop what they are doing to turn their head or sniff the air in your direction have likely become aware of your presence. These animals may exhibit various behaviors:
 - *Curious* polar bears typically move slowly, stopping frequently to sniff the air, moving their heads around to catch a scent, or holding their heads high with ears forward. They may also stand up.
 - *A threatened or agitated* polar bear may huff, snap its jaws together, stare at you (or the object of threat) and lower its head to below shoulder level, pressing its ears back and swaying from side to side. These are signals for you to begin immediate withdrawal by backing away from the bear. If this behavior is ignored, the polar bear may charge. Threatened animals may also retreat.
 - In rare instances you may encounter a *predatory* bear. It may sneak or crawl up on an object it considers prey. It may also approach in a straight line at constant speed without exhibiting curious or threatened behavior. This behavior suggests the bear is about to attack. Standing your ground, grouping together, shouting, and waving your hands may halt the bear's approach.
- If a polar bear approaches and you are in the bear's path—or between a mother and her cubs—get out of the way (without running). If the animal continues to approach, stand your ground. Gather people together in a group and/or hold a jacket over your head to look bigger. Shout or make noise to discourage the approach.
- If a single polar bear attacks, defend yourself by using any deterrents available. If the attack is by a surprised female defending her cubs, remove yourself as a threat to the cubs.

Floyd, Christopher B POA

From: Nichols, Todd F (DFG) [todd.nichols@alaska.gov]
Sent: Monday, January 23, 2012 12:31 PM
To: Floyd, Christopher B POA
Subject: Little Diomedes Small Boat Harbor Breakwaters

Mr Floyd,

ADF&G has reviewed your proposed project alternatives and have found no issues of concern nor preference for any specific alternative.

Todd 'Nik' Nichols

Habitat Biologist

ADF&G Fairbanks

(907) 459-7363

From: [Megan Boldenow@fws.gov](mailto:Megan.Boldenow@fws.gov)
To: [Floyd, Christopher B POA](mailto:Floyd.Christopher.B.POA)
Subject: Re: FW: Little Diomedede correspondence [navigation improvements]
Date: Wednesday, January 04, 2012 12:44:39 PM

Hi, Chris. Great timing! Jewel and I had Little Diomedede on our list of things to discuss this week.

You are correct in identifying oil spills and the potential for introduction of rats to the island as our two primary concerns at Little Diomedede. I've identified some additional concerns that should be discussed in the EA you are drafting. I think these have come out as second tier concerns, once blasting and quarrying were eliminated from the project. (And just to confirm- there won't be any blasting, including for dredging or for leveling an area for placement of infrastructure?)

1. Repeated helicopter disturbance. Seabirds are sensitive to disturbance at their nesting colonies. Helicopters in particular may cause massive fly-off and may impact productivity at nesting colonies, as well as the numbers of birds found on islands in years following repeated helicopter disturbance.

We would like to see the EA discuss the short-term impacts of helicopter traffic related to construction. In order to determine whether the project will introduce increased long-term impacts related to helicopter traffic, the EA should also address current helicopter frequency as well as anticipated, routine helicopter frequency post-heliport construction. A discussion of the present location of the helicopter landing pad/tarmac, relative to the location of breeding birds, versus the location relative to breeding birds after construction would also be useful.

2. Attraction of predators, including arctic fox and gulls, as a result of human activities.

Seabirds generally need predator-free nesting areas, so the EA should consider the potential to increase seabird predators on Little Diomedede. For example, gull numbers increase with access to human waste. This could impact Parakeet Auklets, which are particularly vulnerable to predation by gulls because they do not exhibit mass flight, anti-predator response.

3. Potential for collisions caused by light attraction. Light attraction is particularly a problem for auklets.

Since radiant lights at facilities could be an attractant to birds, especially during periods of inclement weather and/or increasing darkness, shielded lighting will be required at project facilities, to lessen the potential for episodic collision events. Low radiant lighting should be used, and lighting should be directed inward wherever possible so as to prevent "star" effects when viewed offsite. Only lighting necessary for navigational safety should be directed offsite. Anticipated construction and permanent lighting, whether to meet FAA or public safety requirements, should be specified in the EA.

4. Impacts resulting from dredging and placement of fill.

Aside from the potential for direct habitat loss resulting from disturbance to seabird nesting/roosting sites, the project has the potential to impact foraging sites. Insufficient food availability is a threat to seabird populations, and seabirds particularly need access to abundant food supplies near the nesting sites. There has been documentation that seabirds use the breakwater area at Little Diomedede for feeding because of its shallow depths. I believe the planned harbor is located next to the breakwater, and this area would be dredged for barge access. Dredging and the placement of fill should minimize impacts to this potentially important feeding area to the extent practicable. The EA should discuss the potential for impacts to the breakwater area.

We want to note the recommended construction timing window, as identified in our 2008 comment letter: construction and other activities that may potentially result in the take of migratory birds should be prohibited between May 1 and September 30.

We would appreciate an opportunity to review your draft EA, so as to identify any potential issues that we have missed here; and we would be more than happy to meet with you about the project, at the point you think a meeting would be most useful, to discuss the issues identified above or any other questions you might have. Jewel and I may convene a brainstorming session with folks that more regularly deal with seabird issues to make sure that we identify and, to the extent possible, address potential problems. We will additionally be contacting our Migratory Bird office, once we have the opportunity to review the draft, so that we can identify early whether your project will require a permit. You would be more than welcome to be involved in these discussions.

Because previous field work at Little Diomedede focused on proposed quarry sites, we would love to be kept in the loop about any planned site visits. It may be helpful for us to document distance of proposed infrastructure from active colonies.

Thanks for the early opportunity to review the proposed heliport at Little Diomedede. We look forward to continued coordination with you.

Megan

Megan Boldenow
Biological Technician
Conservation Planning Assistance
Fairbanks Fish and Wildlife Field Office
101 12th Ave, Room 114
Fairbanks, AK 99701
907.456.0227

"Floyd, Christopher B POA" <Christopher.B.Floyd@usace.army.mil>

01/03/2012 01:07 PM To
<megan_boldenow@fws.gov>
cc
Subject
FW: Little Diomedede correspondence [navigation improvements]

Hi Megan -

I was trying to remember where you, Jewel Bennett, and I left the FWCA issues on this project...

I'm working on the EA for the latest proposed design. I have the old 1991 FWCA Report and the 2008 Planning Aid Letter for the previous, more ambitious project designs. Those previous correspondences focused mainly on the effects of blasting and quarrying on Little Diomedede Island.

Since the current plan does not involve blasting or quarrying, I've identified USFWS concerns about (a) rats, and (b) fuel spills as the prime remaining issues brought up in previous correspondence with USFWS, and am addressing those in the EA.

Please let me know if USFWS has identified additional issues it would like to address under the FWCA.

Thanks much,

Chris Floyd
Environmental Resources
US Army Corps of Engineers
907-753-2700

-----Original Message-----

From: Jewel_Bennett@fws.gov [mailto:Jewel_Bennett@fws.gov]
Sent: Tuesday, November 08, 2011 11:10 AM
To: Floyd, Christopher B POA
Subject: Re: Little Diomedede correspondence

Chris: Thank you for the reports. I've forwarded them to Megan, who is already digging into the project information. Her email is: megan_boldenow@fws.gov; phone is: 907-456-0227.

Jewel

Jewel Bennett, Chief
Conservation Planning Assistance Branch
Fairbanks Fish and Wildlife Field Office U.S. Fish and Wildlife Service
101 12th Ave., Room 110
Fairbanks, AK 99701
907-456-0324
907-456-0208 fax
Jewel_Bennett@fws.gov

"Floyd, Christopher B POA" <Christopher.B.Floyd@usace.army.mil>

11/08/2011 10:44 AM To
<Jewel_Bennett@fws.gov>
cc
Subject
Little Diomedede correspondence

Hi Jewel -
Attached is the 1991 FWGCAR we discussed.

I've also attached what appears to be an informal field report by Jim Zelenak, probably something he provided to my coworker Chris Hoffman to work into our Feasibility Study Report.

cfloyd
[attachment "1991 FWGCAR.pdf" deleted by Jewel Bennett/R7/FWS/DOI]
[attachment "Little Diomedede Seismic Monitoring June 2007.doc" deleted by Jewel Bennett/R7/FWS/DOI]



REPLY TO
ATTENTION OF:

DEPARTMENT OF THE ARMY
U.S. ARMY ENGINEER DISTRICT, ALASKA
P.O. BOX 6898
ELMENDORF AFB, ALASKA 99506-0898

SEP 23 2009

District Engineer

Mr. Patrick F. Omiak, Sr.,
President
Native Village of Diomedede (Inalik)
P.O. Box 7079
Diomedede, Alaska 99762

Dear President Omiak:

The Alaska District, U.S. Army Corps of Engineers (Corps) is currently studying the feasibility of providing coastal storm damage protection and harbor development at Little Diomedede. We have developed several alternatives to improve small boat and barge navigation. Since we were not able to meet with you as planned on August 20, 2009 due to transportation issues, drawings of the alternatives were provided to Kawerak, Inc. for delivery to the Native Village of Diomedede. The Corps will plan a future meeting to discuss the alternatives and other issues as the study progresses. We want to hear about the tribe's interests and concerns throughout the development of the study. Also, if the study shows that a project is feasible, then there may be future opportunities for the tribe to be involved in planning the storm damage protection and/or harbor development.

Please consider this letter our notification of proposed Department of Defense activity under the Department of Defense American Indian and Alaska Native Policy (please see policies enclosed). If you believe this activity may significantly affect tribal rights and/or protected resources, and you wish to enter into government-to-government consultation on those tribal rights and/or protected resources, please advise me in writing on what tribal rights and/or protected resources you wish to consult about.

If you have any questions, please feel free to contact me or my project manager, Dave Williams at (907) 753-5621 or e-mail: David.P.Williams@usace.army.mil. You may also contact my tribal liaison, Amanda Shearer, at (907) 753-5674 or e-mail: Amanda.M.Shearer@usace.army.mil.

Sincerely,

Reinhard W. Koenig
Colonel, Corps of Engineers
District Commander

CF: Ms. Frances Ozenna, Tribal Administrator



United States Department of the Interior

FISH AND WILDLIFE SERVICE
Fairbanks Fish and Wildlife Field Office
101 12th Avenue, Room 110
Fairbanks, Alaska 99701
June 25, 2008



U.S. Army Corps of Engineers
Attention: Colonel Kevin J. Wilson
District Engineer, Alaska District
Post Office Box 6898
Elmendorf AFB, Alaska 99506-6898

Re: Little Diomed Navigation
Improvement Feasibility Study

Dear Colonel Wilson:

The Service is providing this Planning Aid Letter as agreed to in the FY 2007 Scope of Work for the feasibility study of navigation improvements at Ignaluk, Little Diomed Island, Alaska, and in accordance with the Fish and Wildlife Coordination Act. We describe potential impacts to wildlife and habitats; summarize information from our June 26-30, 2007 site visit and from past seabird studies on Little Diomed; make preliminary recommendations for avoiding or mitigating such impacts; and suggest alternatives for consideration in the Corps' National Environmental Policy Act (NEPA) evaluation.

Background: The Corps' Alaska District previously investigated the feasibility of constructing navigation improvements at Little Diomed and prepared reconnaissance and technical reports in 1982, 1990 and 1994, concluding that improvements were possible and in the interest of the Federal government, but that they were not economically feasible at those times. In 2003, the Corps reinitiated the feasibility study for constructing a protected harbor/barge-landing at Little Diomed. In 2006, the Corps expanded the study to include evaluating the feasibility of constructing a year-round airstrip/harbor/barge-landing in marine waters adjacent to the village using locally-quarried (on-island) materials.

The Service's Migratory Bird Management Office collected field data and prepared reports on breeding seabirds relative to potential material sources on Little Diomed Island identified by the Corps (Fowler 1991, Fowler and Irons 1992). In 1992, the Service prepared a Fish and Wildlife Coordination Act Report that evaluated the potential impacts of two alternative breakwater designs on Little Diomed adjacent to the village of Ignaluk, using locally-quarried materials from three potential sites (McIntosh 1992). The Service also conducted a two-year seabird monitoring program on Little Diomed in 1998-99 (Barnes et al. 1999, Benson et al. 2000). In 2007, the Service accompanied a team from the Alaska District and a geotechnical survey crew to Little Diomed to assess seabird distributions, habitat use and response to seismic tests in two potential quarry sites identified by the Corps adjacent to the village of Ignaluk (Fig. 1).

Threatened and Endangered Species: Little Diomed Island is within the migratory ranges of spectacled and Steller's eiders, both of which are listed as threatened under the Endangered Species Act (ESA). Neither species breeds, molts, or overwinters at Little Diomed, nor are they known to stop-over in the vicinity of the island during migration. Therefore, the Service does not expect project-related activities to adversely impact these listed species.

On May 14, 2008, the polar bear was listed as threatened under the ESA. Polar bears occur in the vicinity of, and have denned on, Little Diomed Island (McIntosh 1992). If this project moves toward construction, the Corps should initiate consultation in accordance with section 7 of the ESA by contacting the Service's Endangered Species Branch (Ted Swem, 907-456-0441). Polar bears also are protected under the Marine Mammal Protection Act (MMPA), and the Service has developed protocols for minimizing bear-human interactions and potential impacts to polar bears. The Corps should consult with the Service's Marine Mammal Management Office (Craig Perham, 907-786-3810) and obtain information prior to commencing project activities to assure they are conducted in compliance with the MMPA.

Potential Impacts to Fish, Wildlife and Habitats: The Service's primary concern with regard to proposed transportation improvement projects at Little Diomed is potential impacts to the island's nesting seabirds. The island provides important breeding habitat for millions of seabirds including auklets, murre, puffins, guillemots, gulls, kittiwakes and cormorants. It supports the largest breeding colonies of least and crested auklets and black-legged kittiwakes in the Alaskan waters of the northern Bering Sea (Sowls et al. 1978, Drury et al. 1981).

Because of the density of breeding auklets and other seabirds on Little Diomed, it would be impossible to develop a quarry on the island without destroying some bird nesting habitat. Also, it is not known if a quarry site on the island could be restored to useful breeding habitat after mining is completed and, if so, to what extent and over what time frame post-mining. If quarrying activities were to be conducted during the breeding season, it would be impossible to avoid taking migratory birds, which is prohibited under the Migratory Bird Treaty Act.

In addition to the direct impact of habitat loss, the indirect impacts of blasting, excavating, material-hauling and other related disturbances could prevent birds from conducting normal breeding activities in areas adjacent to the quarry site. Such activities could: (1) deter pairs from attempting to breed; (2) interrupt incubation; (3) reduce nest and nestling attendance; (4) increase risk of egg and nestling exposure and depredation; and (5) cause panic flights resulting in egg or chick mortality. All these would result in reduced reproductive success, although the geographical extent of such indirect impacts, and their effects on populations, would be difficult to estimate or measure.

In the 1992 Coordination Act Report, the Service evaluated potential impacts of quarry development at three proposed sites: the talus slopes just south of the village of Ignaluk, the beach-rubble shoreline just south of the village, and a rock cliff about one mile south of the village. The jetty construction proposed at that time would have required about 42,000 – 47,000 cubic yards (cy) of material. The Service concluded that the greatest impacts to birds were associated with the talus slope, but that adverse impacts were also likely at the beach-rubble site.

Quarrying at the rock cliff site was thought to have the least potential for adverse impacts, and the greatest potential for effective mitigation.

The Corps estimates the currently-proposed year-round airstrip would require 1,000,000 cy of material; more than 20 times the volume previously evaluated. This proposal has the potential for much greater adverse impacts to breeding seabirds and their nesting habitats than previously evaluated transportation improvements. However, the size of the quarry needed to provide this amount of material has not been calculated, so a quantitative assessment of impacts is not possible at this time. One of the two areas currently proposed as potential material sources encompasses the talus slope and beach-rubble shoreline south of the village; the other includes the talus slope and shoreline immediately north of the village. Birds most likely to be impacted in these areas are least, crested and parakeet auklets, horned puffins and pigeon guillemots. The cliffs south of the village are not currently being considered as a material source.

In addition to the direct and indirect effects of quarry development and construction, the proposed project could have other impacts on nesting seabirds and other wildlife that should be evaluated during the Corps' NEPA review. These include increased disturbance to nesting and foraging birds and marine mammals associated with increased boat, barge and air traffic; the increased risk of oil or fuels spills; the potential for introducing invasive species of plants or animals; alteration of nearshore currents and its effects on marine nutrient upwelling and transport; and impacts to marine benthic communities of the increased footprint and greater depth (up to 40 feet) at which fill would be placed (compared to previously evaluated transportation improvements at Little Diomedé).

Of these, the Service is most concerned about the potential for increased boat and barge traffic to result in the introduction of rodents to Little Diomedé Island. Introduced rodents, particularly Norway rats, are causing significant wildlife and habitat damage on island ecosystems in Alaska, especially in the Aleutians, where such introductions are known on at least 12 large islands (over 2,740 acres in size) and on dozens of smaller islands in the Aleutian Archipelago. Little Diomedé's seabird nesting colonies could be decimated rapidly if rats were to be introduced and become established on the island. The large equipment that would need to be brought to the island for mining could also transport non-native or invasive plant seeds or parts, which could adversely affect native vegetation and seabird nesting habitats.

It should be recognized that construction of the airstrip/harbor/barge-landing, combined with the climate-mediated extension of the ice-free season and increased interest in oil and gas exploration and development in the Chukchi and Beaufort seas, may result in a significant increase in the volume of marine traffic at Little Diomedé. It is possible that the island's harbor may become a major stopover site for oil and gas and other transport vessels, or a potential place of refuge for vessels in distress. This increase in marine traffic could increase the risk of oil or fuel spills, and it could impact birds, marine mammals and subsistence activities. Increased boat and barge traffic would also increase the likelihood of introducing marine invasive species – either through fouled hulls or release of ballast waters. Invasive species could alter the marine food web, including benthic communities, which could affect many species of seabirds as well as marine mammals.

June 2007 Site Visit: Kirsten Bixler, from the Service's Migratory Bird Management Office, and Jim Zelenak, from the Fairbanks Field Office, accompanied Corps staff and geotechnical survey contractors to Little Diomed June 26-30, 2007. Although the FY 2007 Scope of Work allowed for 10 days of on-island work, the crew was stranded for four days in Nome due to poor weather and left the island early due to schedule conflicts with the transport vessel, the MV Peregrine. The crew arrived at Little Diomed on the evening of the 26th and departed the island on the morning of the 30th. Due to the shortened schedule, bird work focused on monitoring bird response to seismic tests, qualitatively assessing bird abundance, distribution and habitat use in the two areas proposed for quarry development, and conducting counts from a Zodiac offshore.

The seismic crew detonated four blasts in the potential quarry site south of the village of Ignaluk – two in the evening on the 27th, and two in the late morning on the 29th. Monitoring details are provided in Attachment 1, and video of bird response to seismic blasts is provided on the accompanying disc. In summary, the blasts on the 27th were detonated when most auklets were away from the island, feeding at sea, which occurred daily during this visit from about 3:00 p.m. to 9:00 p.m. Very few auklets were present on the talus slopes at the time of the first blasts. On the 29th, the blasts were detonated when thousands of auklets were present on the slopes, and the response was dramatic. Most birds within approximately 500 meters of the blast site, some 10,000 or more auklets, flew from the slope in a panic flight. A few birds returned to the slope within one minute, most within 3-5 minutes, and after 10 minutes, bird numbers and activity on the rocks appeared to return to the pre-blast condition. Despite the apparent rapid return to pre-blast conditions, the disturbance to the birds was obvious, and repeated blasts and other disturbances associated with mining material for the proposed project could, if conducted during the breeding season, cause substantial adverse impacts to nesting seabirds.

The qualitative assessment of bird distribution and habitat use is based on observations during foot surveys conducted at two elevations through each potential quarry area and during seismic monitoring efforts. As expected, in both the north and south quarry areas, auklet density was greatest on rocky substrates and lowest in vegetated areas, with very few birds observed in grassy areas. Smaller patches of boulders surrounded by vegetation appeared to be used more by least auklets where rocks were small and by parakeet auklets where rocks were larger. In general, the amount of rocky substrate and, therefore, the number of auklets, was higher in the southern quarry site.

Boat surveys also indicated that more birds used the lower slope and shoreline of the south quarry site than the north (150-200 pigeon guillemots and 120-140 black-legged kittiwakes at the south site vs. 5 guillemots and 5-15 kittiwakes at the north site). Kittiwakes were associated with the southern end of the south quarry area, in close proximity to the cliffs just to the south of the quarry area. Smaller numbers of horned and tufted puffins and pelagic cormorants also were observed near the south end of the southern quarry site, and several common murrelets were observed on or over the water adjacent to the north quarry site.

Recommendations: The proposed transportation improvement project has the potential to adversely impact wildlife in the vicinity of Little Diomed, particularly the island's important breeding seabird colonies. The Service offers the following recommendations for avoiding, minimizing and mitigating these potential impacts:

1. The Corps should continue to evaluate alternate off-island material sources. The most significant impacts of the proposed project would be avoided if materials could be brought in from an existing permitted source or from a new source in a less biologically important area.
2. If alternate, off-island material sources are not feasible, the Corps should consider obtaining materials from the rocky cliffs to the south of the south quarry area. Fewer birds use the cliffs, and careful blasting and mining during the non-breeding season would avoid direct impacts to nesting seabirds and would have a higher likelihood of resulting in useful habitat, post-mining (i.e., the cliffs could be blasted to mimic existing features like ledges).
3. Regardless of location, if an on-island material source is used, blasting or other mining or construction activities that may potentially result in the take of migratory birds should be prohibited between May 1 and September 30.
4. Prior to construction, the Corps and its contractors should consult with the U.S Fish and Wildlife Service to develop a mining reclamation and monitoring plan. The goal will be to restore areas impacted by mining and project construction, by matching contours and habitat features (e.g., slope; size and distribution of rocks, etc.), to maximize the likelihood that they will return to useful nesting habitats in the future. Monitoring bird use and productivity will be critical to determining the success of these mitigation efforts.
5. The Corps and its contractors must take every possible precaution to prevent the introduction of invasive species of plants or animals to Little Diomedé Island and surrounding marine waters. Particular care should be given to prevent rat introduction and establishment on the island. New State of Alaska wildlife regulations regarding rats became effective on September 13, 2007. These regulations make it illegal to knowingly or unknowingly harbor or release rats. It also requires boaters, shippers and others moving containers that may contain rats to be vigilant in checking for rats and in taking action to control or eradicate rats where they are found. An overview of these new regulations is found at: http://www.adfg.state.ak.us/special/invasive/new_regs07.php. Fritts (2007) includes a more comprehensive listing of Alaska laws related to rats and rodents in Appendix G, and provides recommendations for rat prevention and control. (http://www.adfg.state.ak.us/special/invasive/documents/invasive_rodent_plan.pdf). Other useful information may be obtained at the U.S. Fish and Wildlife Service's Invasive Species web site (<http://www.fws.gov/invasives/>) and at the *Hazard Analysis and Critical Control Point (HACCP) Planning for Natural Resource Management* web site (<http://www.haccp-nrm.org/>).
6. The Corps should evaluate potential impacts of increased boat, barge and air traffic on breeding seabirds, marine mammals, oil or fuel spill-potential, and the subsistence activities of the village of Ignaluk.

Conclusion: The Service believes the proposed project has the potential to significantly impact breeding seabirds on Little Diomedede, but that most impacts could be avoided or minimized by carefully selecting the most appropriate material source, implementing seasonal restrictions on mining and construction activities, and incorporating mitigation in the mining plan. These measures, combined with strictly enforced requirements to prevent introduction of invasive species, particularly rats, should reduce the likelihood of significant adverse impacts. Monitoring of areas disturbed by mining should be a priority to determine the effectiveness of mitigation efforts and to evaluate the long-term consequences of the project, if any, on seabird use and productivity.

These comments are submitted in accordance with provisions of the Endangered Species Act of 1973 (87 Stat. 844) and the Fish and Wildlife Coordination Act (48 Stat. 401, as amended: 16 U.S.C. 661 et seq.) and constitute the report of the Department of the Interior.

We appreciate this opportunity to comment. Please contact Jim Zelenak (907-456-0354 or jim_zelenak@fws.gov) if you have questions or need additional information regarding these comments.

Sincerely,



Larry K. Bright
Branch Chief,
Conservation Planning Assistance

JRZ/jrz

References

- Barnes, L. J., J. B. Benoit and D. B. Irons. 1999. Populations and productivity of seabirds on Little Diomedede, Alaska, 1998. Unpubl. Rep., U.S. Fish and Wildlife Service, Migratory Bird Management Office, Anchorage, AK.
- Benson, J. E., L. M. Greffenius and D. B. Irons. 2000. Seabird monitoring at Little Diomedede Island, Alaska in 1999. Unpubl. Rep., U.S. Fish and Wildlife Service, Migratory Bird Management Office, Anchorage, AK.
- Drury, W. H., C. Ramsdell and J. B. French. 1981. Ecological studies in the Bering Strait region. Pages 175-487 in: Final reports of principal investigators, Environmental Assessment of the Alaskan Continental Shelf, Biological Studies Vol. 11, NOAA-BLM, Juneau, AK.

- Fowler, A. C. 1991. Seabird use at proposed quarry sites, Little Diomedes Island, Alaska. Unpubl. rep., U.S. Fish and Wildlife Service, Migratory Bird Management Office, Marine and Coastal Bird Project, Anchorage, AK.
- Fowler, A. C. and D. B. Irons. 1992. Populations and productivity of seabirds on Little Diomedes Island. Unpubl. rep., U.S. Fish and Wildlife Service, Migratory Bird Management Office, Marine and Coastal Bird Project, Anchorage, AK.
- Fritts, E. I. 2007. Wildlife and People at Risk: A Plan to Keep Rats out of Alaska. Alaska Department of Fish and Game. Juneau, Alaska. 190 pp.
http://www.adfg.state.ak.us/special/invasive/documents/invasive_rodent_plan.pdf
- McIntosh, E. W. 1992. Navigation Improvement Project, Little Diomedes Island, Alaska, Fish and Wildlife Coordination Act Report. U.S. Fish and Wildlife Service, Ecological Services, Fairbanks, AK.
- Sowls, A. L., S. A. Hatch and C. J. Lensink. 1978. Catalog of Alaskan Seabird Colonies. USDOI Fish and Wildlife Service, FWS/OBS-78/78.