

Date	Permit Number / Waterway	Type	Permittee	Permit Description and Action
5-Oct-11	POA-2011-443_Sagavanirktok River	Permit	Northern Construction and Maintenance LLC	Discharge approximately 32,000 cubic yards of clean earthen materials (sand/gravel) onto a 3.85-acre trapezoidal area.
6-Oct-11	POA-2011-465_Tongass Narrows	Permit	Mr. Dale Collins	Placement of 3600 cubic yards (cy) of shot rock and 167 cy of rip rap material into 0.27 -acre of waters of the U.S. (wetlands) to construct three residential homes.
7-Oct-11	POA-2011-285_Eva Creek	Permit	Golden Valley Electric Association / Greg Wyman	Authorize permanent impacts to 13.45 acres of jurisdictional waters including wetlands and temporary impacts to 5.25 acres of jurisdictional waters including wetlands for construction of the Eva Creek Wind Energy Project.
7-Oct-11	POA-2011-321_Smith Creek	Permit	NANA Regional Corporation	Place 7,500 cubic yards (cy) of fill material to construct a 180-foot by 260-foot building pad, 4.5 feet thick. Up to 6,200 cubic yards of fill would be placed in wetlands adjacent to Smith Creek. The pad would support a structure to consolidate local offices. A garage and generator shed would also be constructed. All work will be performed in accordance with the attached plan, sheets 1-3, dated April 2011.
13-Oct-11	POA-2009-402_Behm Canal	Permit	Southern SE Alaska Emergency Training Center	Mechanically clear and place 1,536 cubic yards of fill material into 3.77-acres of waters of the U.S., including wetlands to construct an emergency training center.
13-Oct-11	POA-2011-623_Tongass Narrows	Letter of Permission	Mr. Steve Seley Jr.	Place the following structures below the mean high water mark of Tongass Narrows: 1) a boat drive down ramp consisting of four 10-foot by 25-foot wood floats supported by four 18-inch galvanized steel piles; 2) a 12-foot by 75-foot mooring float supported by one 18-inch galvanized steel pile; 3) an 85-foot by 16-foot drive down barge ramp that includes an 80-foot by 40-foot float and a dolphin with three 18-inch galvanized steel piles; and 4) the removal of four steel and two creosote piles that will be replaced by six 18-inch galvanized steel piles
14-Oct-11	POA-2011-973_Lake Clark	Letter of Permission	Samaritan's Purse	Install new floating docks at the Samaritan's Purse camp for wounded military personnel.

18-Oct-11	POA-1983-31-M7_Yukon River	Permit Modification	Sweetsir Construction	Remove gravel during winter months from an exposed gravel bar in an area 1,500 feet wide by 9,000 feet long. The gravel is located below the ordinary high water (OHW) mark of the Yukon River. First, snow and ice will be cleared using a bulldozer and loader. The gravel will then be excavated, loaded into dump trucks, and hauled % mile to an upland stockpile site. Up to 250,000 cubic yards of material per year will be mined and stockpiled.
24-Oct-11	POA 2011 297_Six Mile Lake	Permit	City of Nondalton	Discharge 6,850 cubic yards of fill material into 1.73 acres of wetlands to construct: • A 960-foot long by 40-foot wide access road; • A 75-foot by 85-foot water storage tank road; • A 910-foot long by 25-foot wide water line trench;
26-Oct-11	POA-2011-489_Diamond Creek	Permit	Kenai Peninsula Borough	Discharge 22,924 cubic yards of pit-run gravel fill on geotextile fabric into 2.4 acres of wetlands to construct two roads (West Access Road and Loop Road), commercial scales and a staging area associated with the conversion of the Homer Baling/Landfill Facility into a solid waste transfer facility. Six 18" diameter 40-50' long culverts will be installed in wetlands to maintain hydrology.
26-Oct-11	POA-1988-735-M5_Iliuliuk Harbor	Permit Modification	Unisea, Inc. Attention: Mr. Art Aliment	This is the 5th modification of the original permit. Special permit condition number 4, attached to modification POA-1988-735-M4, is modified as follows: 4. All construction work shall be conducted within the timing window that extends from April 15 to October 30 of the calendar year.
26-Oct-11	POA-2000-1015-M3_Zimovia Strait	Permit Modification	Mr. David and Ms. Paula Rak	This is the third modification of the original permit. The permit is hereby modified as follows: The time limit for completing the work authorized ends on October 31, 2016. If you find that you need more time to complete the
27-Oct-11	POA-2011-103_Hastings Creek	Permit	Northcoast Construction	Expand an existing gravel mining area on a 43-acre Mineral Survey (MS) tract. The project will directly impact 16.99 acres of wetlands, of which 10.51 acres will be stripped and excavated in order to access the gravel resource. The remaining 6.48 acres will be used to stockpile 26,000 cubic yards of overburden. Portions of the excavated area may also be used as temporary material stockpile areas and to set up a pit floor for a rock crushing plant.